

KAISER HILL COMPANY


ACCELERATED ACTION DESIGN FOR THE ORIGINAL LANDFILL ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

GEOTECHNICAL INVESTIGATION PHASE 3 STABILITY ANALYSIS TECHNICAL SUPPORT MEMORANDUM

Project No. 57378.6020 December 2004



A **TYCO** INTERNATIONAL LTD. COMPAN'





ACCELERATED ACTION DESIGN FOR THE ORIGINAL LANDFILL ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

GEOTECHNICAL INVESTIGATION PHASE 3 STABILITY ANALYSIS TECHNICAL SUPPORT MEMORANDUM

Prepared for: Kaiser-Hill Company, L.L.C. Golden, Colorado

Prepared by:
Earth Tech, Inc.
Englewood, Colorado

Project No. 57378.6020

November 2004

TABLE OF CONTENTS

<u>Section</u> <u>Pag</u>			
LIST	Γ OF FIGURES	ii	
LIST	Γ OF APPENDICES	ii	
EXE	CUTIVE SUMMARY	ES-1	
1.0	INTRODUCTION		
	1.1 PURPOSE		
	1.2 SITE DESCRIPTION AND PROJECT ALTERNATIVES	1-1	
	1.3 SUPPORTING INVESTIGATIONS	1-2	
2.0	FIELD AND LABORATORY INVESTIGATIONS	2-1	
	2.1 EXPLORATION BOREHOLES AND TEST PITS		
	2.2 GEOTECHNICAL LABORATORY TESTING	2-2	
3.0	SITE CONDITIONS	3-1	
	3.1 REGIONAL GEOLOGIC AND SEISMIC SETTING	3-1	
	3.1.1 Geologic Setting		
	3.1.2 Seismic Sources and Historic Seismicity		
	3.2 SITE GEOLOGIC CONDITIONS		
	3.3 GROUNDWATER CONDITIONS		
	3.4 LANDSLIDING		
•	3.5 SEISMIC SHAKING		
4.0	GEOTECHNICAL MATERIAL PROPERTIES		
	4.1 GENERAL MATERIALS CHARACTERIZATION		
	4.1.1 Waste and Other Fill	4-1	
	4.1.2 Rocky Flats Alluvium		
	4.1.3 Colluvium and Weathered Claystone	4-2	
	4.1.4 Unweathered Claystone		
	4.3 SEISMIC STRENGTH CONSIDERATIONS		
- 0			
5.0	STABILITY ANALYSIS		
	5.1 CRITERIA		
	5.1.1 Static Stability		
	5.2 BASIS OF ANALYSIS		
	5.3 CONDITIONS ANALYZED		
	5.4 METHODOLOGY		
•	5.5 RESULTS		
	5.6 OBSERVATIONS AND CONCLUSIONS		
٠.	5.7 CONCEPTUAL ACCELERATED ACTION DESIGN		
6.0	REFERENCES	6-1	

LIST OF FIGURES

<u>Figure No.</u>	<u>Title</u>
1	Geotechnical Investigation Sampling Locations
2	Triaxial Shear Test Data - Drained Strength - Maximum Stress Ratio
3	Triaxial Shear Test Data - Drained Strength - 5 Percent Strain
4	Direct Shear Test Data - Drained Strength - Peak and Residual
5	Triaxial Shear Test Data - Undrained Strength - Maximum Stress Ratio
6	Triaxial Shear Test Data - Undrained Strength - 5 Percent Strain
7	Stability Analyses Results – M&E Section B-B'
8	Stability Analyses Results – M&E Section C-C'
9	Stability Analyses Results – M&E Section D-D'

LIST OF APPENDICES

<u>Appendix</u>	<u>Title</u>
A	Borehole and Test Pit Logs
В	Geotechnical Laboratory Test Data
C	Geologic Map and Cross Sections
D	Groundwater Modeling Input
E	Stability Analyses
F	Deformation Analysis

EXECUTIVE SUMARY

The purpose of this memorandum is to provide geotechnical input to support design of the accelerated action alternative at the Original Landfill (OLF) at the U.S. Department of Energy's Rocky Flats Environmental Technology Site (RFETS). The primary purpose and focus of the geotechnical investigation has been to develop geotechnical data and perform engineering analyses to a level adequate to support final design of the accelerated action. This has culminated with Phase 3 of the investigation, primarily consisting of the stability analysis of the OLF site with various accelerated action alternatives.

The Phase 2b field investigation work, conducted in June and July 2004, included both drilling and test pit exploration with associated sampling of subsurface materials for geotechnical laboratory testing. It was conducted for the primary purpose of obtaining additional data regarding the properties of the weaker colluvium/slide and weathered claystone bedrock materials underlying the site and controlling the landfill stability. This data, in combination with existing data from previous site investigation work, provides the basis for stability analyses (Phase 3) to support the final accelerated action design.

In support of the current project efforts, a comprehensive hydrogeologic model has been developed for Kaiser-Hill Company by Integrated Hydro Systems, LLC, based on the groundwater monitoring wells and geotechnical borings throughout the RFETS area. Input from this model was used in assigning groundwater levels used in the landfill slope stability analysis for specific geologic cross sections analyzed.

Existing data from previous site investigation work was used to support seismic stability evaluations. Both probabilistic and deterministic site-specific seismic shaking hazards were studied as part of the 1994 work by Risk Engineering. For this OLF Phase 3 evaluation, a value of 0.12g is established for the peak bedrock acceleration when proceeding with methods for the seismic slope stability analyses, and the mean magnitude earthquake of 5.9, for an RMA/Derby source, is established for use in deformation analyses. Detailed explanation of selected

Accelerated Action Design for the Original Landfill
Rocky Flats Environmental Technology Site
Geotechnical Investigation
Golden, Colorado

procedures and methodology for seismic stability evaluation, including deformation analysis, is provided in this report.

Significant laboratory strength testing of samples of the critical weaker colluvium and weathered claystone bedrock materials provided the primary basis for selecting parameters of these materials for use in the stability analysis. The approach used in selecting these critical materials strength parameters was to assign a lower bound value for all test data within the stress range involved in the analysis for various potential sliding surfaces. Drained strength, appropriate for use in long term static stability analysis, was assigned a design envelope with a 20 degree friction angle. Undrained strength, applied in pseudostatic seismic stability analysis, was assigned a design envelop with a 15 degree friction angle.

Static stability under long-term, steady state conditions, is required to achieve a minimum static safety factor of 1.5. This criteria is typical for earthfill embankments and is required by most agencies and design guidelines, and it is also used for solid waste landfills.

The minimum required pseudostatic safety factor is 1.0 using a seismic coefficient of one half the peak horizontal bedrock acceleration, or 0.06g for the case of the OLF. Seismically-induced permanent displacement shall be less than 12 inches, the generally accepted standard of practice for landfill covers, for the selected design earthquake event, should the pseudostatic safety factor be less than 1.0.

The results of computer-aided stability runs for the various combinations of three critical and representative geologic cross sections, established soil and bedrock density and strength parameters, three geometric conditions, circular arc and sliding block potential failure mechanism searches, and two different groundwater conditions, for both static and seismic conditions, are provided on key summary figures, and show:

• All cases analyzed for existing topographic conditions have safety factor results equal to or less than 1.5 for static analysis and less than 1.0 for pseudostatic analysis.

- All cases analyzed for an overall 18 percent regrade condition have safety factor results ranging from 1.5 to 1.7 for static analysis and less than 1.0 for pseudostatic analysis.
- All cases analyzed for an overall 18 percent regrade condition have estimated maximum seismically induced permanent displacement results ranging from 5 to 10 inches.
- A surficial stability check of anticipated cover materials indicates that static and pseudostatic safety factors for saturated slope conditions are acceptable.

Some final observations and conclusions regarding aspects of this investigation that are considered conservative to the results of the stability analysis and design of the accelerated action are as follows:

- Strength parameters used for the critical materials controlling stability results are conservative lower bound values of all test data within the anticipated stress range.
- The highest groundwater condition analyzed in combination with seismic loading is quite conservative, as the likelihood of both these conditions occurring simultaneously is low.
- The overall 18 percent regrade design slope is conceptual in nature. Further refinement of this regraded slope with further consideration given to surface water management, groundwater elevations, and bedrock elevations will improve stability issues.

As a result of the data presented and reviewed in this report, the results of static and seismic stability analyses, and past design experience, it is concluded that no stability enhancement beyond slope regrading is required to meet established design criteria for the accelerated action at the OLF.



1.0 INTRODUCTION

The following sections present information regarding the purpose of this memorandum and the supporting field investigation and engineering analysis. This section also presents site background information and details past investigation efforts.

1.1 PURPOSE

The purpose of this memorandum is to provide geotechnical input to support design of the accelerated action alternative at the Original Landfill (OLF) at the U.S. Department of Energy's Rocky Flats Environmental Technology Site (RFETS).

This document is prepared for Kaiser-Hill Company, LLC, and summarizes the results of Earth Tech Phase 2 and Phase 3 geotechnical investigation activities for accelerated action design. Phase 1 and preliminary Phase 2 work was documented in memoranda dated April 26 and July 27, 2004, respectively. This submittal includes supplementary field exploration and laboratory testing data (Phase 2 investigation), as well as geotechnical engineering analyses and conclusions (Phase 3 investigation), in support of the accelerated action design.

The primary purpose and focus of the geotechnical investigation has been to develop geotechnical data and perform engineering analyses to a level adequate to support final design of the accelerated action. This has culminated with Phase 3 of the investigation, primarily consisting of the stability analysis of the OLF site with various accelerated action alternatives.

1.2 SITE DESCRIPTION AND PROJECT ALTERNATIVES

The OLF site is located south of RFETS Buildings 440 and 460, along the north hillside of a ravine in the Woman Creek drainage area, extending from approximate Elevation 6,040 feet at the top to Elevation 5,950 feet at its base. The OLF site footprint has a maximum length along the east-west direction of approximately 1,700 feet, and approximately 500 feet in the north-south direction, with an approximate area on the order of 20 acres. Existing slope gradients range from approximately flatter than 6 to 1 (horizontal to vertical) to 2 to 1, with a total slope height from the top of the hillside to the Woman Creek drainage of about 90 feet.

Relative to the specific OLF area of the RFETS, and the associated geotechnical investigation directed toward the Phase 3 stability analysis of the site, aspects of the accelerated action project alternatives involving the landfill area slope and conditions controlling its stability are as follows:

- No action for the landfill, only industrial area regrading (existing topographic conditions for stability analysis).
- Overall 18 percent regraded landfill slope with 2-foot soil cover and drainage improvements (18 percent regrade condition for stability evaluation).
- Landfill slope regrade with buttress at toe for stability enhancement (18 percent regrade with buttress condition for stability evaluation).

A fourth alternative adds an uphill groundwater cutoff wall. Since groundwater modeling has indicated that a cutoff would have relatively minor impact in lowering groundwater levels in the landfill slope and enhancing stability, this was not translated to an additional alternative for stability evaluation.

1.3 SUPPORTING INVESTIGATIONS

The relevant geotechnical and geologic investigations, both previous and current, that were conducted at or adjacent to the RFETS OLF and support this memorandum, are as follows:

- Metcalf & Eddy (M&E) 1995 exploration of the OLF, which reviewed historic air photographs of fill placement (early 1950s to late 1980s), and included drilling and geologic logging of 20 exploratory borings and collecting suitable soil samples for conducting geotechnical laboratory testing, and presenting findings for evaluating causes and extent of landsliding at the site. Depth of borings typically ranged from approximately 30 feet (namely, a few feet into the unweathered bedrock formation) to 150 feet.
- Earth Tech 2002 exploration at the top of the OLF slope into the Rocky Flats Alluvium, including 13 exploratory borings located approximately parallel and at a distance of nearly 100 feet north of the OLF, on the alignment of a potential groundwater diversion system. Exploration included both auger and rock core drilling to depths of 50 to 80 feet and soil/rock sampling, and classification, index, and engineering properties testing in the laboratory.
- Earth Tech 2004 supplemental exploration of the OLF, in support of the accelerated action design and focused on investigating the weaker subsurface materials controlling

landfill stability (Phase 2b investigation). Exploration included drilling and geologic logging of 11 borings to depths of 42 feet, and excavating and logging 6 test pits.

- Geomatrix Consultants/Risk Engineering 1994 evaluation of subsurface soils conditions at the top of the Rocky Flats Alluvium, including review and summary of available geotechnical data at 60 locations, including a total of approximately 150 borings within the RFETS, including 22 previous soil investigation reports for individual buildings, six geophysical reports, four seismic hazard/risk and geologic investigation reports, and one groundwater monitoring report.
- Risk Engineering 1995 comprehensive evaluation of earthquake sources in the vicinity of the RFETS. Work was performed by a team of consultants and members of academia lead by Risk Engineering (Geomatrix Consultants, EQE International [Dr. K.W. Campbell], University of Utah [Dr. W.J. Arabasz], Stanford University [Dr. A. Cornell], Dr. G.A. Bollinger, 1994), including a state-of-the-art seismic hazard study. Previous geologic and seismicity studies had been conducted by Blume (1974), TERA (1976), Dames and Moore (1981) and Ebasco (1992).

2.0 FIELD AND LABORATORY INVESTIGATIONS

The most recent geotechnical field and laboratory investigation programs undertaken at the original landfill were for the primary purpose of obtaining additional data regarding the properties of the weaker colluvium/slide and weathered claystone bedrock materials underlying the site and controlling the landfill stability. This data, in combination with existing data from previous site investigation work, provides the basis for stability analyses to support the final design of the accelerated action. The investigation activities were conducted in accordance with the Phase 2b Field and Laboratory Investigation Plan dated June 2004.

2.1 EXPLORATION BOREHOLES AND TEST PITS

The Phase 2b field investigation work, conducted in June and July 2004, included both drilling and test pit exploration with associated sampling of subsurface materials for geotechnical laboratory testing. A focused drilling program was directed toward undisturbed sampling of the weaker subsurface materials susceptible to, or currently involved in, instability, including primarily the colluvium/slide and weathered claystone bedrock materials. Limited test pitting by backhoe excavation at strategic locations was directed toward obtaining a visual look at the colluvium/slide interface with the weathered claystone bedrock surface, and sampling of these weaker subsurface materials as appropriate.

Exploration and sampling locations are shown on Figure 1. Borehole and test pit logs are provided in Appendix A.

Listed below is a summary of the drilling and test pit work:

- Drilling and test pit exploration activities occurred between June 18 and July 14, 2004.
- Exploration boreholes, including some adjacent offset holes for additional sampling or due to difficult drilling conditions, were drilled at or near the 10 locations identified in the investigation work plan (Figure 1). One additional hole was drilled in the vicinity of Test Pit No. TP-5.
- Borehole depths ranged from 14 to 42 feet.
- All boreholes were advanced through the weathered claystone bedrock materials and terminated in relatively unweathered claystone bedrock.

- Undisturbed samples were retrieved during the drilling operations from the various material types encountered, focusing on the colluvium and weathered claystone bedrock materials.
- Continuous dry core was retrieved from all boreholes and saved in core boxes for visual observation.
- Exploration test pits were excavated at or near the 6 locations identified in the investigation work plan (Figure 1).
- Test pits typically ranged from 10 to 15 feet in depth.
- The weathered claystone bedrock material was intercepted in 5 of the 6 test pits, and sampled in 4 of the test pits (Test Pit Nos. 1, 3, 4, and 6).

Field exploration findings are summarized as follows:

- No significant unanticipated conditions were encountered during the Phase 2b field investigation work, relative to conditions anticipated from familiarity with previous site exploration data.
- The field exploration encountered all material types anticipated, including fill, colluvium, valley fill alluvium, severely weathered claystone, moderately weathered claystone, and unweathered claystone. These material types and depths at which they were encountered match up well with the findings from previous site exploration.
- The most critical colluvium/slide and severely weathered claystone bedrock materials were encountered at most of the exploration locations.
- The most unanticipated finding was localized soft, fine-grained alluvial material encountered at one exploration location below the base of the landfill, at Borehole No. BH-9.

2.2 GEOTECHNICAL LABORATORY TESTING

Review of the undisturbed samples and core retrieved during the Phase 2b field exploration work, and formulation of the geotechnical laboratory testing program, occurred between July 12 and 15, 2004. This process included detailed evaluation and selection of samples and procedures for the testing program, including careful review of field data and logs, and visual review of the drilling core and undisturbed samples retrieved for potential testing. This activity involved discussion between the geotechnical engineer and field geologist, and a meeting and review of representative samples for testing between the geotechnical engineer and laboratory testing staff.

The primary focus of the Phase 2b laboratory testing program was the determination of strength of the weaker colluvium/slide and weathered claystone bedrock materials underlying the site and controlling the landfill stability. A range of index properties tests was also performed on selected samples for classification, characterization, and confirmation of field logging. Based on the sample review and testing program formulation process described above, the most critical and also representative samples available were selected for testing.

Listed below are the test procedures and numbers of tests performed for the Phase 2b laboratory investigation:

- Moisture Content (ASTM D2216) 8 (additional tests part of other engineering properties tests)
- Density (ASTM D2937) 8 (additional tests part of other engineering properties tests)
- Particle Size Analysis (ASTM D422) 23
- Atterberg Limits (ASTM D4318) 17
- Consolidation (ASTM D2435) 4
- Direct Shear (ASTM D3080) 27 points
- Consolidated Undrained Triaxial Strength ICU (ASTM D4767) 33 points

For the direct shear strength tests specified, 15 points were run on severely weathered claystone materials, 6 points were run on moderately weathered claystone materials, and 6 points were run on colluvium materials. For the triaxial strength tests specified, 18 points were run on severely weathered claystone materials, 6 points were run on moderately weathered claystone materials, 6 points were run on colluvium materials, and 3 points were run on fine grained alluvium materials.

The laboratory testing program described above was completed in September 2004. All Phase 2b geotechnical laboratory test data is provided in a separate volume to this memorandum, referenced in Appendix B.

3.0 SITE CONDITIONS

The following section details regional geologic and seismic conditions, site geologic conditions, site groundwater conditions, landsliding issues, and anticipated seismic shaking. Information from each of these conditions is incorporated into subsequent stability analyses.

3.1 REGIONAL GEOLOGIC AND SEISMIC SETTING

The regional geologic and seismic setting surrounding the OLF are presented in the following section.

3.1.1 Geologic Setting

The OLF is located on the south side of the RFETS, which is in turn located on the western edge of the Colorado Piedmont section of the Great Plains Physiographic Province (Hunt, 1974). The piedmont slopes eastward and is incised by drainages flowing from the Front Range into the Great Plains. The Rocky Flats was formed by erosion of Cretaceous-age (Arapahoe and Laramie) bedrock formations, and subsequent deposition of the Pleistocene Rocky Flats Alluvium atop the resulting eroded surface. The claystone bedrock slopes below the rocky surface were exposed by continued stream erosion through the pediment. Landsliding on these slopes probably commenced at about the middle Pleistocene, shortly after the slopes were initially exposed (Shroba and Carrara, 1994). A more detailed description of the regional geologic history and setting is presented in the Geologic Characterization Report for RFETS (EG&G, 1995).

As described in previous RFETS geologic and seismologic reports (Blume, 1974; Ebasco, 1992; Risk Engineering/Geomatrix, 1994), in general, the lithologic column includes the following:

- Rocky Flats Alluvium, consisting of fan deposits of early Pleistocene age (1 to 2.5 million years) is derived from the Front Range. These deposits are predominantly of bouldery and cobbley, silty, clayey, and sandy gravel nature, ranging in thickness from less than 1 foot to over 100 feet, and averaging 10 feet. Rocky Flats Alluvium is underlain by sedimentary bedrock.
- Sedimentary Bedrock of Cretaceous age (65 to 135 million years) of the Arapahoe Formation, Laramie Formation, and Fox Hill Sandstone, and Pierre Shale, in descending order, which at the RFETS dips generally 1 to 5 degrees to the east, with local variations of up to 20 degrees. The uppermost unit, the Arapahoe Formation is approximately 120 feet thick and consists of claystone with interbedded sandstone and siltstone. The

Laramie Formation consists of clayey shale, sandy shale and claystone, and is approximately 600 to 800 feet thick. The Fox Hill Sandstone is approximately 100 feet thick. The Pierre Shale is approximately 8,000 feet thick.

• Crystalline Bedrock, underlying sedimentary units at the site, at a depth on the order of 10,000 to 13,000 feet.

3.1.2 Seismic Sources and Historic Seismicity

A state-of-the-art evaluation of earthquake sources in the vicinity of the RFETS was performed by a team of consultants and members of academia lead by Risk Engineering (1994), and some of their findings and conclusions are summarized below:

Primary seismic sources that were identified (Risk Engineering Table 2-1 and Figure 2-3) include the following faults, all located within 25 kilometers of the site:

- Golden-Boulder Fault, maximum magnitude 7 to 7-1/2,
- Valmont Fault, magnitude 5-3/4 to 6-3/4
- Walnut Creek Fault, magnitude 5-3/4 to 6-3/4 and
- Rock Creek Fault, magnitude 5-3/4 to 6-3/4

Five areal seismic sources were identified (Risk Engineering Figure 2-2), as follows:

- Denver Basin Regional Source I, with maximum magnitudes from 5-1/2 to 7 or 5-1/2 to 6, depending whether or not the 1882 Colorado earthquake occurred within this regional source
- Eastern Rocky Mountains Regional Source II with maximum magnitudes from 5-1/2 to 7 or 5-1/2 to 6-1/2, depending whether or not the 1882 Colorado earthquake occurred within this regional source
- Western Colorado/Rio Grande Rift Source Regional Source III with maximum magnitudes from 6-1/2 to.7-1/2
- Great Plain Sources Regional Sources IV and V, with maximum magnitudes from 5-1/2 to 6

The areal sources represent the occurrence of earthquakes which could not be associated with a specific fault.

An additional seismic source was associated with deep-well waste fluid injection, as follows:

 Rocky Mountain Arsenal (RMA)/Derby located approximately 15 to 25 kilometers east of the Rocky Flats, which could generate maximum magnitude earthquakes of 5-1/2 to 7.

The 1994 Risk Engineering study included a comprehensive review of historical records, to provide a data base for statistical evaluation, including pre-instrumental shocks in Colorado, such as the Maximum Historic 1882 Colorado earthquake with an assigned, estimated moment magnitude of 6.4 ± 0.3 . However, there is uncertainty as to the source location of this historic event.

The translation of this historic seismic data to selection of a design seismic event is discussed later in this Section 3.

3.2 SITE GEOLOGIC CONDITIONS

As described in the 1995 M&E report, the Original Landfill is located in the Buffer Zone to the south of Building 440 and 460, on the south facing slope, between the edge of the Rocky Flats alluvial terrace and Woman Creek. It is reported, based on review of historic air photographs, that placement of fill commenced during the early 1950s and continued at least into the late 1980s, with much of the waste fill apparently dumped off the edge of the flat alluvial terrace, onto the slope and intermixed with native Rocky Flats alluvium and colluvial materials.

Areal distribution of the surficial geologic units is shown on Figure 2 of the 1995 M&E geotechnical/geologic investigation report, which is reproduced in Appendix C of this memorandum (Figure C1). In addition, Figures 4 through 10 of the M&E report include geologic cross sections A-A' through G-G' showing interpreted surface and subsurface soil and bedrock conditions, which are also included in Appendix C of this memorandum (Figure C2 through C8). Results of the supplementary (Phase 2b) geotechnical field exploration at the site appear to generally confirm subsurface soil conditions depicted by the 1995 M&E report. Phase 2b exploratory borings and test pits (included in Appendix A of this memorandum) were added to the 1995 M&E cross sections (Appendix C).

A brief description of the site geologic units is as follows:

Waste Fill: Waste fill predominantly consists of sandy and clayey gravel and cobbles (GC) derived from colluvial and Rocky Flats alluvial materials that were mixed with varying concentrations of waste from historical RFETS production activities. It was estimated that the ratio of volume of soils to waste is on the order of 2 to 1, or about 67 percent soil to 33 percent waste. The observed waste included sheet metal, wood, broken glass, plastic, rubber, metal shavings, glass, solid blocks of graphite and graphite sand, concrete, asphalt and portions of 55-gallon steel drums. The fill generally varies from loose to medium dense, generally dry to moist, although occasionally wet when underlain by an impervious material. Waste fill ranged in thickness at boring locations from approximately 2 to 11 feet, although it may locally be as thick as 15 to 20 feet, as shown on interpreted geologic sections. Further, it is anticipated that after potential slope regrading and capping of the original landfill site, some sections may locally include on the order of 25 feet of waste and other fill.

<u>Clean Fill</u>: Clean fill soils were locally found under the road located immediately south of the south interceptor ditch (SID), and as relatively thin cover (generally less than 10 feet in thickness) related to the construction of the buried outfall pipe over the northeastern portion of the OLF, as shown on cross section D-D', E-E', and G-G' (Appendix C).

Colluvium (Qc): These deposits vary from sandy, clayey gravel and cobbles (derived from the Rocky Flats Alluvium) to sandy clay (GC to CL), and are located on slope areas below the Rocky Flats Alluvium. Colluvial materials have reportedly (M&E, 1995) been mobilized by several instances of landsliding, and apparently have slid atop the weathered bedrock, as well as have been incorporated within deeper seated slides.

The coarser-grained colluvium is generally medium dense, while the finer-grained colluvium varies from stiff to medium stiff, although looser, softer and wet colluvium was occasionally encountered during the 1995 M&E exploration. Colluvium ranged in thickness at boring locations from approximately 1 to 13 feet, although it may locally be as thick as 15 feet or slightly thicker, as shown on interpreted geologic section G-G' (Appendix C).

Rocky Flats Alluvium (Qrf): These pediment/fan deposits which comprise the flat alluvial surface of Rocky Flats were generally dense, sandy, clayey gravel with cobbles (GP, GC), with

occasional interbedded layers of stiff to hard clays and sandy clays (CL, CH) as well as fine, medium dense to very dense clean and clayey sands (SP, SC). Alluvial materials have reportedly (M&E, 1995) ranged in thickness at boring locations at the top of the slope, from approximately 30 to nearly 50 feet, and generally above Elevation 5,995 feet to 6,010 feet, as shown on interpreted geologic sections A-A' through F-F' (Appendix C).

Geomatrix (1994) conducted a fairly comprehensive characterization of this alluvium with the purpose of evaluating its susceptibility to liquefaction (if any) based on numerous available geotechnical studies previously conducted at the Rocky Flats (namely, field exploration and laboratory test data). Of the 327 soil samples and penetration resistance measurements, roughly speaking one third corresponded to clayey materials (CL), one third in sandy materials (SC, SM), and the other third in gravelly materials (GC, GM). It was concluded that the clayey materials were generally very stiff, and that the sandy and gravelly materials were medium dense to very dense. Geomatrix also reported average groundwater levels within the Rocky Flats Alluvium of 5 to 10 feet below ground surface. Woodward-Clyde Consultants (WCC, 1986) similarly reported groundwater depths of 7 to 15 feet in 5 of 10 exploratory borings. Groundwater within the Rocky Flats Alluvium is interpreted to be perched within the varied and individual layers of more pervious sands or gravel above clay layers or the claystone bedrock.

<u>Valley Fill Alluvium (Qal)</u>: These deposits encountered along Woman Creek vary from medium dense to dense, sandy, silty-clayey gravel with cobbles (GP, GM-GC). Alluvial materials have reportedly (M&E, 1995) ranged in thickness at boring locations at the toe of the slope, from approximately 5 to 7 feet, as shown on interpreted geologic sections A-A' through F-F' (Appendix C). Groundwater in alluvium was found as shallow as 2 feet.

Claystone: The bedrock underlying the OLF predominantly consists of Laramie Formation claystone, with subordinate beds of siltstone and sandstone. Under the landfill, this formation is relatively flat-lying (i.e., near horizontally bedded), and for engineering property evaluation purposes it was characterized, depending on the degree of weathering, as "severely weathered" (sw), "moderately weathered" (mw), or "unweathered" (uw), as part the 1995 M&E investigation. This characterization was adopted by this geotechnical investigation and is summarized as follows:

- <u>Severely Weathered Claystone (CSsw)</u>, which represents bedrock that is weathered to the extent that the original rock texture and structure (e.g., bedding, fracturing) is no longer recognizable. This material generally consists of moist to wet, stiff to very stiff (occasionally medium stiff), lean to fat clay, and ranged in thickness at exploration locations from less than 0.5 to 4 feet.
- Moderately Weathered Claystone (CSmw), which represents bedrock that ranges from highly weathered (but showing some discernable structure with typical iron oxide staining) to slightly weathered (nearly fresh, but showing some occasional iron staining). Moderately weathered claystone is usually friable (locally plastic) and soft, typically damp to moist, and of hard consistency, and moderately to highly plastic. Bedding and fracturing (jointing) ranges from massive (without recognizable bedding structure, unfractured) to thinly laminated (parallel bedding surfaces spaced at less than about 0.1 inch) and/or intensely fractured, interbedded with thin laminae of silt and very fine sand. The thickness of the moderately weathered claystone ranged from approximately 2 to 23 feet.
- <u>Unweathered Clavstone (CSuw)</u>, which represents bedrock that completely lacks iron staining, and represents rock that has little or no hydraulic connection with surficial water. (i.e., water in the upper hydrostratigraphic unit). The strength, hardness, and fracturing characteristics of the unweathered claystone were generally comparable to those of the moderately weathered claystone, although somewhat drier (ranging from damp to dry) and harder to drill. Depth to the top of unweathered claystone was interpreted to range from a minimum of approximately 15 to 20 feet at the toe of the slope to about 50 feet under the Rocky Flats Alluvium, as shown on M&E Sections A-A' through F-F' (Appendix C).

3.3 GROUNDWATER CONDITIONS

The 1995 M&E report concluded that, based on examination of 62 shallow groundwater monitoring wells and geotechnical borings, most groundwater in the study area appears to be perched atop bedrock, within the deeper portions of colluvium and fill overlying bedrock. The source of most groundwater was interpreted to be within the lower portion of the Rocky Flats Alluvium, penetrating the colluvium and/or fill surficial deposits. Based on the previous groundwater level measurements, the shallow groundwater appeared to concentrate in the lower portion of the surficial deposits, and flow downslope near parallel to the ground and bedrock surfaces, as shown on M&E geologic cross sections (Appendix C).

More recently, in support of the current project efforts, a comprehensive hydrogeologic model has been developed for Kaiser-Hill Company by Integrated Hydro Systems, LLC, based on the groundwater monitoring wells and geotechnical borings throughout the RFETS area. The results

of this hydrogeologic model are the subject of a separate technical support memorandum. Input from the model used in assigning groundwater levels used in the landfill slope stability analysis, for the geologic cross sections analyzed, is included in Appendix D of this memorandum.

In general, groundwater was found to approximately follow the shape of the top of the weathered claystone bedrock profile and to be located within the lower portion of colluvium and fill surficial deposits. When compared to the existing landfill ground surface slope, the groundwater surface was found to locally reach depths of less than 10 feet.

When compared to the alternative regraded slope configuration, modeled groundwater depths for a typical year climate condition are generally 5 to 10 feet below regraded ground surface or greater, with localized areas less than 5 feet. For a wet season climate condition, modeled groundwater was observed to rise. The modeled groundwater elevations used in the slope stability evaluation were those for a mean annual wet-year groundwater level, and a maximum annual wet-year groundwater level. The modeled groundwater profiles representing these two conditions, for the three cross sections evaluated (cross sections B, C and D), are shown in Appendix D.

As summarized previously, Geomatrix Consultants (1994) also reported average groundwater levels within the Rocky Flats Alluvium of 5 to 10 feet below ground surface. Woodward-Clyde Consultants (WCC, 1986) similarly reported groundwater depths of 7 to 15 feet in 5 of 10 exploratory borings. Groundwater within the Rocky Flats Alluvium is interpreted to be perched within the varied and individual layers of more pervious sands or gravel above clay layers or the claystone bedrock.

3.4 LANDSLIDING

The project site area is generally shown as having some potential for landsliding based on preliminary U.S. Geological Survey maps of landslide deposits of the Denver Quadrangle and the Louisville Quadrangle compiled by Colton and Holligan (1975 and 1977, respectively). Colton and Holligan define landslide deposits as masses of earth and rock that have moved downslope as earthflows and slumps that have formed along gravel-capped mesas where springs and seeps have saturated the underlying shaley or clayey parts of the Pierre Shale, the Laramie

Formation, and the Arapahoe Formation (all Upper Cretaceous). In addition, Colton and Holligan also define areas susceptible to landsliding as general slopes steeper than 10 percent, because slopes of only a few degrees on saturated shale have failed. Conversely, slopes steeper than 10 percent that are underlain by sandstone units of the Fox Hill Sandstone (Upper Cretaceous) and the lower part of the Laramie Formation are generally not susceptible to large slope failures.

Landsliding of these slopes probably commenced at about the middle Pleistocene, shortly after the slopes were initially exposed (Shroba and Carrara, 1994). The 1995 M&E geotechnical/geologic investigation concentrated in understanding the potential for landsliding at the site, and included a detailed review of available geologic data and airphoto interpretation, geologic mapping, and exploratory drilling. The geologic map and cross sections developed by this previous investigation, depicting the evidence of previous landsliding, are reproduced in Appendix C of this technical memorandum for reference.

It should also be noted that water from the RFETS facilities was periodically drained on to the landfill area slopes by a ditch (covered prior to 1983) and an outfall pipe constructed in 1983, which likely caused episodes of sliding from 1983 to 1986, after which the outfall pipe was replaced by a buried outfall pipe that drains southeast into the south interceptor ditch (SID).

3.5 SEISMIC SHAKING

Both probabilistic and deterministic site specific seismic shaking hazards were studied as part of the 1994 work by Risk Engineering. The probabilistic approach was used in subsequent calculations, according to federal regulation requirements for landfill cover design, supplemented with deterministic analyses for computation of seismically-induced permanent displacements of slopes, as part of the stability evaluation for this investigation.

Probabilistic analyses integrate overall earthquake magnitudes and locations to calculate a combined frequency of exceeding various ground motion levels. Conversely, deterministic analyses are based on the concept of a single design event. The dominant earthquake may be chosen as the mean magnitude and distance that caused a ground motion level to be exceeded at the chosen return period.

The dominant seismic source used for deterministic seismic hazard evaluations was a recognizable seismic source that generally dominates earthquake hazard at the RFETS, namely the RMA/Derby, with a mean magnitude of 5.9 and distance of 27 kilometers, resulting in a peak horizontal acceleration in rock of approximately 0.083g (as summarized in Risk Engineering Tables J-3, J-4 and Figures J-15 through J-18). This event was established for permanent slope deformation analysis evaluations for this OLF Phase 3 evaluation.

Further, these analyses were performed for both "rock" and "soil" site conditions. A firm rock profile is defined as corresponding to an average shear wave velocity in the top 100 feet of at least 2,500 feet per second. Peak horizontal acceleration in rock evaluated by Risk Engineering as part of the seismic shaking hazard study for an earthquake event having a median value with 2 percent probability of exceedance in 50 years, which is the regulatory standard, was calculated to be slightly greater than 0.10g. U.S. Geologic Survey maps show a peak horizontal bedrock acceleration value of approximately 0.12g, for the same probability of exceedance.

The project site is in a zone of fairly low potential for major seismic activity. However, the appropriate seismic potential and shaking hazards need to be recognized and accounted for in the accelerated action design. The above seismic shaking evaluation methods, including the selected seismic shaking input criteria, is detailed in subsequent discussions related to the landfill slope potential deformation evaluation, as part of the overall stability analysis.

For this OLF Phase 3 evaluation, a value of 0.12g is established for the peak bedrock acceleration when proceeding with methods for the seismic slope stability analyses, and a design earthquake with a mean magnitude of 5.9 is established for use in the deformation analyses. Further details related to the seismic stability and deformation analyses are described in Section 5 of this report.

4.0 GEOTECHNICAL MATERIAL PROPERTIES

This section details the material properties for the soil and bedrock materials evaluated in the geotechnical evaluation. It includes material characteristics of waste and other fill, Rocky Flats, Alluvium, colluvium and weathered claystone, and unweathered claystone. This section also includes discussions on critical material strengths and seismic strength considerations.

4.1 GENERAL MATERIALS CHARACTERIZATION

The evaluation of the various geologic units made during field investigation, including air photograph interpretation, geologic mapping, logging of exploratory boreholes and test pits, penetration testing, coring, and sampling, was supplemented with geotechnical laboratory testing, including classification, index, and engineering properties testing on selected soil and weathered bedrock samples. Material property profiles versus depth, based on data from the 2004 and 2002 Earth Tech investigations as well as the 1995 M&E investigation, were utilized for general characterization and evaluation of material properties variation. Observations from this data evaluation are discussed in the following sections for general materials characterization.

4.1.1 Waste and Other Fill

Waste fill materials are known to include significant amounts of Rocky Flats Alluvium (possibly as much as 67 percent), construction debris, and other materials. They exhibit blow counts on the order 10 to more than 50 blows per foot (bpf), but most commonly in the range of 10 to 35, and are therefore considered loose to medium dense. Clean fill (used for road and outfall pipe backfill) was not specifically targeted during this investigation, but it is anticipated to range medium dense to very dense.

4.1.2 Rocky Flats Alluvium

Geomatrix Consultants (1994) discussed the clayey, sandy, and gravelly/cobbley nature of this alluvium. Blow counts in the clayey materials average 28 ± 14 bpf, although several blow counts were cut off at 30 to 50 blows, and, therefore, the reported average blow count value is considered conservative. Blow counts within the sandy materials averaged 38 ± 14 bpf, and, similarly cut off at 50 blows, the reported average blow count value is considered conservative. Blow counts within the gravelly materials averaged 41 ± 13 bpf and, similarly cut off at 50

blows, the reported average blow count value is considered conservative. Based on Geomatrix Consultants evaluation of soil penetration resistance, it is concluded that the clayey (CL, CH) materials are generally very stiff, and that the sandy (SM, SC) and gravelly (GP, GM, GC) materials are medium dense to very dense.

4.1.3 Colluvium and Weathered Claystone

These materials exhibit Plastic Limit (PL) values ranging from approximately 15 to 20 and Liquid Limit (LL) values ranging from approximately 36 to nearly 80, with resulting Plasticity Index (PI) values ranging from roughly 20 to nearly 60. These soils typically classify as fat clay (CH) and less frequently as lean clay (CL), and in the case of the colluvium, they contain sand and gravel in various fractions. The coarse-grained fraction (sands, gravels, and cobbles), are usually less than 20 percent, but occasionally as high as 60 percent.

The bottom of these materials is highlighted by a significant contrast of soil penetration resistance between surficial materials (waste, clean fill, colluvium, and severely weathered claystone) versus the moderately weathered to unweathered claystone bedrock formation, indicating a significant improvement of engineering properties (compressive and shear strength increase, and reduction in compressibility), for materials encountered below the more highly weathered bedrock material. This depth is variable, but is typically about 30 to 35 feet below the existing slope ground surface.

In-place moisture contents and dry unit weights in colluvium were found to typically vary from 15 to 35 percent and 100 ± 10 pounds per cubic foot (pcf), respectively. When comparing in-place moisture contents with PL and LL values, it is apparent that in-place moisture contents are somewhat higher than the PL, with liquidity indices on the order of 0 to 0.3, suggesting a slightly overconsolidated colluvial material (possibly the result of clay desiccation). Unconfined compressive strength in the colluvium usually varied from approximately 1 to 2.5 tons per square foot (tsf), although values as low as 0.7 tsf and higher than 4.5 tsf were occasionally measured.

Four consolidation tests performed on severely weathered claystone (CSsw) suggested over consolidation ratios approximately in the range of 1.5 to 3.5.

4.1.4 Unweathered Claystone

In-place moisture contents were found to typically range from 5 to 25 percent (or about 10 percent less than overlying materials). When comparing in-place moisture contents with PL and LL values (essentially in the same general range of those for the overlying colluvium and weathered claystone), it is apparent that in-place moisture contents are usually less than, or about equal to PL values. Consequently, liquidity indices were commonly less than zero, indicating their overconsolidated nature (namely, stronger and less compressible engineering characteristics). Consistent with the latter comparison, unconfined compressive strength in moderately weathered to unweathered claystone usually varied from approximately 10 to 25 tsf, although values as low as 5 tsf and higher than 35 tsf were occasionally reported.

4.2 CRITICAL MATERIAL STRENGTH

As discussed previously, the primary focus of the most recent Phase 2b field and laboratory investigations has been to obtain additional data regarding the properties, primarily engineering strength, of the weaker colluvium/slide and weathered claystone bedrock materials underlying the OLF site and controlling the landfill stability. The numbers and types of strength tests performed, as well as on which type of material the various tests were conducted, was summarized in Section 2.2. The results of all the strength testing performed for the Phase 2b investigation are provided and summarized on Figures 2 through 6. For each type of strength test result, the data for all tests on colluvium/slide and weathered claystone materials is compiled on one figure, for summarization and comparison purposes.

Figures 2 and 3 present triaxial shear test, drained strength test data, which is appropriate for use in long term static stability analysis. Figures 5 and 6 present triaxial shear test, undrained strength test data, from the same strength tests on the various samples listed, which is appropriate for use in short-term loading conditions, such as seismic shaking. Figure 4 presents both peak and residual strength test data from direct shear testing, according to the method providing primarily drained strength results.

The difference between the two triaxial drained strength test data summaries, Figures 2 and 3, and between the two triaxial undrained strength test data summaries, Figures 5 and 6, is the

presentation of the data according to a couple of different, commonly selected sample failure criteria. Figures 2 and 5 present strength data based on a maximum principal stress ratio sample failure criteria. Figures 3 and 6 present strength data based on a 5 percent strain sample failure criteria. The summaries indicate that the results are very much the same for the two different criteria.

A lower bound strength envelope for all Phase 2b investigation tested colluvium/slide and weathered claystone critical materials is superimposed on the test data summaries for both drained, effective stress strength (Figures 2, 3, and 4) and undrained, total stress strength (Figures 5 and 6), respectively.

When reviewing Figures 2, 3, 5, and 6, it can be seen that the laboratory samples demonstrated a significant cohesion value that contributes to the overall material strength. Figure 2 shows cohesion ranging from 200 pounds/square foot (psf) to 600 psf with an average of 410 psf; Figure 3 shows 150 psf to 700 psf with an average of 425 psf; Figure 5 shows 150 psf to 600 psf with an average of 420 psf; and Figure 6 shows 100 psf to 800 psf with an average of 510 psf. The lower bound strength envelope, which is superimposed on each figure, as a conservative approach, represents zero cohesion and a low enough friction angle such that all strength values within the anticipated stress range are above this lower bound.

4.3 SEISMIC STRENGTH CONSIDERATIONS

Beyond the undrained strength properties determined from the strength tests discussed above, assessment of potential loss of undrained strength as a result of seismic ground shaking is another important consideration for the stability evaluation of the landfill slope. In general, materials underlying the OLF at the RFETS are not expected to be susceptible to significant pore water pressure buildup during seismic loading, or exposed to drastic reduction in cyclic shear strength during cycling loading from seismic shaking. A summary of material properties that lead to indicate their cyclic strength behavior is provided below.

Fill materials, when compacted would not be susceptible to a significant loss of strength, whether or not they are of a cohesive nature. Uncompacted fill, such as the OLF waste mixed with significant amounts of Rocky Flats Alluvium, although it would generally not be as dense as in

its natural condition, contains significant amounts of clay, and thus is not expected to lose significant amounts of strength during shaking. It is possible, however, that localized pockets, where uncompacted cohesionless granular material may have become saturated, could be adversely affected by seismic shaking. Even in this case, the situation would be considered to have limited lateral extent and thickness and would not be anticipated to constitute a generalized condition under significant portions of the landfill site.

Rocky Flats Alluvium underlying the upper portions of the OLF slope, while containing a significant fraction of granular materials, are fairly dense, and also include a clay matrix that significantly reduces, if not completely eliminates, the potential for a rapid increase in pore water pressure due to cyclic loading. This is consistent with the findings of Geomatrix Consultants (1994), indicating that sandy and gravelly fractions were generally dense, with blow counts on the order of 38 ± 14 bpf and 41 ± 13 bpf, respectively. Similarly, clayey soil fractions were very stiff with blow counts on the order of 28 ± 14 bpf.

Colluvial materials, which contain significant amounts of cohesive soils (clay) and claystone bedrock materials, are highly cohesive and very stiff to hard, and therefore are not anticipated to be prone to a significant amount of pore water pressure buildup and loss of shear strength during seismic shaking.

As a result of these soil and bedrock physical properties, the seismic stability evaluation discussed in the next section, which uses undrained strength properties for the critical clay type colluvium/slide and weathered claystone bedrock materials, is considered to be based on conservative analysis parameters.

5.0 STABILITY ANALYSIS

This section discusses the basis, results, observations, and conclusions of the stability analyses performed to support design of the OLF accelerated action. Two primary components of the analyses are associated with static long-term loading conditions and potential seismic short-term loading conditions applied to the landfill slope. These two different aspects of stability are addressed throughout the various discussions for this section. The key bases and results of the entire stability analyses are provided on Figures 7, 8, and 9. Supporting results from computer-aided analyses of static and pseudostatic methods for all cases and conditions analyzed, as summarized on Figures 7, 8, and 9, are provided in Appendix E. Deformation analysis methods, performed as part of the seismic stability analysis, are discussed in detail in Appendix F.

5.1 CRITERIA

Criteria for the static stability analysis and seismic stability analysis are presented in the following sections. This includes regulatory guidance for seismic evaluation procedures.

5.1.1 Static Stability

Static stability under long-term, steady state conditions, evaluated in general accordance with conventional two-dimensional limit equilibrium analysis, is required to achieve a minimum static safety factor of 1.5. This value is typical of earthfill embankments and is required by most agencies and design guidelines, and it is also used for solid waste landfills.

5.1.2 Seismic Stability

Generally acceptable methods of slope stability analysis for assessing the seismic stability of earthfills, including in highly seismic areas of the western United States, are summarized below. These procedures are described in guidelines implemented by several state agencies (i.e., California Division of Mines and Geology [CDMG], 1997). In recent years, these procedures were extended to solid waste landfill structures once appropriate parameters for the analysis of landfills were developed (Kavazanjian, 2002; Bray, 1995).

• The pseudostatic stability analysis is a method that may be used in conjunction with a predetermined horizontal seismic coefficient. The seismic coefficient results in an "equivalent" static horizontal acceleration at the center of gravity of a potential sliding earthfill mass in a conventional limit-equilibrium analysis. This is the simplest approach to a dynamic slope stability calculation, and is one of the most often used in current practice and is generally considered to be a conservative approach.

Although there is no specific guidance regarding the selection of seismic coefficients in pseudostatic analyses for solid waste landfills, pseudostatic slope stability analysis is often performed using a seismic coefficient estimated from procedures developed for earth embankments.

A range of seismic coefficients and pseudostatic factors of safety, that have been used in engineering practice and referenced in the literature for earthfill structures, generally fall within a trapezoidal area as shown on Figure 1 of CDMG (1997) guidelines (reproduce as Figure F1 in Appendix F of this report), for jurisdictions where pseudostatic coefficients have not been adopted by the lead agency. This figure presents a summary of the recommended values of the seismic coefficient for the ranges of factor of safety and earthquake parameters presented in publications by Seed (1979) and Hynes & Franklin (1984). Seismic coefficients as high as one half of the peak horizontal acceleration in rock have been used, in combination with pseudostatic factors of safety of 1.0 to 1.15 for earth structures.

It is also noted that a pseudostatic analysis is not considered necessary in cases where the static factor of safety is at least 1.7 for earthfill structures (Hynes and Franklin, 1984).

• A simplified seismically-induced permanent displacement analysis of earthfill slopes, which includes design chart solutions, such as those proposed by Makdisi and Seed (1978), based on previous work by Newmark (1965), is a secondary method used in seismic stability analysis when pseudostatic analysis is an inadequate model.

The original Newmark procedure involves calculation of the yield acceleration, defined as the inertial force required to cause the static factor of safety to reach 1.0 from the traditional limit-equilibrium pseudostatic analysis. The procedure uses a design earthquake strong motion record and calculates cumulative displacements above the yield acceleration.

Makdisi and Seed's procedure seeks to define seismic embankment stability in terms of acceptable deformation in lieu of conventional factors of safety, using a modified Newmark analysis. This method presents a rational approach to determine the yield acceleration, including dynamic characteristics and deformability of the fill slopes, and average acceleration of the potential sliding mass. Design curves are used to estimate the permanent earthquake-induced deformations of embankments 100 to 200 feet high, based on previous well-documented cases analyzed by more sophisticated techniques. These methods have been applied to solid waste landfills and highway embankments.

Additional details of the Makdisi and Seed procedure, which has been selected for the seismic analysis of the OLF, have been summarized in Appendix F of this report.

Further work on amplification or deamplification of acceleration potential of landfills was conducted Bray et al. (1998), by including not only the effect of the fundamental period and dynamic parameters of solid waste landfills in the evaluation of the maximum horizontal acceleration, but also the predominant period of the rock motion.

• More complex deformation analyses include numerical methods, such as the use of dynamic finite elements (such as QUAD4) or finite difference mathematical models, or one-dimensional (such as SHAKE) analyses, for selected acceleration time histories. These more complex analyses have been used in highly seismic areas of the western United States for structures that pose high risk to human life and property, where the above indicated "simplified" procedures (pseudostatic analysis, simplified displacement analysis) were either not applicable or did not yield conclusive results. This last category of analysis methods is not considered necessary for the OLF site.

In addition to selection of the appropriate sophistication level of the above standard methods being part of the analysis criteria, regulatory requirements and guidelines also can control analysis criteria. As summarized in Earth Tech's memorandum dated May 26, 2004 (Slope Stability Evaluation – Seismic Issues), State of Colorado hazardous waste regulations (Colorado Code of Regulations [CCR] 1007-3) and solid waste regulations (Colorado Code of Regulations [CCR] 1007-2) are generally silent regarding the seismic stability evaluation and design of landfills. These regulations are consistent with the Code of Federal Regulations (CFR) for Hazardous Wastes 40 CFR Parts 258 and 260-279.

Though there are no specific guidelines regarding the seismic analysis of the landfills at RFETS, the following paragraphs summarize examples of seismic design guidelines that have been developed for high-risk structures such as dams.

- The Colorado rules and regulations for dam safety and dam construction state:
 - 1. The minimum acceptable pseudo-static stability analysis factor of safety is 1.0, and shall be attainable using a pseudo-static load coefficient of one-half the predicted peak bedrock acceleration (g's), but not less than 0.05.
 - 2. For those Class I dams, and large and intermediate Class II dams, for which a pseudo-static analysis is not appropriate, as determined by Rule 5.A. (6)(j)(IV), a deformational analysis shall be performed in a manner acceptable to the State

Engineer. The freeboard remaining due to deformation of the dam shall not be less than three feet.

- USCOLD (1999) states that "If the embankment or the foundation materials are not susceptible to [significant] loss of strength or stiffness [i.e., liquefaction], and if the level of ground motion to be considered does not exceed 0.40g to 0.50g, then simplified methods may be sufficient to estimate the permanent deformations potentially induced by the ground motion."
- Utah (2002) states that "For a maximum acceleration of 0.2g or less, or a maximum acceleration of 0.35g or less if the embankment consists of clay on clay or bedrock foundation, a pseudostatic coefficient which is at least 50 percent of the maximum peak bedrock acceleration at the site should be used in the stability analysis. The minimum factor of safety in an analysis should be 1.0." If the ground shaking noted above is exceeded: "a deformation and settlement analysis should be performed to estimate anticipated total crest movement."
- Washington (1993) notes that seismic analyses are not required if all of the following are met: "1) The dam is well-built (densely compacted) and peak accelerations are 0.2g or less, or the dam is constructed of clay soils, is on clay or rock foundations and peak accelerations are 0.35g or less; 2) The slopes of the dam are 3 horizontal to 1 vertical or flatter; 3) The static factors of safety of the critical failure surfaces involving the crest are greater than 1.5 under loading conditions expected prior to an earthquake; and 4) The freeboard at the time of the earthquake is a minimum of 2 to 3 percent of the embankment height (not less than 3 feet)".
- State of California (Department of Conservation, Division of Mines and Geology) Special Publication 117: Guidelines for Mitigating Seismic Hazards in California, refers the selection of the Seismic Coefficient to research by the U.S. Army Corps of Engineers (Miscellaneous Paper: GL-84-13: "Rationalizing the Seismic Coefficient Method," authored by Hynes and Franklin, 1984) which provided amplification factors to be used when considering the crest of an embankment in comparison with amplifications at the base, with the intention of identifying those embankments which could be expected to experience unacceptable deformations. They suggested using one-half the bedrock acceleration applied to the embankment crest with an acceptable factor of safety greater than 1.0, and limited the assessment to earthquakes of less than magnitude 8 with nonliquefiable materials comprising the embankment. A reduction on material static undrained shear strengths up to 20 percent may be applicable depending on the nature and cyclic behavior of soils.

It should be noted that the above-listed requirements pertain to high risk dam structures whose failure could result in immediate loss of human life and/or significant property damage. The RFETS OLF is not this type of high risk structure.

Considering the project site setting, geologic conditions, standard of practice, and regulatory requirements, the following seismic stability analysis criteria were adopted for the OLF site:

- Minimum required pseudostatic safety factor of 1.0 using a seismic coefficient of one half the peak horizontal bedrock acceleration. For the case of the OLF, one-half of the peak horizontal bedrock acceleration represents 0.06g.
- Seismically-induced permanent displacement less than 12 inches, the generally accepted standard of practice for landfill covers, for the selected design earthquake event, should the pseudostatic safety factor be less than 1.0.

5.2 BASIS OF ANALYSIS

The Phase 3 stability analysis was performed on the following bases:

- Use of existing geologic cross sections from the M&E report. The most critical section through the landfill is not obvious; analyses were performed on the three existing cross sections encompassing the waste and past slide materials across the entire hillside slope which are believed to bracket the typical and most critical stability conditions (M&E geologic cross sections B-B', C-C', and D-D').
- Use of density and strength material parameters established on Figures 7, 8, and 9. Material properties were selected based on Phase 2b field and laboratory geotechnical data collected as part of this investigation (Figures 2 through 6, Appendices A and B), supplemented by the results of previous investigations at the project site by Metcalf & Eddy (1995). Strength values represent a lower bound friction angle with zero cohesion, which is a lower bound for all strength values within the anticipated stress range.
- Use of groundwater levels generated from the hydrogeologic modeling described earlier (Appendix D).
- Comparison of analyses factor of safety results to minimum required criteria of 1.5 for static conditions and 1.0 for seismic conditions using a pseudostatic analysis. Comparison of estimated seismically induced permanent displacement to maximum allowed 12 inches for pseudostatic analysis cases yielding a safety factor less than 1.0.

5.3 CONDITIONS ANALYZED

Geometric conditions analyzed in the Phase 3 stability analyses associated with the project alternatives, as depicted on Figures 7, 8, and 9, are as follows:

• Existing ground surface and slope, per the M&E geologic cross sections.

- Overall 18 percent regraded cover slope superimposed over existing ground surface topography.
- Stability buttress at the toe of the landfill with the 18 percent regraded slope.

For each of the various variable conditions used as the bases of analyses, the following conditions were analyzed, in terms of general mechanisms of potential sliding and the approach to searching for potential failure surfaces with minimum factors of safety for each case analyzed:

- Circular failure surface search through all materials in the landfill slope above the unweathered claystone bedrock.
- Sliding block failure surface search within the critical colluvium/slide and weathered claystone bedrock materials, as depicted on the M&E geologic cross sections.
- Shallow sliding potential in regraded cover materials.

For each of the various geometric conditions and potential sliding mechanisms considered, the stability was analyzed for two groundwater conditions, as follows:

- Average wet year climate conditions (Appendix D).
- 100-year wet year climate conditions (Appendix D).

For each of the various conditions and cases considered, analyses were performed for both static and seismic conditions. Seismic conditions were analyzed initially using a pseudostatic analysis approach with a horizontal force seismic coefficient of 0.06g. The simplified deformation analysis was also employed for the various cases analyzed.

In addition, a check was made of surficial sliding potential in regraded cover materials based on saturated ground conditions.

5.4 METHODOLOGY

Stability analyses of the landfill slope for various project alternatives were conducted in the following evaluation/computational sequence:

• Static slope stability analysis and selection of potential critical slip surfaces.

- Pseudostatic slope stability analysis and evaluation of yield acceleration seismic coefficient.
- Determination of average acceleration of potential slide mass under selected design conditions for seismic shaking.
- Estimation of seismically induced permanent displacement for the selected design earthquake event using simplified deformtion analysis.

These four stages of the analysis are described in the following sections.

To assess permanent, long-term steady state stability of the landfill, conventional two-dimensional limit-equilibrium stability analyses methods were performed for static conditions. The limit equilibrium methods were also employed for an initial, simplified assessment of seismic stability using the assigned seismic coefficient of 0.06 g for pseudostatic conditions. Factors of safety against sliding using circular arc and sliding block failure surfaces were computed for both the static and pseudostatic analyses. For the approach taken of assigning a uniform lower bound strength to the most critical colluvium/slide and weathered claystone materials, which is conservative, and considering the geometry of the landfill slope and subsurface material layers, either circular arc or sliding block failure modes could be critical, and these methods of modeling potential critical failure surfaces used for the stability analyses are appropriate.

The landfill slope for the various conditions previously discussed was computer-analyzed for circular arc failure modes using Bishop's modified method and for sliding block failure modes using Janbu's modified method. These methods incorporate, as basic input data, the geometry of the slope and subsurface material layers, unit weight and shear strength properties of the soil and bedrock materials, and the distribution of boundary and internal water forces. After a failure surface has been assumed, the soil mass above the sliding surface is divided into a series of vertical slices. Forces acting on each slice include the earth pressures on its sides, water pressures on its sides and bottom, effective earth pressures with associated friction acting on the assumed sliding surface, and cohesion along the sliding surface. Various trial failure surfaces are analyzed until a minimum factor of safety is obtained for the case being studied.

The modified Bishop and Janbu methods are generally conservative and efficient methods of analysis used for initial extensive screening of potential slip surfaces. In addition, the Spencer method, being a more rigorous method of slope stability analysis, was used to check the most critical cases identified by searching methods employed by the modified Bishop and Janbu methods. Spencer's method satisfies both force and moment equilibrium of the sliding mass, whereas the modified Janbu and Bishop methods satisfy only force and moment equilibrium, respectively. Further, the most critical slope stability results were also independently evaluated as part of normal quality control procedures.

The various computational methods discussed above were performed by computer analyses. The computer program PC STABL 5M, developed at Purdue University, was used to perform the stability analyses. The program performed automatic searches of different potential failure surfaces to determine the most critical surface having the lowest factor of safety for the condition being analyzed.

For seismic stability analysis required beyond the initial, simplified pseudostatic analysis check, the Makdisi and Seed procedure for computation of seismically induced permanent displacement was employed. The methodology of this procedure, which is widely accepted in geotechnical earthquake engineering and state-of-practice in seismic stability evaluation of landfill slopes, is detailed separately in Appendix F of this memorandum.

For the surficial stability check of anticipated cover materials, an infinite slope analysis method of calculation was used.

5.5 RESULTS

The results of computer-aided stability runs for the various combinations of three cross sections, established soil and bedrock density and strength parameters, three geometric conditions, circular arc and sliding block potential failure mechanism searches, and two different groundwater conditions, for both static and seismic conditions, are provided and summarized on Figures 7, 8, and 9 for the M&E geologic sections B-B', C-C', and D-D', respectively. The results can be summarized as follows:

- The analysis of geologic section B-B' appears most critical. However, there are only subtle, minor differences in minimum safety factor results between the various cross sections analyzed.
- Results obtained from analyses of potential sliding block surfaces are slightly more critical, by only a difference of 0.1 on the safety factor, or the same as results of the analyses of potential circular arc sliding surfaces in all cases analyzed. This is consistent with the geometric configuration of the critical colluvium/slide and weathered claystone bedrock material layers oriented beneath the long flat landfill slope.
- For the two climatic conditions modeled by two slightly different groundwater levels, results indicate a maximum difference in safety factors of 0.1.
- All cases analyzed for existing topographic conditions have safety factor results equal to or less than 1.5 for static analysis and less than 1.0 for pseudostatic analysis.
- All cases analyzed for the 18 percent regrade condition have safety factor results ranging from 1.5 to 1.7 for static analysis and less than 1.0 for pseudostatic analysis.
- All cases analyzed for the 18 percent regrade with buttress condition have safety factor results ranging from 1.7 to 1.9 for static analysis and ranging from 0.9 to 1.0 for pseudostatic analysis.
- All cases analyzed for existing topographic conditions have estimated maximum seismically induced permanent displacement results ranging from 10 to over 12 inches.
- All cases analyzed for the 18 percent regrade condition have estimated maximum seismically induced permanent displacement results ranging from 5 to 10 inches.
- All cases analyzed for the 18 percent regrade with buttress condition have estimated maximum seismically induced permanent displacement results ranging from 3 to 5 inches.
- For the surficial stability check of anticipated cover materials, static and pseudostatic safety factors for saturated slope conditions are acceptable (Appendix E).

In addition to the summary of specific results for each case and condition analyzed, in terms of safety factor against sliding and maximum permanent displacement for seismic shaking, all analyses input variables are listed and illustrated on the results Figures 7, 8, and 9. Selected material parameters are listed in a summary table against a key for each subsurface material type. Geologic cross sections reflecting the three project alternative geometric conditions analyzed are provided adjacent to associated stability analyses results and depicting the distribution of hillside

materials and groundwater levels. On these geologic sections, for each of the geometric conditions analyzed, typical critical circular arc and sliding block surfaces are illustrated.

Backup of all computer runs showing both the critical sliding surface identified and all surfaces analyzed in the analysis search in a graphic form similar to the cross sections on Figures 7, 8, and 9, for all cases and conditions computed, are provided in Appendix E, organized to correspond to the summary of results on Figures 7, 8, and 9.

5.6 OBSERVATIONS AND CONCLUSIONS

Based on the findings of this geotechnical investigation and specifically the results of the stability analysis performed for the accelerated action alternatives, major observations and conclusions are as follows:

- The primary factor controlling the stability of the existing landfill slope and any regrading modification to it, for both local shallow instability and overall deeper instability potential, is the strength of the colluvium/slide and underlying weathered claystone bedrock materials beneath the landfill site.
- Groundwater conditions within the landfill hillside slope play a significant role in stability conditions from the standpoint of both effect on material strength of the clay type materials comprising the colluvium and weathered bedrock and hydrostatic loading conditions within the landfill slope.
- The criteria used in this analysis of 1.5 factor of safety for the static condition, 1.0 factor of safety using one-half of the peak bedrock acceleration for pseudostatic analyses, and permanent seismically-induced deformations less than 12 inches are consistant with guidance as outlined in Section 5.1.
- The current, more obvious existing evidence of local and surficial instability at the site, of lesser consequence, will be mitigated by improved control of surface water and improvement of material type and strength in slope regrading planned for the accelerated action.
- The critical potential sliding mechanism for lower probability, more massive and deeper instability, which would be of greater consequence, is a large sliding block configuration or a broad circular arc surface involving a majority of the slope with the sliding surface within the weakest colluvium and weathered claystone bedrock materials.

- All conditions analyzed for modifications to the landfill slope as part of accelerated action alternatives, either by regrading the slope to the overall 18 percent configuration or by regrading with a stability enhancing buttress, meet or exceed the minimum required safety factor of 1.5 for long term static conditions and would limit maximum seismically induced permanent displacement from seismic shaking under design seismic conditions to less than the maximum 12-inch established design criteria.
- A buttress at the toe of the landfill slope provides enhancement to the overall landfill slope stability, but very subtle improvement for the size and configuration analyzed, approximately 20 feet high, extending about 50 feet beyond the existing slope toe, with a 2.5 to 1, horizontal to vertical, side slope.
- The results of the static and seismic stability analyses do not conclude that stability enhancement beyond the slope regrading condition is required.

Some final observations and conclusions regarding aspects of this investigation that are considered conservative to the results of the stability analysis and design of the accelerated action are as follows:

- Strength parameters used for the critical materials controlling stability results are conservative lower bound values of all test data within the anticipated stress range.
- Neglecting cohesion in the somewhat overconsolidated clay type colluvium and weathered bedrock materials, as established in material parameter selection, particularly for the undrained strength used for short term seismic loading, is conservative to the stability analysis results.
- The highest groundwater condition analyzed in combination with seismic loading is quite conservative, as the likelihood of both these conditions occurring simultaneously is low.
- The 12-inch maximum displacement criteria for seismically induced deformation could be considered conservative, as only a soil cover, with no deformation sensitive design components, such as synthetic liners and piping systems, is anticipated for the accelerated action design.
- The 18 percent regrade design slope is conceptual in nature. Further refinement of this regraded slope with further consideration given to surface water management, groundwater elevations, and bedrock elevations will improve stability issues.

5.7 CONCEPTUAL ACCELERATED ACTION DESIGN

As a result of the data presented and reviewed in this report, the results of static and seismic stability analyses, and past design experience, it is concluded that no stability enhancement

beyond slope regrading is required to meet established design criteria for the accelerated action at the OLF.


6.0 REFERENCES

- Advanced Terra Testing, Inc. (2004), Geotechnical laboratory test results, RFETS. Report of test results prepared for Kaiser-Hill, including moisture and density determinations, Atterberg limits, particle size distribution, consolidation, direct shear, and triaxial compression tests, dated August 2004.
- Ambraseys, N.N. and Sarma, S.K. (1967), "The Response of Earth Dams to Strong Earthquakes." Geotechnique, London, England, Vol. 17, September, pp. 181-213.
- Blume [URS/Blume & Associates] (1974), "Seismic and Geologic Investigations and Design Criteria for Rocky Flats Plutonium Recovery and Waste Treatment Facility." Report prepared for CF Braun and Company.
- Bray, J.D., Augello, A.J., Leonards, G.A., Repetto, P.C. and Byrne, R.J. (1995), "Seismic Stability Procedures for Solid -Waste Landfills." Journal of Geotechnical Engineering, Vol. 121, No. 2, February 1995, pp. 139-151.
- California Department of Conservation, Division of Mines and Geology (1997), "Guidelines for Evaluating and Mitigating Seismic Hazards in California." Special Publication 117, 73p.
- Colorado Department of Public Health and Environment, *Hazardous Waste Commission Regulations*, 6 CCR 100-3.
- Colorado Department of Public Health and Environment, Regulations Pertaining to Solid Waste Disposal Sites & Facilities, 6 CCR 100-2.
- Colorado Division of Water Resources, Rules and Regulations for Dam Safety and Dam Construction, 2 CCR 402-1.
- Colorado Geological Survey, Division of Minerals and Geology, Department of Natural Resources (2003), "Published Faults of the Colorado Front Range, Digital Data." Open-File Report 03-04 (CD), compiled by Matthew L. Morgan.
- Colorado Geological Survey [CGS] and Association of Engineering Geologists [AEG], (2003), "Engineering Geology in Colorado Contributions, Trends, and Case Histories." AEG Special Publication No. 15 and CGS Special Publication 55, edited by Douglas D. Boyer, Paul M. Santi, and William Pat Rogers.
- Colorado Geological Survey (2000), "Colorado Earthquake Information, 1867-1996." CGS Bulletin 52 (CD) compiled by Robert M. Kirkham and William P. Rogers.
- Colorado Geological Survey (2000), "Colorado Earthquake Information, 1867-1996." CGS Bulletin 52 (CD) compiled by Robert M. Kirkham and William P. Rogers.

- Colorado Geological Survey (1986), "Contributions to Colorado Seismicity and Tectonics A 1986 Update." CGS Special Publication 28, Edited by William P. Rogers and Robert M. Kirkham.
- Dames and Moore (1986), "Geologic and Seismologic Investigations for Rocky Flats Plant." Report prepared for the U.S. Department of Energy, dated July 1981, Volume 1.
- Earth Tech (Undated), "Alignment of Potential GW Diversion System, Original Landfill, Rocky Flats ETS." Interpreted geologic profile (fence diagram), including 11 exploratory borings, prepared for U.S. Department of Energy.
- Earth Tech (2004), "Geotechnical Investigation for Accelerated Action Design at the Original Landfill Phase 1 Data Review Technical Memorandum, Rocky Flats Environmental Technology Site, Original Landfill." Memorandum prepared for Kaiser-Hill Company, dated April 26, 2004.
- Earth Tech (2004), "Geotechnical Investigation for Accelerated Action Design at the Original Landfill Phase 2b Field and Laboratory Data Investigation. Summary of Work to Date" Technical Memorandum, Rocky Flats Environmental Technology Site, Original Landfill, prepared for Kaiser-Hill Company, dated July 27, 2004.
- Earth Tech (2004), "Accelerated Action Design at the Original Landfill, Rocky Flats Environmental Technology Site, 95% Design Revision 1 Submittal Volume II of II (Appendices A Through M)." Memorandum prepared for Kaiser-Hill Company, dated August, 2004.
- EG & G (1995), "Geologic Characterization Report for Rocky Flats Environmental Technology Site."
- Franklin, A.G. and Chang, F.K. (1977), "Earthquake Resistance of Earth and Rockfill Dams." U.S. Army Corps of Engineers Miscellaneous Paper GL-77-17, Waterways Experimental Station, Vicksburg, Mississippi.
- Hunt, C.B. (1974), "Natural Regions of the United States and Canada." Published by W.H. Freeman and Company, 725 p.
- Hynes-Griffin, M.E. and Franklin, A.G. (1984), "Rationalizing the Seismic Coefficient Method." U.S. Army Corps of Engineers Miscellaneous Paper GL-84-13, AD-A144 730, 37 pages.
- I.C.O.L.D. (1975), "A Review of Earthquake Resistance Design of Dams." International Commission on Large Dams, Bulletin 27, March.
- Kavazanjian, E. (1999), "Seismic Design of Solid Waste Containment Facilities." Invited paper, 8th Canadian Conference on Earthquake Engineering, Vancouver, British Columbia, Canada, June 13 to 15, 1999, 20p.

- Marcuson, W.F. III, Hynes, M.E. and Franklin, A.G. (1992), "Seismic Stability and Permanent Deformation Analyses: The Last Twenty-Five Years." Proceedings Conference on Stability and Performance of Slopes and Embankments -II, ASCE, New York, N.Y., pp. 552-592 pages.
- Metcalf and Eddy (1995), "Rocky Flats Environmental Technology Site, Geotechnical Investigation Report for Operable Unit No. 5." Draft report prepared for the U.S. Department of Energy, dated September, 1995.
- Makdisi, F. and Seed, H.B. (1978), "Simplified Method for Estimating Dam and Embankment Earthquake-Induced Deformations." Journal of the Geotechnical Engineering Division, ASCE, Vol. 104, No. GT7, dated July 1978, pp. 849-867.
- Makdisi, F. and Seed, H.B. (1977), "A Simplified Method for Estimating Earthquake-Induced Deformation in Dams and Embankments." Report No. UCB/EERC-77/19, Earthquake Engineering Research Center, University of California, Berkeley, California.
- Makdisi, F. and Seed, H.B. (1977), "Simplified Procedure for Computing Maximum Crest Acceleration and Natural Period for Embankments." Report No. UCB/EERC-77/19, Earthquake Engineering Research Center, University of California, Berkeley, California.
- Newmark, N.N. (1965), "Effects of Earthquakes on Dams and Embankments." Geotechnique, London, England, Vol. 15, No. 2, June 1965.
- Risk Engineering (1995), "Seismic Hazard Analysis for Rocky Flats Plant." Final Report prepared for EG&G Rock Flats, Inc., dated September 29, 1994.
- Rust Environment and Infrastructure (1995), "Geotechnical Field Notes Rust Field Logging Procedures for Geotechnical Investigation of OU-5 Original Landfill." Appendix A (Draft).
- Sarma, S.K. (1975), "Seismic stability of Earth Dams and Embankments." Geotechnique, London, England, Vol. 25, No. 4, December.
- Seed, H.B. and Idriss, I.M. (1982), "Ground Motions and Soil Liquefaction During Earthquakes." E.E.R.I Monograph Series No. 5.
- Seed, H.B (1979), "Considerations in the Earthquake-Resistance of Earth and Rockfill Dams." Geotechnique, London, England, Vol. 29, No. 3, pp. 215-263.
- Seed, H.B. and Martin, G.R. (1966), "The Seismic Coefficient in Earth Dam Design." Journal of the Soil Mechanics and Foundations Division, ASCE, Vol. 92, No. SM3, May, pp. 25-58.
- Seed, H.B., Ugas, C. and Lysmer, J. (1974), "Site-Dependent Spectra for Earthquake-Resistance Design." Report No. UCB/EERC-74/12, November, Earthquake Engineering Research

- Center, University of California, Berkeley, California. Also, Bulletin of the Seismological Society of America, Vol. 66, No. 1, February 1976, pp. 221-243.
- Shroba, R.R. and Carrara, P.E. (1994), "Preliminary Surficial Geologic Map of the Rocky Flats Plant and Vicinity, Jefferson and Boulder Counties, Colorado." U.S.G.S. Open-File Report 94-162.
- Southern California Earthquake Center/University of Southern California (1999), "Recommended Procedures for Implementation of DMG Spatial Publication 117, Guidelines for Mitigating Liquefaction Hazards in California." Report by Implementation Committee, edited by G.R. Martin and M. Lew, March, 63 pages.
- U.S. Environmental Protection Agency (1993), "Solid Waste Disposal Facility Criteria," Technical Manual, November.
- U.S. Geological Survey (1955), "Surficial Geology of the Louisville Quadrangle, Colorado." Geological Survey Bulletin 996-5.
- U.S. Geological Survey (1975), "Preliminary Map of Landslide Deposits, Denver 1 x 2 degree Quadrangle, Colorado." Miscellaneous Field Studies Map MF-705, by Roger B. Colton and Jeffrey A. Holligan.
- U.S. Geological Survey (1977), "Photo Interpretive Map Showing Areas Underlain by Landslide Deposits and Areas Susceptible to Landsliding in the Louisville Quadrangle, Boulder and Jefferson Counties, Colorado." Miscellaneous Field Studies Map MF-871, by Roger B. Colton and Jeffrey A. Holligan.
- U.S. Geological Survey (1961), "Bedrock Geology of the Louisville Quadrangle, Colorado." Geologic Quadrangle Maps of the United States Map GQ-151 by Frank D. Spencer.



ICU TRIAXIAL TEST RESULTS

								DRAINED	STRENGTH 3
	KEY	MATERIAL 1	LOCATION	SAMPLE	DEPTH (feet)	USCS 2	DENSITY (pcf)	COHESION (psf)	FRICTION ANGLE (degrees)
				L1	14		125		
-		CSSW	TP1	L2	14		127	300	30
- [L3	14		125		
				L1	10		121		
-		CSSW	TP4	L2	10		122	400	15
				L3	10		127		
- 1				L1	7		126		
-		CSSW	TP6	L2	7		126	200	34
				L3	7		130		
-							130		
-		CSMW	B3	S2	18-20.5	CH	129	300	17
L							127		
١							125		
١		Qc	B4	S2	12-14.5	СН	120	500	15
L							122		
	, ,						129		
-		CSSW	B4	S3	14.5-17	СН	125	500	22
L							125		
:							123		
-		cssw	B6	S1	11-13.4	СН	128	600	20
L							124	i	
-							128		
-		cssw	B7	S1	13-15	СН	128	400	24
L							127		;
ſ							120		
-	—	Qc	B8	S1	6-8.2		121	300	30
1.							122		
				L7	17.5-18		122		
		CSMW	B7	L8	18-18.5		125	600	19
L				L9	18.5-19	СН	120		

¹ Qc = COLLUVIUWSLIDE, CSSW = SEVERELY WEATHERED CLAYSTONE, CSMW = MODERATELY WEATHERED CLAYSTONE

EARTH TECH

FIGURE 2
ORIGINAL LANDFILL GEOTECHNICAL INVESTIGATION
TRIAXIAL SHEAR TEST DATA - DRAINED STRENGTH

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE GOLDEN, COLORADO

NOVEMBER 2004

57378

57378\cad\Figure2.dwg - 28 Oct 2004

 $^{^{\}rm 2}$ UNIFIED SOIL CLASSIFICATION, BASED ON GRADATION AND ATTERBERG LIMITS

 $^{^{3}}$ BASED ON MAXIMUM PRINCIPAL STRESS RATIO FAILURE CRITERIA, EFFECTIVE STRESS PARAMETERS

STABILITY ANALYSIS STRESS RANGE

SELECTED LOWER BOUND

MOHR CIRCLES

ICU TRIAXIAL TEST RESULTS

ĺ								DRAINED S	STRENGTH 3
	KEY	MATERIAL 1	LOCATION	SAMPLE	DEPTH (feet)	USCS ²	DENSITY (pcf)	COHESION (psf)	FRICTION ANGLE (degrees)
				L1	14		125		
		CSSW	TP1	L2	14		127	150	30
				L3	14		125		
ĺ				L1	10		121		
ı		CSSW	TP4	L2	10		122	400	15
				L3	10		127		
				L1	7		126		
1	—	CSSW	TP6	L2	7		126	150	35
				L3	7		130		
							130		
ŀ	—	CSMW	В3	S2	18-20.5	СН	129	700	16
							127		
- 1							125		
		Qc	B4	S2	12-14.5	CH	120	450	16
L							122		
	· .						129		
-		CSSW	B4	S3	14.5-17	СН	125	500	22
.							125		j
1				·			123		
-		cssw	B6	S1	11-13.4	СН	128	600	20
Į							124		
					'		128		
-	—	CSSW	B7	S1	13-15	CH	128	400	24
L							127		
							120		
١	—	Qc	B8	S1	6-8.2		121	400	28
							122		
				L7	17.5-18		122		
	—	CSMW	B7	L8	18-18.5		125	500	19
Į				L9	18.5-19	CH	120		

¹ Qc = COLLUVIUM/SLIDE, CSSW = SEVERELY WEATHERED CLAYSTONE, CSMW = MODERATELY WEATHERED CLAYSTONE

EARTH TECH

FIGURE 3
ORIGINAL LANDFILL GEOTECHNICAL INVESTIGATION
TRIAXIAL SHEAR TEST DATA - DRAINED STRENGTH

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE GOLDEN, COLORADO

NOVEMBER 2004

² UNIFIED SOIL CLASSIFICATION, BASED ON GRADATION AND ATTERBERG LIMITS

³ BASED ON 5 PERCENT STRAIN FAILURE CRITERIA, EFFECTIVE STRESS PARAMETERS

STABILITY ANALYSIS STRESS RANGE

DIRECT SHEAR TEST RESULTS 1

						-	PEAK ST	RENGTH 2	RESIDUAL	STRENGTH ²
KEY ²	MATERIAL ³	LOCATION	SAMPLE	DEPTH (feet)	uscs⁴	DENSITY (pcf)	COHESION (psf)	FRICTION ANGLE (degrees)	COHESION (psf)	FRICTION ANGLE (degrees)
	cssw	TP1	L4	14	СН	124 125 124	535	24.6	0	30.1
	cssw	TP4	L4	10	СН	101 118 108	346	24.0	434	11.3
	cssw	TP6	L4	7	СН	134 134 131	1008	33.6	245	19.3
	Qc	B3	L3 L4 L4	15.5-16 16-16.5 16-16.5		126 124 124	912	14.6	463	19.9
	CSMW	B4	L5 L6 L6	19.5-20 20-20.5 20-20.5	СН	122 126 131	0	29.0	0	24.8
·	Qc	В7	L2 L3 L3	8.5-9 9-9.5 9-9.5	CL	127 125 124	358	22.9	180	26.9
	CSSW	B7	L4 L5 L6	11.5-12 12-12.5 12.5-13		125 122 122	579	15.8	269	21.1
	cssw	В9	L5 L7 L8	7-7.5 8.5-9 9-9.5	СН	123 123 127	435	24.6	149	24.6
	CSMW	B10	L5 L6 L6	9.5-10 10-10.5 10-10.5	СН	124 124 124	25	40.6	282	24.3

¹ CONSOLIDATED DRAINED PROCEDURES (EFFECTIVE STRESS PARAMETERS)

EARTH TECH

FIGURE 4
ORIGINAL LANDFILL GEOTECHNICAL INVESTIGATION
DIRECT SHEAR TEST DATA - DRAINED STRENGTH


ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE GOLDEN, COLORADO

NOVEMBER 2004

² DASHED = PEAK STRENGTH, SOLID = RESIDUAL STRENGTH

³ Qc = COLLUVIUM/SLIDE, CSSW = SEVERELY WEATHERED CLAYSTONE, CSMW = MODERATELY WEATHERED CLAYSTONE

⁴ UNIFIED SOIL CLASSIFICATION, BASED ON GRADATION AND ATTERBERG LIMITS



ICU TRIAXIAL TEST RESULTS

			· · · · · · · · · · · · · · · · · · ·	Γ			UNDRAINED	STRENGTH ³
KEY	MATERIAL 1	LOCATION	SAMPLE	DEPTH (feet)	USCS 2	DENSITY (pcf)	COHESION (psf)	FRICTION ANGLE (degrees)
			L1	14		125		
	cssw	TP1	L2	14		127	400	19
			L3	14		125		
			L1	10		121		
_	cssw	TP4	L2	10		122	300	12
			L3	10		127		
			L1	7		126		
	CSSW	TP6	L2	7		126	150	24
			L3	7		130		
						130		
	CSMW	B3	S2	18-20.5	СН	129	600	13
						127	_	
						125		
	Qc	B4	S2	12-14.5	СН	120	500	11
<u> </u>						122		
		5.4		44545	ا ا	129		
	CSSW	B4	S3	14.5-17	СН	125	600	15
						125		
						123		4-
	cssw	В6	S1	11-13.4	СН	128	450	17
						124		
	00014	ן דם	04	40.45		128	200	40
	CSSW	B7	S1	13-15	СН	128	300	18
$\vdash \vdash \vdash$						127		
						120		0.4
	Qc	B8	S1	6-8.2		121	300	24
				47.5.40		122		
	00144	D7	L7	17.5-18		122	600	40
	CSMW	B7 ,	L8	18-18.5		125	600	13
			L9	18.5-19	СН	120		

^{10 1} Qc = COLLUVIUM/SLIDE, CSSW = SEVERELY WEATHERED CLAYSTONE, CSMW = MODERATELY WEATHERED CLAYSTONE

EARTH TECH


FIGURE 5
ORIGINAL LANDFILL GEOTECHNICAL INVESTIGATION
TRIAXIAL SHEAR TEST DATA - UNDRAINED STRENGTH

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE GOLDEN, COLORADO

NOVEMBER 2004

 $^{^{\}mathbf{2}}$ UNIFIED SOIL CLASSIFICATION, BASED ON GRADATION AND ATTERBERG LIMITS

 $^{^{\}rm 3}$ BASED ON MAXIMUM PRINCIPAL STRESS RATIO FAILURE CRITERIA, TOTAL STRESS PARAMETERS



ICU TRIAXIAL TEST RESULTS

							UNDRAINED	STRENGTH ³
KEY	MATERIAL 1	LOCATION	SAMPLE	DEPTH (feet)	uscs ²	DENSITY (pcf)	COHESION (psf)	FRICTION ANGLE (degrees)
			L1	14		125		
	cssw	TP1	L2	14		127	550	16
			L3	14		125		
1			L1	10		121		
	cssw	TP4	L2	10		122	400	11
			L3	10		127		
			L1	7		126		
	CSSW	TP6	L2	7		126	100	26
			L3	7		130		
	001414		00	40.00.5	ا ا	130	200	44
	CSMW	B3	S2	18-20.5	CH	129	800	11
						127		
	Qc	B4	S2	12-14.5	СН	125 120	600	10
	QC	D4	32	12-14.5	Cn	120	600	10
						129		
	cssw	В4	S3	14.5-17	СН	125	700	14
	00011		00	14.0-17		125	,00	14
						123		
	cssw	В6	S1	11-13.4	СН	128	500	16
			٠.			124		
		•				128		
	cssw	B7	S1	13-15	СН	128	400	16
	-					127		-
						120		,
	Qc	B8	S1	6-8.2		121	350	23
						122		
		-	L7	17.5-18		122		
	CSMW	В7	L8	18-18.5]	125	700	12
			L9	18.5-19	СН	120		

¹ Qc = COLLUVIUM/SLIDE, CSSW = SEVERELY WEATHERED CLAYSTONE, CSMW = MODERATELY WEATHERED CLAYSTONE

EARTH TECH


FIGURE 6
ORIGINAL LANDFILL GEOTECHNICAL INVESTIGATION
TRIAXIAL SHEAR TEST DATA - UNDRAINED STRENGTH

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE GOLDEN, COLORADO

NOVEMBER 2004

 $^{^{2}}$ UNIFIED SOIL CLASSIFICATION, BASED ON GRADATION AND ATTERBERG LIMITS

 $^{^{3}}$ BASED ON 5 PERCENT STRAIN FAILURE CRITERIA, TOTAL STRESS PARAMETERS



GEOMETRIC	ANALYSIS	GROUNDWATER	MINIMUM SAF	ETY FACTOR	YIELD 3	MAXIMUM ⁴
CONDITION	TYPE	CONDITION	STATIC	0.06 g ²	ACCELERATION	SEISMIC DISPLACEMENT
· · · · · · · · · · · · · · · · · · ·	CIRCULAR	AVERAGE ¹ WET YEAR	1.5	0.8	0.02	10"
EXISTING	SEARCH	100-YEAR WET YEAR	1.4	0.8	0.01	N/A ⁵
EXIOTING	SLIDING BLOCK	AVERAGE ¹ WET YEAR	1.4	0.8	0.01	N/A ⁵
	SEARCH	100-YEAR WET YEAR	1.3	0.8	0.01	N/A ⁵

	CIRCULAR	AVERAGE ¹ WET YEAR	1.6	0.9	0.03	6*
18%	SEARCH	100-YEAR WET YEAR	1.5	0.9	0.02	10"
REGRADE	SLIDING BLOCK	AVERAGE ¹ WET YEAR	1.6	0.9	0.03	6*
, .	SEARCH	100-YEAR WET YEAR	1.5	0.9	0.02	. 10⁼

	CIRCULAR SEARCH	AVERAGE ¹ WET YEAR	1.7	1.0	0.06	3"
18% REGRADE		100-YEAR WET YEAR	1.7	1.0	0.05	4"
WITH BUTTRESS	SLIDING BLOCK	AVERAGE ¹ WET YEAR	1.7	1.0	0.05	4"
	SEARCH	100-YEAR WET YEAR	1.7	0.9	0.04	5"

¹ AVERAGE WET YEAR GROUNDWATER CONDITION, NOT SHOWN ON SECTIONS, IS 1 TO 2 FEET LOWER THAN 100-YEAR WET YEAR GROUNDWATER CONDITION.

FIGURE 7

ORIGINAL LANDFILL GEOTECHNICAL INVESTIGATION STABILITY ANALYSES - M&E SECTION B-B'

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE GOLDEN, COLORADO


NOVEMBER 2004

² SEISMIC COEFFICIENT FOR PSEUDOSTATIC ANALYSIS.

³ SEISMIC COEFFICIENT THAT PRODUCES SAFETY FACTOR OF 1.0 IN PSEUDOSTATIC ANALYSIS.

 $^{^{}f 4}$ ESTIMATED MAXIMUM SEISMICALLY INDUCED PERMANENT DISPLACEMENT USING SIMPLIFIED **DEFORMATION ANALYSIS.**

 $^{^{5}}$ PROCEDURE FOR ESTIMATING SEISMICALLY INDUCED PERMANENT DISPLACEMENT BECOMES INVALID, IN THIS CASE, FOR YIELD ACCELERATIONS OF 0.01 AND LESS. MAXIMUM DISPLACEMENT IN THIS CASE LIKELY GREATER THAN 12 INCHES.



STREAM ALLUVIUM

ENGINEERED FILL

1995 METCALF & EDDY REPORT SECTION C-C*

WEATHERED CLAYSTONE

UNWEATHERED CLAYSTONE

125

120

130

130

125

130

135

200

33

20

GEOMETRIC	ANALYSIS	GROUNDWATER	MIŅIMUM SAF	ETY FACTOR	YIELD 3	MAXIMUM ⁴ SEISMIC
CONDITION	TYPE	CONDITION	STATIC	0.06 g ²	ACCELERATION	DISPLACEMEN
	CIRCULAR	AVERAGE 1 WET YEAR	1.4	0.8	0.01	N/A ⁵
EXISTING	SEARCH	100-YEAR WET YEAR	1.4	0.8	0.01	N/A ⁵
20011110	SLIDING BLOCK SEARCH	AVERAGE ¹ WET YEAR	1.5	0.9	0.02	10"
		100-YEAR WET YEAR	1.5	0.8	0.01	N/A ⁵
	-					
	CIRCULAR	AVERAGE 1 WET YEAR	1.7	0.9	0.04	5"
18%	SEARCH	100-YEAR WET YEAR	1.6	0.9	0.03	6"
REGRADE	SLIDING BLOCK	AVERAGE ¹ WET YEAR	1.7	0.9	0.04	5"
2	SEARCH	100-YEAR WET YEAR	1.6	0.9	0.03	6"

	CIRCULAR	AVERAGE ¹ WET YEAR	1.8	1.0	0.06	3"
18% REGRADE	SEARCH	100-YEAR WET YEAR	1.8	1.0	0.06	3 "
WITH BUTTRESS	SLIDING BLOCK	AVERAGE ¹ WET YEAR	1.9	1.0	0.06	3"
	SEARCH 1	100-YEAR WET YEAR	1.8	1.0	0.06	3"

^{.1} AVERAGE WET YEAR GROUNDWATER CONDITION, NOT SHOWN ON SECTIONS, IS 0 TO 2 FEET LOWER THAN 100-YEAR WET YEAR GROUNDWATER CONDITION.

0 25 50 SCALE IN FEET

15

30

600

200



FIGURE 8

ORIGINAL LANDFILL GEOTECHNICAL INVESTIGATION STABILITY ANALYSES - M&E SECTION C-C'

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE GOLDEN, COLORADO


NOVEMBER 2004

 $^{^{2}\ \}mbox{SEISMIC}$ COEFFICIENT FOR PSEUDOSTATIC ANALYSIS.

³ SEISMIC COEFFICIENT THAT PRODUCES SAFETY FACTOR OF 1.0 IN PSEUDOSTATIC ANALYSIS.

⁴ ESTIMATED MAXIMUM SEISMICALLY INDUCED PERMANENT DISPLACEMENT USING SIMPLIFIED DEFORMATION ANALYSIS.

⁵ PROCEDURE FOR ESTIMATING SEISMICALLY INDUCED PERMANENT DISPLACEMENT BECOMES INVALID, IN THIS CASE, FOR YIELD ACCELERATIONS OF 0.01 AND LESS. MAXIMUM DISPLACEMENT IN THIS CASE LIKELY GREATER THAN 12 INCHES.



						SHEAR S	TRENGTH	
	MATERIAL		UNIT WEIGHT		STATIC		SEISMIC	
KEY	DESIGNATION	DESCRIPTION	MOIST (pcf)	SATURATED (pcf)	COHESION (psf)	FRICTION ANGLE (degrees)	COHESION (psf)	FRICTION ANGLE (degrees)
	(1a)	WASTE	120	125	50	30	50	30
1///	16	WASTE / FILL / COVER	120	125	50	30	50	30
	2	COLLUVIUM / SLIDE	120	125	0	20	0	15
20000	3	ROCKY FLATS ALLUVIUM	120	125	0	37	200	30
	4	STREAM ALLUVIUM	125	130	0	33	0	33
	(5)	WEATHERED CLAYSTONE	120	125	0	20	0	15
	6	UNWEATHERED CLAYSTONE	125	130	600	30	600	30
	7	ENGINEERED FILL	130	135	200	35	200	35

0 25 50 SCALE IN FEET

GEOMETRIC	ANALYSIS	GROUNDWATER	MINIMUM SAF	ETY FACTOR	YIELD 3	MAXIMUM ⁴ SEISMIC	
CONDITION	TYPE	CONDITION	STATIC	0.06 g ²	ACCELERATION	DISPLACEMENT	
	CIRCULAR	AVERAGE 1 WET YEAR	1.3	0.7	N/A ⁵	N/A ⁶	
EXISTING	SEARCH	100-YEAR WET YEAR	1.3	0.7	N/A ⁵	N/A ⁶	
Duorino	SLIDING BLOCK	AVERAGE ¹ WET YEAR	1.5	0.8	0.01	N/A ⁶	
	SEARCH	100-YEAR WET YEAR	1.4	0.8	0.01	N/A ⁶	

	CIRCULAR	AVERAGE ¹ WET YEAR	1.7	0.9	0.04	5"
18%	SEARCH	100-YEAR WET YEAR	1.6	0.9	0.03	6"
REGRADE	SLIDING BLOCK	AVERAGE ¹ WET YEAR	1.6	0.9	0.03	6"
3	SEARCH	100-YEAR WET YEAR	1.6	0.9	0.02	10"

	CIRCULAR	AVERAGE 1 WET YEAR	1.7	1.0	0.05	4"
18% REGRADE	SEARCH	100-YEAR WET YEAR	1.7	0.9	0.04	5 "
WITH BUTTRESS	SLIDING BLOCK	AVERAGE ¹ WET YEAR	1.7	0.9	0.04	5"
	SEARCH	100-YEAR WET YEAR	1.7	0.9	0.04	5"

¹ AVERAGE WET YEAR GROUNDWATER CONDITION, NOT SHOWN ON SECTIONS, IS 0 TO 3 FEET LOWER THAN 100-YEAR WET YEAR GROUNDWATER CONDITION.

EARTH TECH

FIGURE 9

ORIGINAL LANDFILL GEOTECHNICAL INVESTIGATION STABILITY ANALYSES - M&E SECTION D-D'

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE GOLDEN, COLORADO

NOVEMBER 2004

57378

1995 METCALF & EDDY REPORT SECTION D-D'

² SEISMIC COEFFICIENT FOR PSEUDOSTATIC ANALYSIS.

 $^{^{\}rm 3}$ SEISMIC COEFFICIENT THAT PRODUCES SAFETY FACTOR OF 1.0 IN PSEUDOSTATIC ANALYSIS.

⁴ ESTIMATED MAXIMUM SEISMICALLY INDUCED PERMANENT DISPLACEMENT USING SIMPLIFIED DEFORMATION ANALYSIS.

 $^{^{5}}$ SAFETY FACTOR LESS THAN 1.0 FOR 0.0 g (STATIC CONDITION), USING ASSIGNED STRENGTH FOR SEISMIC CONDITION.

⁶ PROCEDURE FOR ESTIMATING SEISMICALLY INDUCED PERMANENT DISPLACEMENT BECOMES INVALID, IN THIS CASE, FOR YIELD ACCELERATIONS OF 0.01 AND LESS. MAXIMUM DISPLACEMENT IN THIS CASE LIKELY GREATER THAN 12 INCHES.

APPENDIX A BOREHOLE AND TEST PIT LOGS

TEST PIT LOGS

 <u></u>		·		,		· ·		.,				1 4	1 1 1	1 1.	111	r j i
	Original Landfill	STRUCTURE	NO. STRIKE DIP TYPE	W. J. 608 No Samples Collected	Lu State	caprove,	in soft pister.	3		ACDIVE SADOS FREE WATER IN GP						
	ron mental Technology Site	UNITS	DESCRIPTION COLLUNION	SANDT CLAY	iost.	20 bbles + boilders to 2; to 8	400	1) + caliche) absonce of	Searp		80000000000000000000000000000000000000					
	THENCH NO. TP-2 LOCATION: Rocky Flack Enum SHEET 1 OF 1 NOTES:		DEPTH NO.	0'-4' D Qc (• :	4-6.5 (Sal (GW)	(6,5'-9' (3) (385)) (6	STATION THE STATE OF	2 /		R. Heidsich Lugge	<u>/</u>	5		N, 10°E	
%8∕8,	Ē	A	R	тн	9) т	E C	Ĥ			LECT NO.		IC TREN	ICH LO	FIGURE	но.
		A	tyc	er intel	RNATIONA	AL LTD. C	OMPANY	,	-	5737	18		20.6			
i			-													

TRENCH NO.TP-4	SHEET L OF L NOTES:	CLAY med bingdonp ; 50% med diste. In to seed sand; 20% fine + ese grand	1) 6-10 (2) CSMU (SU?) CLAYSTONE; MA(SOU.?) WithInd; SOFT, frinkly Slick daw fraid slightly	CSSW CLANSENG SON SON SCHOOL + CONTROL OF FRONT STORE SON SING SON	K. Gamp	6/22/04 DATE		A. Heidrich - Contact dippins 14°S.	COLUMN STATE OF STATE		Scale, FT.	Liners capping blacciabed CKSW.	1 = 4 6	Massive siles pp=+5 TV=+10
8.78,	-	UCO INTERNA	TIONAL LTD.	COMPANY	1		57 <u>37</u>	S NO.		BATE		F	IGURE	NO.

•	
	→ ONLAA38 → ONL
	Scale, FI.
	10000 00 00 00 00 00 00 00 00 00 00 00 0
	10 10 10 10 10 10 10 10 10 10 10 10 10 1
,	Tandomly dispersed in clay matrix Aand 198 to Sand 198
NO. STRIKE DIP TYPE	THE DEPTH HO. DESCRIPTION DESCRIPTION DESCRIPTION DESCRIPTION
38UT3URT2	m SHEET T OF T NOTES:

EARTH TECH PROJECT NO. CATE FIGURE NO.
--

BOREHOLE LOGS -

63 PR 15 12 12 15 15 L3 10 CSHW - 17 - 16.5 CLAYSTONE: SOV. Withrd Decker of	Boreh Locati Date: Geolo Drillini	ion - gist.	North Ru	1/30	loui	_Eas				C	otal Depth: 38.07 company: Project No.: 57378 ample Type:
SAMPLE DESCRIPTION Road Fill Fills DESCRIPTION Road Fill Fill Fills DESCRIPTION Road Fill Fill Fill DESCRIPTION Road Fill Fill Fill DESCRIPTION Road Fill Fill DESCRIPTION Road Fill Fill Fill DESCRIPTION Road Fill Fill DESCRIPTION Road Fill F				NG S	UPE	RVISC	OR				DATE
Run 3.0 Run	OF CORE IN BOX TOP/BOTTOM	OF INTERVAL	EET OF CORE ININGERVAL (FIELD EASURENT)	SAMPLE	FRACTURE	BEDDING	GRAIN \$12E	SymBol.	OEPTH IN	אסנים הוואטרסטיב הוואטרסטיב	Road Fill / Fill
SP 6 (SC) SP 6 (SC) Incl Soud; 202 lon plot clay; day; SP 6 (SC) Incl Soud; 202 lon plot clay; day; SP 7 (SC) SP 7 POORLY: GRADED SAND TO 7 (Sp/SN) GRADED SAND TO 15.7 POORLY: GRADED SAND	Q.	in	7	C-L				GC.	-	000	gravel - collises (crushed rock) to 6; 258 med plate clay (logged from cuttings) maists. 1.5-35 less cobbles; pied firese gravel;
5,0-15.7 POORLY GRADED SAND SILTT SAND: orange + white Splan) 908 fine mixed sand; 108 8/7; dry: pockets of teoz, no bedding imported fill; occ. fat clay: 10,0-10,5' FAT cutr: olive groy; waste hup play; most; piece of cs in fill. 10,5' 15.5' wt soud (5h); med. dense, do 12-13-16.5' CLAYSTONE: SOV. withrd 13' L12 10 15' 15' L2 10 15' 15' V. sout; plate; faint relict bodies heavy FeOz stand in waterx: PP=33		_ [/ .		L.			SP			35'-50' CLATET SMID: H. yellowah bon., 808 for SC)
(-3 Run 2.0) hugh platy; moust; piece of es in fill. hugh platy; moust; piece of es in fill. 10,5' 15.5' Lt soud (5h); med. dense, don 12-13-18 Lt DR 1.5' 12 15-18 Lt DR 1.5' L2 10 L55W-16-15-16.5' CLAYSTONE: GOV. withred pred. orange, some gray mottling; V. soft; plate; faint relict body, heavily FeOz stand in matrix: pp=3.3 CSHW - 17-10-16.5' CLAYSTONE: GOV. withred CSHW - 17-16.5' CLAYSTONE: GOV. withred CSHW - 18-16.5' CLAYST	1	<i>is</i> 1						SM	- 7 - - 8- - 9 -		spism) got fine + med. sand; 108 sitt; dry; pockets of teoz, no bedding
(-3) 1.5 18 -13 -14 <u>BEDROCK</u> (-4) DR 1.5 12 12 15 15.7 - 16.5 CLAYSTONE: GOV. which of pred. orange, some gray modfling; U. soft; plate; faint relict boding heavily FeO2 stand in matrix ip P=3.3 13 10 15 10 10 10 10 10 10		or f	2/20		6				10 11 12	No.	high ploty; most; piece of cs in fill. 10,5'= 15.5' wt sound (SA); med, dense, dan
heavily FeOz stained in matrix ipp=3,3			(.5 (.5) (.5) (.5) (.5) (.5)	-	18 12171				- 13 - 14- 15 -		157 -16.5' CLAYSTONE: BOV. Withrd.
2.4 psi 1-18- Soft: friable towards; mad F=Oz	P			L3	250				16- 17 -		pred orange, some gray motiling; V. soft; plate; faint reliet bedry, heavily FeOz stand in motincipp=33 (6.5-31' CLYSTONE, mod. wthrt; dhappy recor

NOTES: General: USCS is modified for this log as follows: Tocally place intensely with Procedure No. RMRS/OPS-PRO.101 General: USCS is modified for this log as follows: Incolly Plat intensity that Procedure No. 18 Revision 0 Materials amounts are estimated by % volume instead of % weight. 17 Well 20ncs, 21-26 (OVer). Revision 0 Materials amounts are estimated by % volume instead of % weight. 170 Well 20ncs, 21-26 (OVer). Revision 0 Date effective: 12/31/98

(1) Badly broken core, accurate tootage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

RO	оск	Y FL	ATS I	ENVI	RONN	MENT	AL T	ECHNO	LOG	Y SITE BOREHOLE LOG PAGE 2 of 2
Во	rehole	e Nun	ber: _	R 7						Surface Elevation:
	5		th:		Ea	ıst:				Area:
	_									Total Depth: Project No.: 57378
		st:								Sample Type:
		quip. LOGC	ING	SUPE	RVIS	OR		· ·		water = 21.9' on 7/14
AP	PRC	VAL				<u> </u>				DATE
	3/	w	j.	T		m š	I		ų	interpreded foulted w/sandston@29.5'
OF COPE	TOP/BOTTO!	EET OF COF	SAMPLE	FRACTURE	BEDDING	GRAIN SIZ DISTRBUTH	USCS	DEPTH S	SOIU LITHOLOGIC LOG	SAMPLE DESCRIPTION
سنعاد	0.00	1. (1:-1	1-			CCMI			black (manganese) deposits on bedding stis.
:5	Ross 5	4.9/				1	CSMM			21-25 breceived + FeO2 stained
		4.0			1	J		-21 -	元	
								22	17.7	22' planar bedding a 20!
6		(·					-23 -	×	10-23.1'-23.7' Afracs, wide to 3/4"
	RUN	4.7			1			_24_	ا ہـ ہـ	infilled w/ manganese , carbon,
	6	5.0					-	_ 25 -	FX	Fe Oz filled , plana h irregular
									£ 12	28'-26 intersely to closely food.
			1					26	\	Count C .
-		İ			[.			_ 27 -	} \	25,5' Z65' his
		1						T 21.	1	25.5' Z6.5' high angle free, Fe Ox stemed
		Ŀ						_28-		26,5-29,5'; CS Blghty. wthrd.
7	Run	-1							1	Sala - 512) C2 Bidnay Man-
1	7	5,0						-29 -	┤ `	
	1	5.0		. 1			,	_ :	651	
						-		_30-	(1,7)	20 -1 DI ANNICH FORME . H II I
	:								I/II_I	29.5'- 31 SANDYSILTSTANE: It. yellowish brail
		1				1	CSUN	-31 -	CSUN	moderather soft wedi; moisti
	:	l						72		I Mustice a service in a many to the
ı						4		32-]	bodding SS interhodded it claver sand profile
_								- 33 -		bodding SS interbodded of clayer send, paralled 31-38' CLATSTONE; un weathered;
		1						_		31-38 CLATSTONE; un weathered; de gray; soft; weath closely franch
9,	rn	5.0	· .	ı			:	-34-		de gray; soft; wants closely trate
- 1	8	1		- 1	.	·		- -35 -	江村	31,5 frac, 150 healed no in filling
		5.0]			- 52 -	+FH	planer; smooth see, in claystone
				. [l		1	2/_	7.44 7.47	· • • • • • • • • • • • • • • • • • • •
		:	1	İ		- 1	1	36		31.5-32 brecciated CS
-			- 1	- 1	i	· 1	.	_ 37		& locally crushed , no FeD2 stains ; occ
		ĺ	1		1	٠. ا				frac's 550-70; sub horz, bedding think!
\dashv								-38-		34,5'-36': crushed;
1	- 1		1	- 1			.]		Ì	
l			- 1	1	. 1			- 39 -		BOHO 1430 GWE 3210 1450
	. }	1				.		110		Backfilled to ste. w/ bentonite chips
								7		Procedure No. RMRS/OPS-PRO.101

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate tootage measurements not possible.

(2) Core breaks cannot be matched, accurate tootage measurements not possible.

Revision 0

Date effective: 12/31/98 Page 27 of 28

Borehole Number: BZ Location - North: Date: 7/6+7/7 Geologist: KIZA to brilling Equip.: All Len	East:	Surface Elevation: Area: Total Depth: 25,0' Company: Project No.: 57. Sample Type:	
RMRS LOGGING SUPE	RVISOR	DATE Dry to 15 7/14	
TOPROTTOM OF CORE IN BOX TOPROTTOM OF INTERVAL FEEL OF INTERVAL FEEL OF INTERVAL FEEL OF INTERVAL SAMPLE NUMBER PRACTURE	BEDDING ANGLE GRAIN SIZE DISTRIBUTION USCS SYMBOL	SAMPLE DESCRIPTION	
X-3 Rm	- / -/ - /	O-6.5 GANDY CLAY II GIRAUE O-C(CL) Med born, some orange; GOZ M Plske clay; 25% for sand; 15 4 csegrevel to 4°; recist; stiff 3' pp. 5+ 3' pp. 5+ 3' pp. 5+ 4' postic; no bed sail silve; need plsty; 10%, for U2 stained throughout 10 8-17.5 CLAYSTONE; med gray; mod. or locallized Foor stains; soft; fire think laminated; near horizon Callibrat Foor stains; soft; fire think laminated; near horizon Callibrat rodules; v. stiff carbon accous; crushed in fraced.; some Fe U2 on 15 17 - 17.5'-25.0' CLAYSTONE; v. dleigray; or 17.5'-25.0' CLAYSTONE; v. dleigray;	intending intensel

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

Loc Dat Ge	cation ite: eologis	le Numl n - Norti st: Equip.:	th:		Eas	ıst:				Surface Elevation: Area: Total Depth: Project No.: 57378 Sample Type:
RN	MRS I	LOGG	ING S							DATE
ž.,,	TOP/BOTTOM OF INTERNAL	FET OF CORE IN INTERVAL FIELD JEASUREMENT	SAMPLE	FRACTUME	BEDDING	GRAIN \$12E DISTRIBUTION	USCS	DEPTH ON	SOIU LITHOLOGIC LOG	
. 4	Run	50	C-1					-21 - -22-	CSUW	CLAYSTONE (cort,)
X.6			177 202 14					-23 - -24		
9ts								-25- -26-		Backfilled w/ bentonite ehips
	•							- 27 - 28		• • • • • • • • • • • • • • • • • • •
								-29 - -30-		
								- 31 - -32-		
								- 35 - -35 -		
							-	-36- - 37 -	:	
						. :		-38- -39 -		

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

Bore Loca Date	hole Nu	mber: orth:	<u>B</u> 3	3	st:	TAL 7	rechno		SY SITE BOREHOLE LOG PAGE 1 OF 2 Surface Elevation: Area: Total Depth: 34 Company: Project No.: 57378
Drillir	ng Equip			10					Sample Type:
	RS LOC ROVA	****	SUPE	ERVIS	OR ———				DATE
OF COPE IN BOX TOP/BOTTOM	OF INTERVAL FEET OF COPE ININTERVAL	MEASUREMENT	FRACTURE	BEDDING	GPAIN \$12E DISTRIBUTION	USCS.	DEPTH IN	SOIV LITHOLOGIC	SAMPLE DESCRIPTION Road Fill
X-1 A	un 4.	0 64			镁	Q f	- 1 - - 2 - - 3 -	8 6	OL 13 GRAVELLY SANDY CLAY ; varies the CL) born to yellowsh brn; 50% mod date clay; 25% for bocse sand; 25% for to cae grown to 3; damp; angular gravel /crushed rock; varies w/
2 Ru	1,5 3,5 3,5	C-1					- 5 - - 6 - - 7 - - 8-	Ø D D	depth to SANDY CLAYEY GRANZE. el SANDY CLAYEY GRANZE. dive gray mottled orange; 30.2 med. plate clay 202 for mod-sand; 502 cægravel to 35
v-3 p€	20		600	c-1			- 9 - 10	D.	16' Shully refosal; 3" tock = 10,0'
DR	1,5		13 7913				- 11 - 12		COLLUVIUM COLLUVIUM 13-16' LEAN CLAY N/ GRAVEL; orange; 13-16' LEAN CLAY N/ GRAVEL; orange;
THE DR	NR 1.3', 1.5'	C-1 L-2 L-3 L-4	200 267			Se.	- 14- - 15 - - 16-		(CL) Gold med, to high placed y 201 (CL) Gold med, to high placed y 201 Process gravel & 4", rounded; 201 From the ese sand PP=1.8 TV=6 15' becomes nottled grey BEDKOCK
or 5 P	22 24	174	15 15 100			sow sow	- /7 - -/8 - /9 -	L'XX	16-17.5 CLAYSTONE; med.gray: sev- CL wthid, to soil; U. soft a place: soil-like: FAT CLAY. high place V. stiff; maist; PP=2.2. TEO2 stamme seltly corporarious. TV=>10

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

Bo Lo Da Ge	reholication te:eologi	e Nun	nber: _ th:	<u> 83</u>	<u> </u>		AL T	ECHNO	NOLOGY SITE BOREHOLE LOG PAGE 2 OF 2 Surface Elevation: Area: Total Depth: Project No.: 57378 Sample Type:				
• .	1.7	LOGO	ING	SUPE	RVIS(OR ·			:	DATE Dry to 28' 7/14/04			
OF CORE	TOP/BOTTOM	EET OF COPE IN INTERVAL	SAMPLE	FRACTURE	BEDDING	GRAIN SIZE DISTRIBUTION	USCS	OEPTH IN CEEL	SOIU LITHOLOGIC	SAMPLE DESCRIPTION			
P X-5	Rur	3.5	52 C-1				-	-21 - -22 -23 -	CSW	angular clay pieces in clay matrix. wrexciated; matrix Feoz stance. 20.5: PP>5: Occ. 51hs, rare			
V-10	pR	1.5	13 30 47	1-10 1-9 1-10		•:	CSUN	-24 - 25 - -26		na bodding; Precessis Falls total. 22' PP=3.0 24' PP=5			
X-1	aun 5	3,5	ـ1ـ					- 27 - 28 29 - 30		24-25.5 CLAYSTONE (SANDS) 25.5-24 CLAYSTONE: Vide, gray; Unweithered; Soft; weak; crushed; disturbed; rare FeOzstame; thuity laminotes o 10°dip.			
	S	5.6						- 31 - -32- -33 -		26.5-27.5' breezinted 30'rig chatter. 29'2 30' locally mod. wthred.			
								-35 - -36-					
								- 37 - 38 - 39 -					

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

	Bo Lo Da Go	oreho ocatio ate: _ eoloo	ole Nu in - No 6/2	mber: orth: _ K / /	B B G/25 A He 2ME	Ea Ea	st:	AL 7	TECHNO	•	Surface Elevation:
			LOG OVA	. :	SUPE	RVISC	OR .			<u> </u>	DATE
	TOP/BOTTOM OF COPE IN BOX	TOP/BOTTOM OF	FEET OF COPE IN INTERVAL	SAMPLE	FRACTURE	BEDDING	GRAIN SIZE DISTRIBUTION	SYMBOL	OEPTH IN	SOIU	SAMPLE DESCRIPTION
	∠-\ ×-2	Run 1		C-I				्रे म	-1 - -2 - -3 - -4 - -5 - -6 -	0	Road Fill 0-8.5' SANDY CLAYEY GRAVEL W/COBER BLAG GC) redent brown to dark brown; for +cse gravel + cottles to 8"; Bo 2 med plste. clay; 208 for to 22 sand.
	-3	DR P	3-9 1.2: 2.0/. 2.5	£ 2 £ 3 51	100- 250 250 250 250	Ů.		₹c	8- 9 - 10 12 13 14		2.5-14? SANDY CLAY; dk. brn; 708md. (CL) pister clay; sol fre. sand; rare. In. gravel; most; stiff; pp=1.75 mixed up pieces of CSSW claystone / lean clay LEAN CLAY, med. piste; caliche nodules Sev. Luthrol claystone in QC BEDROCK
X	-3 (hu^ 3	2,0	S3 C-1	8 5 400	972	c	inw .	-14- -15- -16- -17- -18- 19- 20		C35W V. Soft; pktc; whred today; saventhad. V. Soft; pktc; whred today; extension Fall stamed pp = 2,3; v. stiff; some calich nodula; sluse 18 17-29 CLATSTONE: mod. wthred; locally crushed uf slicks 4 heavy Feor stains; intensely freed. + laminated be domy up depth.

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.10

Revision 0

Date effective: 12/31/98

U.S. DEPARTMENT OF ENERGY ROCKY FLATS PLANT

Bo Loc Da Ge	rehole cation te: ologis	Num - Non t:	ber: _ th:	*B*					HNOLOGY SITE BOREHOLE LOG Surface Elevation: Area: Total Depth: Company: Sample Type:				
	ARS I		ING S	SUPE	RVIS(OR				DATE .			
OF CORE	TOP/BOTTOM OF INTERVAL	EET OF CORE IN INTERVAL (FIELD	BAMPLE NUMBER	FRACTURE	BEDDING	OPAIN SIZE DISTRIBUTION	USCS	DEPTH W	SOIU		SAMPLE DESCRIPTION		
x-3	DR C	3.5 3.5	L6_	25				-21 - -22-	C5 rw	22 ['] 6	closely fixed; from sks hannly toon travel; soft; wesh; pp=45		
X4		5.0						-23 - -24- - 25 - -26- -27 -		ta	econes thinly laminoted; saft; weeks mod. strong; MINN Februstanical		
B		5,0						-28- -29 - -30- -31 -	C5 UW	29'-34' CSUN	CLATSTONE; med. gray; which the Soft week; no feor, -108 contained deposits; horiz. laminated to thinky laminated		
X-6								-32- -33 -		160			
								- 35 - - 36 - - 37 - - 38 - - 39 -		Bach fill	ed w) bentonik chips		

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate tootage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98 Page 27 of 28

8 1 0 0	oreho ocation ale: eologi rilling	le Nui n - No 6/ st: Equip	riber: 23/ C	ENVI B4 Ck. H M E SUPE	A Ea eide	isi: S	ALT	Surface Elevation: 59/5 Area: RF OLF Total Depth: 33.5 Company: Layne Project No.: 57378 Sample Type: Continuous Core 5 × 3 **			
7	MKS PPR(SUFE				DATE 6/23/04			
TOP/BOTTOM OF COPE	TOP/BOTTOM OF	FEET OF CORE ININITERVAL	BAMPLE	FRACTURE	BEODING	GRAIN SIZE DISTRIBUTION	USCS. SYMBOL	DEPTH IN	3017 נודיםנסמכ נודים	Advance borning using 8" hollow ster august Continues about core sampling using SAMPLE DESCRIPTIONS favor between Road FILL	
X	l Run	NO PR					Q.F.	-		0'-9! GL SANDY CLAYEY GRAVEL W/ BOBBLES dark brown; 502 gravel a cobbbes to 6; rounded; 258 med. plste clay; 251 fa. sand appears med. donce; moist; appear derived from Rocky Flats Alluvium.	
10	Run 2	25	No lina					-5- -6- -7-		agentings of scler	
X-1	Kun 4	25	7				Re			Qc SANDYCLAY; dk bm; ~ 708 med. plack clay ~ 308 en bo cse sand; moist; spepart firm. 9-14' soil in coebarrel is in form	
	Rox B	25						- 13 - 14		oflow shown, possible cobble logad in engorbit, Pull argors. No obstruction: Enler hole + drive califted	
X-3	12 S	20/					SW	- /7 - - 18-	CSA ⁴	PEDROCK 16'-18' CLAYSTONE; medigry; sevi withed; extension FeO2 stoining in matrix; stiff V. soft; plostic : pp= 66 e 16-2'; mort; Crushed & intersely free'd.	
	0 × ×	727	15/1				DHW	- 19 - C	SPALA	18-30', becomes My, less becz intensity to closely fraced; smooth from sfer.	

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate tootage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

B L C C	Borehol _ocation Date: Geologi Drilling (Equip.:	nber: _ rth: 123/o (< #	B4 1	Æ Ea	ast:	TAL T	ECHNO	CHNOLOGY SITE BOREHOLE LOG Surface Elevation: Area: Total Depth: 33.5 Company: Sample Type:				
	RMRS	LOGG OVAL	ING S	SUPE	RVIS	OR			<u>.</u>	DATE Moist @ 23 7/14/04			
TOP/BOTTOM OF CORE	TOP/BOX OF	FEET OF COPE IN INTERVAL (FIELD	BAMPLE.	FACTURE	BEDDING	GRAIN SIZE DISTREUTION	USCS	DEPTH W	SOIU SOIU SOIU	SAMPLE DESCRIPTION			
xy	OR HA		NK 1.41.					-21 - -22- -23 -	CS Sw	CSNH cost. 20,5' less Feoz; deposited as since (43 mm) nodule fevert frocs. 8fc's; August 622'ul care somel; recovered proche in coc.			
	Run 8	2.5						_24 _ 25 -		25 heavy Ecr in 70 joints w/ 26 mad fract, subvert joints w/ heavy FeOz ; laminated ul fingraine			
X-5	9	3.5	ωl					- 27 - 28 29 -		26' mad. fraced, Subvert joints will heavy FeOz; laminated ul fingrained gondstone; claystone bedding laminated, to thinky laminated,			
X6	hun	5.0	ocrylic liner		·			_30_	CS VW	30/-33,5 CLAYSTUNE; UNWeathered; dark gray; soft; weak) mod. fracid. e high angles; absence of Feoz; laninated bedding present; some			
	10							32 33 -		acrylic liner crushed in core barrel a 3' Blocking clay from full recovery.			
		-						-34- -35 -		Drye completion of boring @ 1415.			
-							-	_ 37 _ _ 38					
							+	- 39 -					

Materials amounts are estimated by % volume instead of % weight.

Badly broken core, accurate lootage measurements not possible.
 Core breaks cannot be matched, accurate lootage measurements not possible.

Date effective: 12/31/98

Procedure No. RMRS/OPS-PRO.101

Page 27 of 28

Revision 0

_	· ·	·									
	Bo Lo Da Ge	reholication te: _ ologi	n - Noi st:	nber: nh: 2/28 Rick	BS BS Hell	Eas		ALT	ECHNO		Y SITE BOREHOLE LOG PAGE 1 OF 3 Surface Elevation: ~ 5, 970 Area: Total Depth: Project No.: 57378 Sample Type:
L	<u> </u>		Equip.				:				
			LOG(DVAL	GING	SUPEI	RVISC	OR			•.	DATE
1,100,000	OF COPE IN BOX	TOP/BOTTDIM OF	FEET OF CORE IN INTERVAL	SAMPLE NUMBER	FRACTURE	BEDDING	GPAIN 812E DISTRIBUTION	USCS	DEPTH N	SOIV	SAMPLE DESCRIPTION FILL
X	-7.	Ren 2 2 25	3/4.0	L1 L2 L3	0 Col (c)			Qe	- 1	Qe.	CL) GRAVELLY CLAY med brn.; 50% med plate clay from to escagravel; mixed w/ clayey sand at sandy clay moist to damp CL/GC) brn.; gray + yellomily brn.; -40% med. plate. clay ~ 30% from to esc. growel; ~ 30% from to esc sand; percent veries w/ depth; moist; lean clay u/grovelly leases + clayey sand leaser, mixed w/ depth; some elayey gravel. 12.5'-13.5' clayey sand w/grovel no slide planes or zones

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate lootage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

1	Boreho	ole Nu n - No nist:	mber orth: _		5	MEN	TAL	TECHN	OLO	Surface Elevation: Area: Total Depth: Company: Sample Type:
	RMRS NPPR	Charles and the	3	SUP	ERVIS	OR				DATE Moist @ 31 7/14/04
TOPREDITOM OF CORE	TOP/BOTTOM OF	FEET OF COPE INIMERIAL	MEASUREMENT SAMPLE	FACTURE	BEDDING	GRAIN SIZE DISTRIBUTION	USCS	OEPTH IN	SOIU	
X-1	t Ru	3,8	, c-	l			Qe	-21		205-24 GRAVELLY CLAY, med ploty.
	P	2.3	S-	100	. اد			-22 -23 -		
	P	2,3	S-2	100-	1			- 25 -		25-27 sandy clay ul grave (Fe Oz stain
	DR	1.5	L 50	47,				- 27 - 28		27! Feuz stained
	P	2.5	53	500 P51				-29 - -30-		gq-30.5' CLAYET & RAUEL
X-4	Bun	3.5	C-1		B 5	a		- 31 -		
X.p	G DR	NR.	110	506	30 50/3 50/3	L-1 L-2 NK	CSHW	- 33 - -34-	1	BEDROCK BEDROCK CLAYSTONE: yellowist brn.
hr.g	ku 7	7			HA 106/4"	nn -	۱۱۳۰	-35 -		w/red+wt. mottling; mod. wthrd; soft friable; no slide places/zones.
	DR PR	NR NK		150/ 6 200/5		0.7	NR L3	36- 37		
	HA				100/4	6.7	<u>L</u> 4	<u>-38</u> -		38'-42' CLAYSTONE; dk.gray) fresh, soft; friable; thinly laminded;
	DR.	257	17	593				_ 39 _ 		dry; intact + in place.

NOTES: General: USCS is modified for this log as follows: Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.101 Revision 0

Date effective: 12/31/98

Page 27 of 28

(2) Core breaks cannot be matched, accurate footage measurements not possible.

RMRS LOGGING SUPERVISOR APPROVAL	Bo Lo Da Ge	rehol cation te: ologi	e Nur ı - No st:	nber: rth:	ENVI B5	Ea	ıst:				Y SITE BOREHOLE LOG Surface Elevation: Area: Total Depth: Company: Project No.: 57378 Sample Type:
14 - 42 becomes laminated. 14 - 43 - 44 - 45 - 46 - 47 - 48 - 49 - 11 - 12 - 13 - 14 - 15 - 16 - 17 - 18 - 18 - 18 - 18 - 18 - 18 - 18	-				SUPE	RVIS					DATE
14 - 42 becomes laminated. 14 - 43 - 44 - 45 - 46 - 47 - 48 - 49 - 11 - 12 - 13 - 14 - 15 - 16 - 17 - 18 - 18 - 18 - 18 - 18 - 18 - 18	TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM	IN INTERVAL	SAMPLE	FRACTURE	BEDDING	GRAIN SIZE DISTRIBUTION	USCS	DEPTH IN	30ייע ניון אסגיספוני ניסס	SAMPLE DESCRIPTION
-14- -15- -16- -17- -18-	X-5		2.5	C-	1			CSUM			
									- 14- - 15 - - 16- - 17 - - 18-		

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate lootage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

Date effective: 12/31/98

Page 27 of 28

B L D G	orehol ocation ate: eologi		nber: th: / 7/9	B104		st:		ECHNO		Y SITE BOREHOLE LOG Surface Elevation: Area:	
		LOGO	GING	SUPE	RVISC	OR			· ·	-DATE	
TOPROTTOM OF COPE	TOP/BOTTOM Of	FEET OF CORE ININTERVAL	SAMPLE NUMBER	FRACTURE	BEODING	OPAIN SIZE OFSTRBUTION	USCS	DEPTH W	אטות רונאטרסמוכ רונאטרסמוכ	SAMPLE DESCRIPTION	
X-	Run 1	3,0	C-1				Qf ^	-1 - -2- -3 -		dh. brn.; 708 med plote clay; and fn. Sand notherse, gravel, angular; stiff.	
X-1	DR.	NR NR	-	569 55			0.	-4- -5-	0	COLLUVIUM	
	ans DR	ho'	C-1 L-1 L-2	4				- 7 - - 8- 9	, , ,	5-N' LEAN CLAY of ERAVEL; V. du bon. 902 med, to high piste. clay; 208 fn + csegrovel to 5; rounded; mast stiff; 108 fn sand PP= 0.741,3 gravelly layers TV = 5,2	
×××	Kyn 3	1.5	(-1	6				_10_ _11 _	000	BEDROK	
X-3	P	11	S-1	0		2	SSW	_12_ - 13 -	11 11	11-14.0' CLAYSTONE: med. gray wol pp grange: seventhed to soil; 4. soft; plstc.; Soil-lite Lean Clay w/ Sand;	⁵ 0?
	or	1.5	L-3 L-4 L-5	4710		e	SHA	-14- -15-		Moist; V, Stiff; PP= 2.1. ; locally Fe Dz Stained throughout,	
×3	Run 4	4.0	c^{-1}				-	-16- -17 -		40'-33,0' CLAYSTONE; med. grayy some orange; mod. wthrd.;	
X-4	DK I	15	-6 ·	86			-	-18-19 19-1	77.75	30ft; friable & week; locally Crushed C3 in clay matrix 75-18; 40° shear sev. Abrd; 51hs; grawl conce	neti
NOTE		neral: L						ows: e instead of	18-18 % we	3,5 crushed, Procedure No. RMRS/OPS-PRO.101 ght. Revision 0	

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

	OCV SITE ROPEHOLE LOG PAGE 2 OF
ROCKY FLATS ENVIRONMENTAL TECHNOL Borehole Number:	Surface Elevation:
Location - North:East:	Area:
Date:	Total Depth: Project No.: 57378
Geologist:	Sample Type:
RMRS LOGGING SUPERVISOR APPROVAL	_ DATE Dry to 31' 7/14/04
JO., JO 3105 SINK 1 F. J YN 1 SE 1 S 1	SAMPLE DESCRIPTION
DK 158 26	vert frais Fe De coated,
1x5 Rm , C-1 -21 -	PP > 5
5 35 -22	crushed
3,5	
	23-24 extensively FCO2 stamed
1 24	241 horz bedding vert fracs
X6 Run 23 61 - 25-	Feoz filled.
	TOZ TITLEG.
2.5	
DR 03 1-9 30 -27 -	28' SS/CS
50 50 21	
KW / /C	
8 5.0 -31 -	
32-	
	of got asserted with any if
csuw 33	33'- 38' CLAYSTONE: Vidlegray; fres
34-	mad, hard; weak to mad strong
16-8 Run 1c-1	horiz, thinly laminoted bedding;
['q	no Fe Oz strins,
36-	
20	
38 +	- los los abise
39	Bachfilled w/ bentonne chips.

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

		<u>-</u>			- /				V SITE PODEHOLE LOC PAGE 1 OF 2]
ROC	CKY FL	ATS	ENVI	RONN	MENT	'AL T	ECHNO		1 211 F BOKEHOLE DOG	
Bore	hole Nun	nber: ,	B	L	st:				Surface Elevation:	
Local Date:	tion - Noi	29/	24						Total Dooth: 3/8.5	·
Geoi	ogist:	Ric	li He	Ideic	1		·		Company: Project No.: 57378	!
Drillir	ng Equip.	: <u></u>	ME-	75					Sample Type:	1
	RS LOGO ROVAL	GING	SUPE	RVIS	OR				DATE G.W @ 10.9 on 7/14/04	
3 3	_ Z =	Ē	T		Mõ	1_	· g	ñ		
OTO XOS	P S S S S S S S S S S S S S S S S S S S	No.	PACTUR ANGLE	AMGLE	GPAIN \$12 DISTPUBLITH	USCS	OEPTH FEET	50 50 E	SAMPLE DESCRIPTION	l
10 N	Z GZ		5 3	" `	8 5	, m	ō	Ē	Road Fill	
XIR	الم ال		1			CJF		Ċ	0'-3' GRAVELLY, CLAY: Medgray ~602)-
	un 40,	101		1		[*	- 1 -	سارا	0'-3' GRAVELLY, CLAY: medgray ~602 (4) med. plste day; ~ 20% for essegrand; ~	Che
	2 /41	7			'		: A	:	med plate dy; - 20% for essegrant; ~	> "
			1 .	1			一2一		20% for med sond; moist.	(wic
		1			'		-3-	<u>. </u>		tri
		1	1					ac	3-6' CLAYEY SANDY GRAVEL : H. brn ;	الإستار
X-2 R	~ 2.6/	7					-4-		(GC) 608 for + congraved zot sound select;	
1x-7	2 //		1	1			- 5 -		dompo	
1 1	- 142	1							COLLUVIUM	
		1		1		ac	-6-	Q _c	6-11.5 LEAN CLAY U/ SAND: olive to de.	
	1			1		30	_ 7 _	سرح .	(CL) brn; 882 md. plate clay joic sand larger ran oriented; moist; Stiff (PP=1.8); gravelly e depth	bools
		l							ariental wit still Go-18 gravely e depth	,
 	1-27	11.1	2	†	1		<i>−8−</i>	QC	hecomes"	
100	1.5	12	244				9 _	W.	8-11.51 SANOY CLAY WI GRAVEL: ILL. brn;	
	7.5	L-3	4]						
Ru	n 2.d						-10-		(CL) GOR mediptie (104) action of moist gravel; 208 for to ese sand; moist	
X.2	3 3.0	C-(11		graver	•
1	270						_ // _		9.5'-11.5' ~ 10t fn. gravel	1
01	2 1,5	14	34] ;		CSSW	12	CSSW	11' PP= 1.3	
	1,5	16	6				10	٠.	11.5'-17.5' BEDROCK	
 	- 		<u> </u>	1			- 13 -		CLAYSTONE, DIM GRAP IMOTOGET.	l .
l o	2.0	52]			14		preddish bens; sev. whod to resid soil	ľ
	2.4	ט	150		.]	ı	-	•	V. soft; plstc.; soil like qualitier-	
	J. T	Ì	PSI			ŀ	- 15 -		LEAN CLAY WI SAND; 908 mad plate	1.
					1		1/		clay) log in send; le a stommen	
X-3 R	V 3.6	C-1			- 1		-/6-		veliks, calich nodules, must, rare good	(183)
I L						- }	- /7 -		cly , 10% for send; fect storesing relies, calich modules; must; rore grand firm (PF = 0.9)	"
^		Tal	4		· -		16	TH.	17.5 pp= 1.0 CLAYSTONE: Mod. withrd.;	<i>L</i> ₁
DA	\ '?\!	1-8	8		ľ	SHW	-/ δ ;	型	- the terms of the	1
יען	1/1/2	19	13	- 1	- 1	Ŀ	19	加	33 dry soft; friable; brecciated; crimpler	
-DF	2 1.4	LIO	13		_			計	6-1/2-14 angular pieces; locally FEDZ.	
	1.5	<u> </u>					20 1	44	Procedure No. RMR S/OPS-PRO.101	1

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate tootage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

rocedure No. RMRS/OPS-PRO.101 Revision 0

Date effective: 12/31/98

RC	OCK	FLA	TS E	NVIR	ONM	IENT	AL T	ECHNO	LOG	Y SITE BOREHOLE LOG PAGE Z OF 2
Во	rehole	Num	ber: _ h:	D /	Eas	<u>=</u>				Area:
	ation le:					^·				Fotal Depth: 36, 5' Company: Project No.: 57378
Ge	ologis	τ:								Company: Project No.:
<u> </u>	<u>-</u>	quip.:							<u> </u>	Sample Type.
1	IRS I PRO		ING S	SUPE	RVISC	OR			·	DATE
TOP/BOTTOM OF COPE IN BOX	OP/BOTTOM OF INTERVAL	ININTERVAL FIELD	SAMPLE	FRACTURE	BEDDING	GRAIN SIZE DISTRIBUTION	USCS	DEPTH IN FEET	SOIU LIIMOLOGIC LOG	SAMPLE DESCRIPTION
F 1000	DR	<u> </u>	L 12	27	}	 	CSMW			20-205' locally FeOz showed
X-3	Run	3.5	C-1				C 31.V	-21-		intensely frace. ; sub horiz bedding
 ~	5	//	'						3-11	Feoz stain bedding planes; mostly
•		3.5						<u> </u>	影	orange; some gray; locally crushed.
	ł							-23 -	学	- · · · · · · · · · · · · · · · · · · ·
X-4							1			70.5-21,5 V, soft to soft pp-0.2
^ \.		-		•			-	-24-	17.	mechanically distaurhed from over drilling
		5.0]				25-		cal had mixed of gravel.
	Run	100]						1	21.5'-23' crushed
İ	6	6.0		ŀ				-26-	1	
•		1				ľ		- 27 -		24-26' subvert. frat, Fooz filled, water
'		١.					•			24 becomes mod fraid, locally crushed;
				·				28	1	smooth sfcs/slus on frais.
X-5		l						_29 -]	27' RP+5
	Run	1	1	'				-27-]	
·	7	25						30-	-	28,5% minor FeUz
	1	2.5							1	
			ļ	, ,				- 31 -	1	
	OR	1.3	<u>13</u>	36				-3z-	4	
		1.5	LIS	42			1			33'-36,5' CLAY STONE; dhe gray; slightly
	<u> </u>	 		· · · ·			CSUL	- 33 -	1	uthrd.; soft to mod hard; weak to
X-6	Run					·		_34_]	modistrong; mod fracidij lam inated;
· .	8								1	Mod. Spring, visor trace of lam marker,
		.		·				-35 -	-	dry; acc rare sands time beds.
								9.		36'-3615' FeOz stained
								-36-		,
			•		•			_ 37 _		Bacutilled w/ bentonite chips,
									.	
					I			38	1	
		.]	1			_ 39 _		
				. 1						
- 1			1	- 1	- 1			150	i	

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

	OCK	V FI.	ATS I	NVI	RONI	MENT	ΓAL Ï	ECHNO	LOG	Y SITE BOREHOLE LOG PAGE _ OF
	oca.	. Nur	ber:	ZX	hac					Surface Elevation: ~5950
	cation			<u> </u>		ıst;				Area: Woman Creek
	ate:		777	04						Total Depth: 25°
G	ologis	-1·		k H	eldri	ck				Company: Project No.: 57378
0,	illing E	ouio.		MR			erm	in Ria		Sample Type:
			SING	CHPE	RVIS	OR	-		11	
	PRC									DATE G. W. @ 9.21 on 7/14/04
-	1-	w_ (=		T] w Z			T v	
₽w×	É	1880	34 2	5 =	2 2	25	5 2	PTH	30 E	SAMPLE DESCRIPTION
88	0 0 g			ANGLE ANGLE	REDDIN	GRAIN SE	USCS	DEPTH	SER	SAMPLE DESCRIPTION
5 5 2	P 2	E ≥	() & Z	1 =	1	9 5			<u> </u>	collumn Qc Qla
	1.	181					M		7	0-15 LEAN CLAY; med brn: 908 med Ast
1x-1	Run	14/	\C-\	1 -	1.		(V)5	1 1	/	Les de la Sunda Colonia
1	1	15					De		خنسا	(CL) clay ilox on some; moist; stiff pp: 14
			حرا				, ,	_ ~_		1.5-810 SANDY CLAYULGRAVEL!
1 3			<i>Y</i> .	1		1		7		1,5-8,0 SAND CONTACT 302
	88	b			1	1		L3 -	10	(CL) wed bin: 508 med piste clay i 30%
1 2		.].				1				forese grant 3"; 20% for 100
1 /					1		1	L 4-	K-	and I have hadden
1				1					<u> </u>	sand, damp; ou cobbles bobbes.
			-		1	88c		- 5 -	┨	1 4 1
}		bel			L_	 	1	/		slide Zone!
X-2	Rur	13/	, .	r -	-	1	1	<i> \(\varphi -</i>	 	6-8'N LEAN CLAT; med. gray; 900
~~	2	150		10	22	151		17	=	med plate clay 3102 fi said locally Froz stained
1	1	**	B8C	'		51		- / -	1	- eves
1	1	١.	7-	l ·	12.4			2		Moist i V. Stiff, PP=2, 3tsf.
1		1	10'	1		500	/ \	T 0 -	200	1 / ' _ ' ALLUVIUM - AND I
	İ		core			Qa	140	L 9 -	KXX.	8.0 14.5 SANDY CLAYET GRAVEL I dk
		ļ.	Box						<u> </u>	
<u> </u>			<u></u>		-	1		-10-	-0	brn) toll randed for-congrands
	DR	25	الحا	108	i	1		1.	0:	30% highpiste clay; 20% fato
	lh.c	15	}	10				- 11 -	۱, °	30% Might City
1		- 67	L22		ł	1		1	0.	ese sand; wet; med dense, 9-109 PP=0.7 > TV=2.0
]	OR.	P.2	1-A-	30/5	1	1		- 12-	1 6	9-103 PP=0.7 > 70=210
1 .	<u> </u>	1.0	 	377	1		1	1	18	13'- Zoh Sand, 200 clay
X-3	Run	15.	C-1		1 2	80		- 13 -	1:0	
	3	7.5	ļ					100	10	REDROCK No slide plane
1		-11		TT	DR	N.R	-	<u> - /4-</u>	00	1
	DR	0.6	13	15	DR 5	NA'LL .	C5GW	L 15-	1	14.5-18 CLAYSTONS, med gray worange
l '	1	4,5	1	12	1 40	Į .	1	厂/"-	1 -	wt. A Mottlins; v. soft to soft;
			tı '-	त्रुव १५० १५०	10	1.	1	11	-	Alb / Call as a lit
	DR	NR	 	30	2.1	92	1	<u> </u>	1 -	pisce to tricate, crushed
	ł].	,	38-	1			17	_	soil-like places in soft clay matrix;
	— —		· ·		2.4	P_	ł	厂′′「	-	plate to frieble; crushed: soil-litte pieces in soft clay matrix; whistiff med-high play pp=2.4
				l 	<i>U</i> .	(100,		18		Most Buet
225	0.5					2.0	Cally	70-		18'-22' CLAYSTONE: dle gray oil some overge;
Bac	R25] .			C4	2.0		L 19 -		18'-22 CLAYSTONE: the gray oil some overage; modiviting; Soft; weak; Fe U: on from.
KL										S.Es. laminated bedfor jintensely fract;
								20		A CONTRACT DOCK BY JUNCKERY JUNCKY

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate tootage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98 Page 27 of 28

	<u> </u>			<u></u>		(T) b 172	AT T	ECUNO	LOGY	V SITE BOREHOLE LOG PAGE 2 OF 2
l n-		Alum	hor	RX				ecui40	200	Y SITE BOREHOLE LOG Surface Elevation:
10	renoi∈ ⇔ation	- Nort	h:	00	Eas	st:				Area:
l Da	te:					·				Total Depth: Project No.: 57378
Ge	ologis	t:					· ·			Company: Project No.:
		quip				30				
	ARS I PRO		ING S	SUPE	KVISC	JK			<u> </u>	DATE
OF CORE	TOP/BOTTOM OF INTERVAL	HINTERVAL (FIELD ASUREMENT)	SAMPLE	FPACTURE	BEDDING	GRAIN SIZE DISTRIBUTION	VSCS	DEPTH IN	SOIU LITHOLOGIC LOG	SAMPLE DESCRIPTION
		5.0		-	-		CSM	•	CSHW	
X-3	25/20	1//	ر ا				U	-21 -		
1~ -	3	5.0							_:	6.1
						,	CSUL	-22-	CSUL	22:25 CLAYSTONE dh gray, Trent
								-23 -		22:25 CLAYSTONE dh gray; fresh unweathered, no discoloration; soft to mod hard; weak to mod strong; thinly laminated a 20°; sitly
] .						Hely laminated a 200 1 chil.
1								_24_		carbanaceus; in place; little fracid.
	L			/		<u> </u>	3.5	25_		1
						ľ				Backfilled w/ bentonite chips.
								-26-		
					. 1			_ 27 -		
								28		
			·	l				_29 _	1	
	,					7				
	·	1						-30-	1	
				·				- 31 -		
								Γ΄΄ -		
								<u>32</u> -	ł	
		1								
						·		- 33 -	1	
								34		
	l					1		-		
								- ۲۶ −		
								36		
·										
								_ 37 _		
								20_		
								00		
				ł	1			_39 _		
				.	i			18.0		

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate tootage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

Revision 0

Page 27 of 28

Date effective: 12/31/98

Bo Lo Da	OCK prehole pcation ate: eologis	Num - Nort 7	ber: _ <u> 6 0</u> 3	B=	9 + 57 leva	<u>(B</u>	ALT 9a o	ECHNO (Aset)		Surface Elevation: ~5950 Area: Woman Creek Company: Project No.: 57378	
Dr	illing E	quip.:	_41	Terri	and 1	CME	<u>-75</u>			Sample Type:	
	MRS I		ING	SUPE	RVIS	OR .		· · ·		DATE GWe 4.4 on 7/14/04	
TOP/BOTTOM OF CORE	TOP/BOTTOM OF INTERVAL	FEET OF COPE ININTERVAL (FIELD	SAMPLE	FRACTURE	BEDDING	GPAIN \$12E DISTREGUTION	USCS	DEPTH IN	301/ 111HOLOGIC 100	SAMPLE DESCRIPTION ALLUVIUM	
*1	Run	50'	C-1	0		10,	Qa	- 1 -		0-6.7' SANDYLEAN CLAY; V. dhbrn; -702 med, plate day; 30% for 6 cse (L) sond) moist; firm; pp-0.5-1.0	
				Opsi		2,4	. 2'	-2- -3-	. (TV=4.0, wete 4.5; occ. rounded growl to 18".	
				DR.	1-10 1-2 1-3	7	1.5	-4- -5-			
X-2	DR	1,2/	L-1 L-2 L-3	23				_6_		6 hecomes growlly; 508 clay; 30 2 sond; 20 8 fn. growel.	
	¢	1,5	45	26			Casw	- 7 - - 8-	cssw	BEDROCK CLAYSTONE; mrd.gray; sev.	
	ÖR	1.3	L-6 L-7 L-8	13				- 9 - -10-		nothers to residual soil; v, soft; alidus nodules; plste; no bedding: Sail-like bean to	•
<u> </u>	P	1.5	S-T	(3) (3)			CSHW	_ // _	CSMU	Fot Clay ul sand: PP=2.2; TV=7.0	•
X-3	Run 2	4.0	C-1					12 13	Corin	9' becomes crushed in day matrix. PP=1.5 TV=7	
		4,0						14	·	111 Shelby refusal. 11-15 gome slus on free sfes; water	
 								- 15-		on frac sfcs	•
χщ	Run 3	60	C-		·			16 17		11-23 CLATSTONE; med gray; Modulhid; soft; weak; faint thinly laming	; d20
		210		-		-		-18-		wedding; Crushed pieces in clay motrix; some alles on frac. sfes. PP=5+.	•
								20		Some Fauz stains on vert. fracs.	
TON	ES: G	eneral:	uscs	is mod	lified fo	r this lo	og as fo	ollows:		Procedure No. RMRS/OPS-PRO.101 Revision 0	. -

Materials amounts are estimated by % volume instead of % weight. (1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate tootage measurements not possible.

Lo Da Ge	OCK orehole cation ite: eologis illing E	Num - Nort	ber: _ h:/	NVIII B 9		IENT	ALŢ	ECHNO		Y SITE BOREHOLE LOG Surface Elevation: Area: Total Depth: Company: Project No.: 57378 Sample Type:
	MRS I		ING S	UPE	RVISC	OR				DATE
OF CORE	3 ,	S A L	BAMPLE NUMBER	FRACTURE	BEDDING	GRAIN \$12E DISTRIBUTION	USCS	DEPTH IN	SOIU LITHOLOGIC LOG	SAMPLE DESCRIPTION
X	aur	45/50 5.	v					-21 - -22- -23 - -24	CSMV	23'-25' CLAYSTONE; black; unweathered soft to mod, hard; mod, strong; thinky laminated; in place.
								-25- -26- -27- -28- -29- -30- -31- -32- -33- -35- -35- -37- -38- -39-		

Materials amounts are estimated by % volume instead of % weight.

- (1) Badly broken core, accurate footage measurements not possible.
- (2) Core breaks cannot be matched, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

U.S. DEPARTMENT OF ENERGY ROCKY FLATS PLANT

Bo Lo Da Ge Dr	oreho ocation ate: eologi illing	le Nu n - Ng 7/ ist: Equip	mber: 1/04 Qu	B		st:	TAL 7	TECHN	OLOG	Sy SITE BOREHOLE LOG Surface Elevation: Area: Total Depth: Company: Sample Type:
4	PPRO									DATE G.Wie 19.0 m7/14/04
TOP/BOTTOM OF CORE IN BOX	TOP/BOTTOM OF	FEET OF COPE IN INTERVAL	SAMPLE	FRACTURE	BEDDING	GPAIN \$12E DISTRIBUTION	USCS	DEPTH IN	SOIL	SAMPLE DESCRIPTION Waste Fill
X-2 X-2	Russ Russ Russ	4: 1.4	1	425			Qc	- 1 2 - 3 - 4 - 5 - 7 - 8 10 - 12 18 - 18	000 / To TA	O'-4' SANDY GRAVELLY CLAY; dh. b. 1t. bm. (CL) Varies; 402 mid. plste clay; 20% fn-med sand; 30% fn-congressed to 4; moist; metal chards e 1.5.
4-	43					_ -		- 19 - -20	SHA	

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate footage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

U.S. DEPARTMENT OF ENERGY ROCKY FLATS PLANT

Boo Loc Dat Ge	rehole ation te: ologis	Num - Nort	ber: _ h:	15 K	CONM		ALT	ECHNO) 	Y SITE BOREHO Surface Elevation: Area: Otal Depth: Company: Cample Type:	Project No.: 57378
	IRS L PRO		ING S	SUPE	RVISC	OR	:	·.		DATE	
OP/BOTTOM OF COPE IN BOX	TOP/BOTTOM OF INTERVAL	EET OF CORE ININTERVAL IFIELD EASUREMENT	SAMPLE	FRACTURE	BEDDING	GRAIN SIZE DISTRIBUTION	USCS	DEPTH ON	SOIU LITHOLOGIC LOG		SAMPLE DESCRIPTION
X-4	5	50,0	C-1				Cany	-21 - -22-		Ь	increased sand content in CS medding e10-200; modifeOz
X -5								-23 - -24-		24'	fn-randel grave (3/4".
4	K5 (6	5.0	c-\			• • ;	Canm	- 25 - 26 - 27 -	1/2	26.5-34	CLAYSTONE; blk.; unwarth off; weak; no apparent bedding
4		- 1				•		-28- -29 -	1	e th	rushed; no fear. PP>5; becomes with leminated widepoth
	10	5.0 5.0	c-1					-30- -31 -		she	27,5' sheared an 50°, slicks ar sfe. 9 [34" thinly laminated.
χЛ	٠					·		-32- -33-		2	4 - 24 Citik Inmittee
								-3 4- -35 -		Bachfilled	w bentomite chips.
								36 37			
	4							_38_ _39 _			

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

Badly broken core, accurate tootage measurements not possible.
 Core breaks cannot be matched, accurate tootage measurements not possible.

Procedure No. RMR S/OPS-PRO. 101

Revision 0

Date effective: 12/31/98

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE BOREHOLE LOG Borehole Number: P-11 Location - North: Surface Elevation: Location - North: Area: Near Women Creek Total Depth: 14 Company: Project No.: 57378 Drilling Equip:: CME-75 Sample Type:												
RMRS LOGGING SUPERVISOR APPROVAL DATE Dry 6 14' on 7/14/04												
TOP/BOTTOM OF COPE IN BOX TOP/BOTTOM OF INTERVAL FEET OF COPE INTERVAL INTE	BEDDING ANGLE GRAIN \$1.2E DISTRBUTION	USCS SYMBOL OEPIN ON	SOUL LITHOLOGIC	SAMPLE DESCRIPTION COLLUVIUM								
X-1 Rm 49 C-1 DR 1/3 C-1 40 X-2 Run 5/5 C-1 DR 1/8 1/8 23 32 X-2 Rm3 3/2 C-1 DR 1/5 L-2 23 1/5 L-3 37 X-3 Run 5/5 C-1 X-3 Run 5/5 C-1		Qc - 1 - 2 - 3 - 4 - 5 - 6 - 7 - 8 - 7 - 10 - 11 - 12 - 13 - 11 - 12 - 13 - 11 - 12		GN 802 fn. to esegravel, rounded; cobbbi to 6; dry BEDROCK 7.5-9' CLAYSTONE: Med. gray mottled Lt. 3ev, whird to presiduel soil; med. plsty. j damp; caliche nodule 9-12.5' CLAYSTONE: med. gray mottled orange mod. whird some FeOz staining along bedding + frac sfc; Soft friable to weak; dry. 12.5-14' CLAYSTONE! dk. gray to blk; unwthrd.; mod. hd.; wh to mod. strong; dry.								
		- 15 16 17 18		Backfilled w/ benbonits chips.								
		-19		D. advan No. PMPS/OPS-PRO 101								

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate lootage measurements not possible. (2) Core breaks cannot be matched, accurate footage measurements not possible.

Revision 0

Date effective: 12/31/98 Page 27 of 28

U.S. DEPARTMENT OF ENERGY ROCKY FLATS PLANT

Bo Lo Da Ge	orehok ocation ate: eologis	le Num	ATS E	<u>R</u>	Eas	ıst:			Surface Elevation: Area: Total Depth: Project No.: 57378 Sample Type:			
		LOGO	SING S	SUPE	RVISC	OR .			DATE			
TOP/BOTTOM OF CORE	2	- F. B. F.	FI	FRACTURE	BEDDING	GRAIN \$12E DISTRIBUTION	USCS SYMBOL	DEPTH IN	SOIU LITHOLOGIC LOG			
	01					50		-212223242526272829 -				
								-313233343536373839 -				

NOTES: General: USCS is modified for this log as follows:

Materials amounts are estimated by % volume instead of % weight.

(1) Badly broken core, accurate tootage measurements not possible.

(2) Core breaks cannot be matched, accurate footage measurements not possible.

Procedure No. RMRS/OPS-PRO.101

Revision 0

Date effective: 12/31/98

APPENDIX B

GEOTECHNICAL LABORATORY TEST DATA

APPENDIX B


GEOTECHNICAL LABORATORY TEST DATA


Geotechnical laboratory testing for Phase 2b work was performed by Advanced Terra Testing, Inc. All test data is provided in a separate volume to this memorandum.


Submitted to the Colorado Department of Public Health and Environment and the U.S. Environmental Protection Agency on September 9, 2004.


APPENDIX C


GEOLOGIC MAP AND CROSS SECTIONS





















FILE NAME: j:\...\rckyflats\g1g1.dwg

6050

5950

5900

5850




OLF study area, waste extent, current surface topography, and vertical profile locations.


A Vertical Profile Location - Initially defined in Metcalf & Eddy Report (9/1995)

► Profile View Direction


Integrated Hydro Systems, LLC




- 1) Horizontal and Vertical Units are feet
- 2) Vertical exaggeration is 3x
- 3) Wet Year water levels based on 100-year climate sequence (see OLF groundwater tech report for details).



- 1) Horizontal and Vertical Units are feet
- 2) Vertical exaggeration is 3x
- 3) Wet Year water levels based on 100-year climate sequence (see OLF groundwater tech report for details).



- 1) Horizontal and Vertical Units are feet
- 2) Vertical exaggeration is 3x
- 3) Wet Year water levels based on 100-year climate sequence (see OLF groundwater tech report for details).



- 1) Horizontal and Vertical Units are feet
- 2) Vertical exaggeration is 3x
- 3) Wet Year water levels based on 100-year climate sequence (see OLF groundwater tech report for details).

APPENDIX E

STABILITY ANALYSES

M&E SECTION B-B' - STATIC


18


EXISTING CONDITIONS

ROCKY FLATS OLF - M&E SECTION B - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC All surfaces evaluated. C:BEACS.PLT By: STAN KLINE 10-22-04 2:12am X-Axis (ft) **Y-Axis** (£


Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION B - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC Ten Most Critical. C:BEACS.PLT By: STAN KLINE 10-22-04 2:12am






ROCKY FLATS OLF - M&E SECTION B - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC Ten Most Critical. C:BEHCS.PLT By: STAN KLINE 10-23-04 6:56pm




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION B - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:BEASS.PLT By: STAN KLINE 10-22-04 1:53am




Factors Of Safety Calculated By The Modified Janbu Method


ROCKY FLATS OLF - M&E SECTION B - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC Surface #1-EASS.OUT. C:BEASSSP.PLT By: STAN KLINE 10-22-04 1:55am




PCSTABL5M/SI FS = 1.44 Theta = 9.49 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices




ROCKY FLATS OLF - M&E SECTION B - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC Surface #1-EHSS.OUT. C:BEHSSSP.PLT By: STAN KLINE 10-22-04 1:27am




ROCKY FLATS OLF - M&E B 18% GRD - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC All surfaces evaluated. C:BGACS.PLT By: STAN KLINE 10-22-04 2:19am



ROCKY FLATS OLF - M&E B 18% GRD - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC Ten Most Critical. C:BGACS.PLT By: STAN KLINE 10-22-04 2:19am




ROCKY FLATS OLF - M&E B 18% GRD - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC All surfaces evaluated. C:BGHCS.PLT By: STAN KLINE 10-25-04 12:10am




Factors Of Safety Calculated By The Modified Bishop Method

7

ROCKY FLATS OLF - M&E B 18% GRD - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC Ten Most Critical. C:BGHCS.PLT By: STAN KLINE 10-25-04 12:10am





ROCKY FLATS OLF - M&E B 18% GRD - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:BGASS.PLT By: STAN KLINE 10-22-04 12:13am



Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E B 18% GRD - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC Surface #1-GASS.OUT. C:BGASSSP.PLT By: STAN KLINE 10-22-04 12:20am






Factors Of Safety Calculated By The Modified Janbu Method

125


ROCKY FLATS OLF - M&E B 18% GRD - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC Surface #1-BGHSS.OUT. C:BGHSSSP.PLT By: STAN KLINE 10-25-04 12:15am



18% REGRADE WITH BUTTRESS CONDITION


2

ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC All surfaces evaluated. C:BBACS.PLT By: STAN KLINE 10-22-04 2:26am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC Ten Most Critical. C:BBACS.PLT By: STAN KLINE 10-22-04 2:26am




30


ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC All surfaces evaluated. C:BBHCS.PLT By: STAN KLINE 10-22-04 2:42am




Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC Ten Most Critical. C:BBHCS.PLT By: STAN KLINE 10-22-04 2:42am






ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC Surface #1-BASS.OUT. C:BBASSSP.PLT By: STAN KLINE 10-22-04 2:05am





ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC Surface #1-BHSS.OUT. C:BBHSSSP.PLT By: STAN KLINE 10-22-04 1:37am




PCSTABL5M/SI FS = 1.65 Theta = 8.87 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

M&E SECTION C-C' – STATIC


EXISTING CONDITIONS

ROCKY FLATS OLF - M&E SECTION C - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC All surfaces evaluated. C:CEACS.PLT By: STAN KLINE 10-23-04 10:18pm




Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E SECTION C - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC Ten Most Critical. C:CEACS.PLT By: STAN KLINE 10-23-04 10:18pm




ROCKY FLATS OLF - M&E SECTION C - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC All surfaces evaluated. C:CEHCS.PLT By: STAN KLINE 10-23-04 9:37pm



ROCKY FLATS OLF - M&E SECTION C - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC Ten Most Critical. C:CEHCS.PLT By: STAN KLINE 10-23-04 9:37pm




ROCKY FLATS OLF - M&E SECTION C - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:CEASS.PLT By: STAN KLINE 10-23-04 10:24pm




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E SECTION C - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC Surface #1-CEASS.OUT. C:CEASSSP.PLT By: STAN KLINE 10-23-04 10:25pm




PCSTABL5M/SI FS = 1.51 Theta = 9.87 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E SECTION C - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:CEHSS.PLT By: STAN KLINE 10-23-04 7:19pm




ROCKY FLATS OLF - M&E SECTION C - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC Surface #1-CEHSS.OUT. C:CEHSSSP.PLT By: STAN KLINE 10-23-04 7:23pm




18% REGRADE CONDITION

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC All surfaces evaluated. C:CGACS.PLT By: STAN KLINE 10-23-04 10:20pm




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC Ten Most Critical. C:CGACS.PLT By: STAN KLINE 10-23-04 10:20pm



Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E C 18% GRD - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC All surfaces evaluated. C:CGHCS.PLT By: STAN KLINE 10-23-04 9:56pm




Factors Of Safety Calculated By The Modified Bishop Method

150

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC Ten Most Critical. C:CGHCS.PLT By: STAN KLINE 10-23-04 9:56pm




ROCKY FLATS OLF - M&E C 18% GRD - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:CGASS.PLT By: STAN KLINE 10-23-04 10:26pm



Factors Of Safety Calculated By The Modified Janbu Method

152


ROCKY FLATS OLF - M&E C 18% GRD - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC Surface #1-CGASS.OUT. C:CGASSSP.PLT By: STAN KLINE 10-23-04 10:29pm



PCSTABL5M/SI FS = 1.65 Theta = 9.43 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices


12

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:CGHSS.PLT By: STAN KLINE 10-23-04 7:42pm



Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC Surface #1-CGHSS.OUT. C:CGHSSSP.PLT By: STAN KLINE 10-23-04 8:02pm




PCSTABL5M/SI FS = 1.59 Theta = 9.46 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices


18% REGRADE WITH BUTTRESS CONDITION

12/2

ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC All surfaces evaluated. C:CBACS.PLT By: STAN KLINE 10-23-04 10:22pm




ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC Ten Most Critical. C:CBACS.PLT By: STAN KLINE 10-23-04 10:22pm




PCSTABL5M/SI FSmin = 1.83 X-Axis (ft)
Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC All surfaces evaluated. C:CBHCS.PLT By: STAN KLINE 10-23-04 10:03pm




Factors Of Safety Calculated By The Modified Bishop Method




ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:CBASS.PLT By: STAN KLINE 10-23-04 10:31pm



ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC Surface #1-CBASS.OUT. C:CBASSSP.PLT By: STAN KLINE 10-23-04 10:33pm




ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:CBHSS.PLT By: STAN KLINE 10-23-04 9:01pm




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC Surface #1-CBHSS.OUT. C:CBHSSSP.PLT By: STAN KLINE 10-23-04 9:03pm




M&E SECTION D-D' - STATIC

ROCKY FLATS OLF - M&E SECTION D - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC All surfaces evaluated. C:DEACS.PLT By: STAN KLINE 10-24-04 2:08am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION D - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC Ten Most Critical. C:DEACS.PLT By: STAN KLINE 10-24-04 2:08am




PCSTABL5M/SI FSmin = 1.31 X-Axis (ft)
Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION D - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC All surfaces evaluated. C:DEHCS.PLT By: STAN KLINE 10-24-04 12:58am




Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E SECTION D - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC Ten Most Critical. C:DEHCS.PLT By: STAN KLINE 10-24-04 12:58am




ROCKY FLATS OLF - M&E SECTION D - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:DEASS.PLT By: STAN KLINE 10-24-04 2:22am



ROCKY FLATS OLF - M&E SECTION D - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC Surface #1-DEASS.OUT. C:DEASSSP.PLT By: STAN KLINE 10-24-04 2:22am




ROCKY FLATS OLF - M&E SECTION D - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:DEHSS.PLT By: STAN KLINE 10-23-04 10:50pm



Factors Of Safety Calculated By The Modified Janbu Method


ROCKY FLATS OLF - M&E SECTION D - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC Surface #1-DEHSS.OUT. C:DEHSSSP.PLT By: STAN KLINE 10-23-04 11:23pm




PCSTABL5M/SI FS = 1.39 Theta = 9.31 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

18% REGRADE CONDITION


ROCKY FLATS OLF - M&E D 18% GRD - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC All surfaces evaluated. C:DGACS.PLT By: STAN KLINE 10-24-04 2:17am



ROCKY FLATS OLF - M&E D 18% GRD - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC Ten Most Critical. C:DGACS.PLT By: STAN KLINE 10-24-04 2:17am




ROCKY FLATS OLF - M&E D 18% GRD - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC All surfaces evaluated. C:DGHCS.PLT By: STAN KLINE 10-24-04 1:17am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E D 18% GRD - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC Ten Most Critical. C:DGHCS.PLT By: STAN KLINE 10-24-04 1:17am




PCSTABL5M/SI FSmin = 1.60 X-Axis (ft)
Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E D 18% GRD - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:DGASS.PLT By: STAN KLINE 10-24-04 2:24am




ROCKY FLATS OLF - M&E D 18% GRD - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC Surface #1-DGASS.OUT. C:DGASSSP.PLT By: STAN KLINE 10-24-04 2:26am




PCSTABL5M/SI FS = 1.61 Theta = 9.29 X-Axis (ft) Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E D 18% GRD - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:DGHSS.PLT By: STAN KLINE 10-23-04 11:19pm




ROCKY FLATS OLF - M&E D 18% GRD - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC Surface #1-DGHSS.OUT. C:DGHSSSP.PLT By: STAN KLINE 10-23-04 11:21pm



PCSTABL5M/SI FS = 1.55 Theta = 9.36 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

18% REGRADE WITH BUTTRESS CONDITION


ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC All surfaces evaluated. C:DBACS.PLT By: STAN KLINE 10-24-04 2:14am



Factors Of Safety Calculated By The Modified Bishop Method


28

ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 20 deg - W/AVEGW - CIRCULAR - STATIC Ten Most Critical. C:DBACS.PLT By: STAN KLINE 10-24-04 2:14am




PCSTABL5M/SI FSmin = 1.70 X-Axis (ft)
Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC All surfaces evaluated. C:DBHCS.PLT By: STAN KLINE 10-24-04 1:48am




ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 20 deg - W/HIGHGW - CIRCULAR - STATIC Ten Most Critical. C:DBHCS.PLT By: STAN KLINE 10-24-04 1:48am




Factors Of Safety Calculated By The Modified Bishop Method

188

ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:DBASS.PLT By: STAN KLINE 10-24-04 2:28am




ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 20 deg - W/AVEGW - SLIDING BLOCK - STATIC Surface #1-DBASS.OUT. C:DBASSSP.PLT By: STAN KLINE 10-24-04 2:30am



Factors Of Safety Calculated By Spencer's Method of Slices


150

ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC All surfaces evaluated. C:DBHSS.PLT By: STAN KLINE 10-23-04 11:58pm




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 20 deg - W/HIGHGW - SLIDING BLOCK - STATIC Surface #1-DBHSS.OUT. C:DBHSSSP.PLT By: STAN KLINE 10-24-04 12:02am




M&E SECTION B-B' - PSEUDOSTATIC

ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g
All surfaces evaluated. C:BEAC06.PLT By: STAN KLINE 10-24-04 3:46am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g
Ten Most Critical. C:BEAC06.PLT By: STAN KLINE 10-24-04 3:46am




ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.02g All surfaces evaluated. C:BEACO2.PLT By: STAN KLINE 10-24-04 3:45am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.02g Ten Most Critical. C:BEAC02.PLT By: STAN KLINE 10-24-04 3:45am




ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g
All surfaces evaluated. C:BEHC06.PLT By: STAN KLINE 10-26-04 12:05am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g
Ten Most Critical. C:BEHC06.PLT By: STAN KLINE 10-26-04 12:05am




ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.01g All surfaces evaluated. C:BEHC01.PLT By: STAN KLINE 10-26-04 12:04am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.01g
Ten Most Critical. C:BEHC01.PLT By: STAN KLINE 10-26-04 12:04am




PCSTABL5M/SI FSmin = 1.02 X-Axis (ft)
Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g All surfaces evaluated. C:BEAS06.PLT By: STAN KLINE 10-24-04 3:53am




Factors Of Safety Calculated By The Modified Janbu Method


ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g Surface #1-BEAS06.OUT. C:BEAS06SP.PLT By: STAN KLINE 10-24-04 3:55am



ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.01g All surfaces evaluated. C:BEAS01.PLT By: STAN KLINE 10-24-04 3:59am




ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.01g Surface #1-BEAS01.OUT. C:BEAS01SP.PLT By: STAN KLINE 10-24-04 4:00am




PCSTABL5M/SI FS = 1.04 Theta = 8.8 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices


ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g
All surfaces evaluated. C:BEHS06.PLT By: STAN KLINE 10-24-04 5:51pm




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g Surface #1-BEHS06.OUT. C:BEHS06SP.PLT By: STAN KLINE 10-24-04 5:54pm






ROCKY FLATS OLF - M&E SECTION B - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.009g Surface #1-BEHS01.OUT. C:BEHS01SP.PLT By: STAN KLINE 10-26-04 12:51am



PCSTABL5M/SI FS = 1.00 Theta = 8.1 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices


18% REGRADE CONDITION

ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g All surfaces evaluated. C:BGAC06.PLT By: STAN KLINE 10-26-04 12:02am



Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g Ten Most Critical. C:BGAC06.PLT By: STAN KLINE 10-26-04 12:02am



Factors Of Safety Calculated By The Modified Bishop Method


23

ROCKY FLATS OLF - M&E B 18% GRD - WCS=15 deg - W/AVEGW - CIRCULAR - 0.03g All surfaces evaluated. C:BGAC03.PLT By: STAN KLINE 10-26-04 12:01am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.03g Ten Most Critical. C:BGAC03.PLT By: STAN KLINE 10-26-04 12:01am




ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g All surfaces evaluated. C:BGHC06.PLT By: STAN KLINE 10-26-04 12:07am



Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g

Ten Most Critical. C:BGHC06.PLT By: STAN KLINE 10-26-04 12:07am




PCSTABL5M/SI FSmin = 0.85 X-Axis (ft)
Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.02g All surfaces evaluated. C:BGHC02.PLT By: STAN KLINE 10-26-04 12:06am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.02g Ten Most Critical. C:BGHC02.PLT By: STAN KLINE 10-26-04 12:06am




ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g All surfaces evaluated. C:BGAS06.PLT By: STAN KLINE 10-26-04 12:45am



Factors Of Safety Calculated By The Modified Janbu Method


JZO

ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g Surface #1-BGAS06.OUT. C:BGAS06SP.PLT By: STAN KLINE 10-26-04 12:46am




PCSTABL5M/SI FS = 0.88 Theta = 7.96 X-Axis (ft) Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.03g All surfaces evaluated. C:BGAS03.PLT By: STAN KLINE 10-26-04 12:43am




ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.03g Surface #1-BGAS03.OUT. C:BGAS03SP.PLT By: STAN KLINE 10-26-04 12:44am




Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E B 18% GRD - WCS= 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g All surfaces evaluated. C:BGHS06.PLT By: STAN KLINE 10-24-04 6:05pm




Factors Of Safety Calculated By The Modified Janhu Method

ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g Surface #1-BGHS06.OUT. C:BGHS06SP.PLT By: STAN KLINE 10-24-04 6:07pm




PCSTABL5M/SI FS = 0.85 Theta = 7.86 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.02g All surfaces evaluated. C:BGHS02.PLT By: STAN KLINE 10-24-04 6:02pm



Factors Of Safety Calculated By The Modified Janhu Method


ROCKY FLATS OLF - M&E B 18% GRD - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.02g Surface #1-BGHS02.OUT. C:BGHS02SP.PLT By: STAN KLINE 10-24-04 6:04pm



PCSTABL5M/SI FS = 1.03 Theta = 8.19 X-Axis (ft) Factors Of Safety Calculated By Spencer`s Method of Slices


18% REGRADE WITH BUTTRESS CONDITION

ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g
All surfaces evaluated. C:BBAC06.PLT By: STAN KLINE 10-26-04 12:03am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g
Ten Most Critical. C:BBAC06.PLT By: STAN KLINE 10-26-04 12:03am




ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g
All surfaces evaluated. C:BBHC06.PLT By: STAN KLINE 10-26-04 12:09am




Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g
Ten Most Critical. C:BBHC06.PLT By: STAN KLINE 10-26-04 12:09am




ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.05g All surfaces evaluated. C:BBHC05.PLT By: STAN KLINE 10-26-04 12:07am



ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.05g Ten Most Critical. C:BBHC05.PLT By: STAN KLINE 10-26-04 12:07am




ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g
All surfaces evaluated. C:BBAS06.PLT By: STAN KLINE 10-26-04 12:48am




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g Surface #1-BBAS06.OUT. C:BBAS06SP.PLT By: STAN KLINE 10-26-04 12:49am




ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.05g All surfaces evaluated. C:BBAS05.PLT By: STAN KLINE 10-26-04 12:47am




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.05g Surface #1-BBAS05.OUT. C:BBAS05SP.PLT By: STAN KLINE 10-26-04 12:48am




PCSTABL5M/SI FS = 1.05 Theta = 6.9 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g
All surfaces evaluated. C:BBHS06.PLT By: STAN KLINE 10-24-04 6:24pm




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g Surface #1-BBHS06.OUT. C:BBHS06SP.PLT By: STAN KLINE 10-24-04 6:27pm




ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.04g
All surfaces evaluated. C:BBHS04.PLT By: STAN KLINE 10-24-04 6:11pm



Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E B 18%W/BM - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.04g Surface #1-BBHS04.OUT. C:BBHS04SP.PLT By: STAN KLINE 10-24-04 6:13pm




PCSTABL5M/SI FS = 1.01 Theta = 7.89 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

M&E SECTION C-C' - PSEUDOSTATIC


EXISTING CONDITIONS

ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.01g All surfaces evaluated. C:CEAC01.PLT By: STAN KLINE 10-26-04 12:10am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.069 All surfaces evaluated. C:CEAC06.PLT By: STAN KLINE 10-26-04 12:11am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.01g Ten Most Critical. C:CEAC01.PLT By: STAN KLINE 10-26-04 12:10am




ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g

Ten Most Critical. C:CEAC06.PLT By: STAN KLINE 10-26-04 12:11am




ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g
All surfaces evaluated. C:CEHC06.PLT By: STAN KLINE 10-26-04 12:15am



Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g
Ten Most Critical. C:CEHC06.PLT By: STAN KLINE 10-26-04 12:15am



PCSTABL5M/SI FSmin = 0.80 X-Axis (ft)
Factors Of Safety Calculated By The Modified Bishop Method


256


ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.01g
All surfaces evaluated. C:CEHC01.PLT By: STAN KLINE 10-26-04 12:14am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.01g
Ten Most Critical. C:CEHC01.PLT By: STAN KLINE 10-26-04 12:14am






ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g Surface #1-CEAS06.OUT. C:CEAS06SP.PLT By: STAN KLINE 10-24-04 6:54pm




ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.02g All surfaces evaluated. C:CEAS02.PLT By: STAN KLINE 10-24-04 6:49pm




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.02g Surface #1-CEAS02.OUT. C:CEAS02SP.PLT By: STAN KLINE 10-24-04 6:51pm




PCSTABL5M/SI FS = 1.02 Theta = 9.42 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g
All surfaces evaluated. C:CEHS06.PLT By: STAN KLINE 10-24-04 7:15pm




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g Surface #1-CEHS06.OUT. C:CEHS06SP.PLT By: STAN KLINE 10-24-04 7:17pm




Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.01g
All surfaces evaluated. C:CEHS01.PLT By: STAN KLINE 10-24-04 7:12pm



Factors Of Safety Calculated By The Modified Janbu Method


ROCKY FLATS OLF - M&E SECTION C - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.01g Surface #1-CEHS01.OUT. C:CEHS01SP.PLT By: STAN KLINE 10-24-04 7:14pm



PCSTABL5M/SI FS = 1.04 Theta = 9.49 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices


18% REGRADE CONDITION

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g All surfaces evaluated. C:CGAC06.PLT By: STAN KLINE 10-26-04 12:12am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.04g Ten Most Critical. C:CGAC04.PLT By: STAN KLINE 10-26-04 12:12am




ROCKY FLATS OLF - M&E C 18% GRD - WCS=15 \deg - W/AVEGW - CIRCULAR - 0.04g All surfaces evaluated. C:CGAC04.PLT By: STAN KLINE 10-26-04 12:12am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g
Ten Most Critical. C:CGAC06.PLT By: STAN KLINE 10-26-04 12:12am




ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g
All surfaces evaluated. C:CGHC06.PLT By: STAN KLINE 10-26-04 12:17am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g Ten Most Critical. C:CGHC06.PLT By: STAN KLINE 10-26-04 12:17am




ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.03g All surfaces evaluated. C:CGHC03.PLT By: STAN KLINE 10-26-04 12:16am




268

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.03g Ten Most Critical. C:CGHC03.PLT By: STAN KLINE 10-26-04 12:16am




ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g
All surfaces evaluated. C:CGAS06.PLT By: STAN KLINE 10-24-04 7:01pm




Factors Of Safety Calculated By The Modified Janbu Method


ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g Surface #1-CGAS06.OUT. C:CGAS06SP.PLT By: STAN KLINE 10-24-04 7:03pm



ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.04g
All surfaces evaluated. C:CGAS04.PLT By: STAN KLINE 10-24-04 6:58pm




ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.04g Surface #1-CGAS04.OUT. C:CGAS04SP.PLT By: STAN KLINE 10-24-04 7:00pm




PCSTABL5M/SI FS = 1.00 Theta = 8.96 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g
All surfaces evaluated. C:CGHS06.PLT By: STAN KLINE 10-24-04 7:23pm




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g Surface #1-CGHS06.OUT. C:CGHS06SP.PLT By: STAN KLINE 10-24-04 7:24pm




275

ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.03g All surfaces evaluated. C:CGHS03.PLT By: STAN KLINE 10-24-04 7:20pm



Factors Of Safety Calculated By The Modified Janhu Method


ROCKY FLATS OLF - M&E C 18% GRD - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.03g Surface #1-CGHS03.OUT. C:CGHS03SP.PLT By: STAN KLINE 10-24-04 7:22pm




PCSTABL5M/SI FS = 1.01 Theta = 9.05 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

18% REGRADE WITH BUTTRESS CONDITION


ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g All surfaces evaluated. C:CBAC06.PLT By: STAN KLINE 10-26-04 12:13am



ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g
Ten Most Critical. C:CBAC06.PLT By: STAN KLINE 10-26-04 12:13am




ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g
All surfaces evaluated. C:CBHC06.PLT By: STAN KLINE 10-26-04 12:17am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g
Ten Most Critical. C:CBHC06.PLT By: STAN KLINE 10-26-04 12:17am




Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g
Ali surfaces evaluated. C:CBAS06.PLT By: STAN KLINE 10-24-04 7:05pm



ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g Surface #1-CBAS06.OUT. C:CBAS06SP.PLT By: STAN KLINE 10-24-04 7:08pm




ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g
All surfaces evaluated. C:CBHS06.PLT By: STAN KLINE 10-24-04 7:26pm



Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E C 18%W/BM - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g Surface #1-CBHS06.OUT. C:CBHS06SP.PLT By: STAN KLINE 10-24-04 7:28pm




PCSTABL5M/SI FS = 1.01 Theta = 7.66 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

M&E SECTION D-D' – PSEUDOSTATIC

EXISTING CONDITIONS


ROCKY FLATS OLF - M&E SECTION D - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.069 All surfaces evaluated. C:DEAC06.PLT By: STAN KLINE 10-26-04 12:20am




Factors Of Safety Calculated By The Modified Bishop Method

268

ROCKY FLATS OLF - M&E SECTION D - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g
Ten Most Critical. C:DEAC06.PLT By: STAN KLINE 10-26-04 12:20am




ROCKY FLATS OLF - M&E SECTION D - WCS = 15deg - W/AVEGW - CIRCULAR - 0.00g(STATIC)
All surfaces evaluated. C:DEACOO.PLT By: STAN KLINE 10-26-04 12:19am




Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E SECTION D - WCS = 15deg - W/AVEGW - CIRCULAR - 0.00g(STATIC) Ten Most Critical. C:DEACO0.PLT By: STAN KLINE 10-26-04 12:19am



ROCKY FLATS OLF - M&E SECTION D - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g
All surfaces evaluated. C:DEHC06.PLT By: STAN KLINE 10-26-04 12:25am




ROCKY FLATS OLF - M&E SECTION D - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g Ten Most Critical. C:DEHC06.PLT By: STAN KLINE 10-26-04 12:25am



ROCKY FLATS OLF - M&E SECTION D - WCS = 15deg - W/HIGHGW - CIRCULAR - 0.0g(STATIC)

All surfaces evaluated. C:DEHC00.PLT By: STAN KLINE 10-26-04 12:24am




Factors Of Safety Calculated By The Modified Bishop Method

ZZ


ROCKY FLATS OLF - M&E SECTION D - WCS = 15deg - W/HIGHGW - CIRCULAR - 0.0g(STATIC)

Ten Most Critical. C:DEHC00.PLT By: STAN KLINE 10-26-04 12:24am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E SECTION D - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g
All surfaces evaluated. C:DEAS06.PLT By: STAN KLINE 10-24-04 7:52pm




SE T

ROCKY FLATS OLF - M&E SECTION D - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g Surface #1-DEAS06.OUT. C:DEAS06SP.PLT By: STAN KLINE 10-24-04 7:53pm




PCSTABL5M/SI FS = 0.80 Theta = 8.42 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E SECTION D - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.01g All surfaces evaluated. C:DEAS01.PLT By: STAN KLINE 10-24-04 7:42pm




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E SECTION D - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.01g Surface #1-DEAS01.OUT. C:DEAS01SP.PLT By: STAN KLINE 10-24-04 7:44pm




PCSTABL5M/SI FS = 1.02 Theta = 8.76 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E SECTION D - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g
All surfaces evaluated. C:DEHS06.PLT By: STAN KLINE 10-24-04 8:27pm




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E SECTION D - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g Surface #1-DEHS06.OUT. C:DEHS06SP.PLT By: STAN KLINE 10-24-04 8:30pm




ROCKY FLATS OLF - M&E SECTION D - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.005g
All surfaces evaluated. C:DEHS01.PLT By: STAN KLINE 10-24-04 8:24pm



Factors Of Safety Calculated By The Modified Janbu Method


ROCKY FLATS OLF - M&E SECTION D - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.005g Surface #1-DEHS01.OUT. C:DEHS01SP.PLT By: STAN KLINE 10-24-04 8:26pm



PCSTABL5M/SI FS = 1.00 Theta = 9.18 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices


305

ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g All surfaces evaluated. C:DGAC06.PLT By: STAN KLINE 10-26-04 12:22am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g Ten Most Critical. C:DGAC06.PLT By: STAN KLINE 10-26-04 12:22am




ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.04g All surfaces evaluated. C:DGAC04.PLT By: STAN KLINE 10-26-04 12:21am



Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.04g Ten Most Critical. C:DGAC04.PLT By: STAN KLINE 10-26-04 12:21am



Factors Of Safety Calculated By The Modified Bishop Method

209


ROCKY FLATS OLF - M&E D 18% GRD - WCS=15 deg - W/HIGHGW - CIRCULAR - 0.06g All surfaces evaluated. C:DGHC06.PLT By: STAN KLINE 10-26-04 12:26am



Factors Of Safety Calculated By The Modified Bishop Method


ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g

Ten Most Critical. C:DGHC06.PLT By: STAN KLINE 10-26-04 12:26am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.03g All surfaces evaluated. C:DGHC03.PLT By: STAN KLINE 10-26-04 12:26am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.03g Ten Most Critical. C:DGHC03.PLT By: STAN KLINE 10-26-04 12:26am




ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g All surfaces evaluated. C:DGAS06.PLT By: STAN KLINE 10-24-04 7:59pm




Factors Of Safety Calculated By The Modified Janhu Method

ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g Surface #1-DGAS06.OUT. C:DGAS06SP.PLT By: STAN KLINE 10-24-04 11:16pm




Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.03g All surfaces evaluated. C:DGAS03.PLT By: STAN KLINE 10-24-04 7:56pm




ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.03g Surface #1-DGAS03.OUT. C:DGAS03SP.PLT By: STAN KLINE 10-24-04 7:58pm




PCSTABL5M/SI FS = 1.02 Theta = 8.87 X-Axis (ft)
Factors Of Safety Calculated By Spencer`s Method of Slices

ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g All surfaces evaluated. C:DGHS06.PLT By: STAN KLINE 10-24-04 8:38pm




Factors Of Safety Calculated By The Modified Janbu Method

ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.06g Surface #1-DGHS06.OUT. C:DGHS06SP.PLT By: STAN KLINE 10-24-04 8:55pm




PCSTABL5M/SI FS = 0.85 Theta = 8.95 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.02g All surfaces evaluated. C:DGHS02.PLT By: STAN KLINE 10-24-04 8:35pm




ROCKY FLATS OLF - M&E D 18% GRD - WCS = 15 deg - W/HIGHGW - SLIDING BLOCK - 0.02g Surface #1-DGHS02.OUT. C:DGHS02SP.PLT By: STAN KLINE 10-24-04 8:37pm




PCSTABL5M/SI FS = 1.04 Theta = 9.03 X-Axis (ft)
Factors Of Safety Calculated By Spencer's Method of Slices

18% REGRADE WITH BUTTRESS CONDITION

ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g
All surfaces evaluated. C:DBAC06.PLT By: STAN KLINE 10-26-04 12:23am



ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.06g Ten Most Critical. C:DBAC06.PLT By: STAN KLINE 10-26-04 12:23am




PCSTABL5M/SI FSmin = 0.96 X-Axis (ft)
Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.05g All surfaces evaluated. C:DBAC05.PLT By: STAN KLINE 10-26-04 12:22am Y-Axis (£

Factors Of Safety Calculated By The Modified Bishop Method


X-Axis (ft)

ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 15 deg - W/AVEGW - CIRCULAR - 0.05g
Ten Most Critical. C:DBAC05.PLT By: STAN KLINE 10-26-04 12:22am




PCSTABL5M/SI FSmin = 1.00 X-Axis (ft)
Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g
All surfaces evaluated. C:DBHC06.PLT By: STAN KLINE 10-26-04 12:28am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.06g Ten Most Critical. C:DBHC06.PLT By: STAN KLINE 10-26-04 12:28am




ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.04g
All surfaces evaluated. C:DBHC04.PLT By: STAN KLINE 10-26-04 12:27am




Factors Of Safety Calculated By The Modified Bishop Method

ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 15 deg - W/HIGHGW - CIRCULAR - 0.04g Ten Most Critical. C:DBHC04.PLT By: STAN KLINE 10-26-04 12:27am




ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g
All surfaces evaluated. C:DBAS06.PLT By: STAN KLINE 10-24-04 8:09pm



Factors Of Safety Calculated By The Modified Janbu Method


ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.06g Surface #1-DBAS06.OUT. C:DBAS06SP.PLT By: STAN KLINE 10-24-04 8:13pm



PCSTABL5M/SI FS = 0.94 Theta = 7.93 X-Axis (ft) Factors Of Safety Calculated By Spencer's Method of Slices

322


ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.04g
All surfaces evaluated. C:DBAS04.PLT By: STAN KLINE 10-24-04 8:06pm



Factors Of Safety Calculated By The Modified Janbu Method

333

ROCKY FLATS OLF - M&E D 18%W/BM - WCS = 15 deg - W/AVEGW - SLIDING BLOCK - 0.04g Surface #1-DBAS04.OUT. C:DBAS04SP.PLT By: STAN KLINE 10-24-04 8:08pm



Factors Of Safety Calculated By Spencer's Method of Slices

INFINITE SLOPE STABILITY - SIMPLIFIED APPROACH

Part I - COHESIVE AND FRICTIONAL SOIL SLOPES

(Ref. USACE [1970), EM 1110-2-1902)

Input Data		
Υsat	125	Total saturated unit weight of soil (pcf)
Υw	62.4	Unit weight of water (62.4 pcf)
γ'	62.6	Submerged unit weight of soil (pcf)
α	10	Angle between seepage flow line and embankment slope
β	10.2	Angle of inclination of embankment slope with horizontal
. b	5.6	Horizontal to vertical slope ratio [or $cot(\beta) = H:V$]
ф	30	Angle of internal friction of soil (degrees)
Ċ	50	Cohesion intercept of soil (psf)
Ψ	0.06	Seismic coefficient
b'	5.2	Cotangent of "seismic-equivalent" angle of inclination of embankment slope w/ hor.
β'	10.9	Seismic-equivalent angle of inclination of embankment slope with horizontal (degrees) Additional Input for Cohesive Soil Case
z	5.0	Depth to potential slip surface (feet)
$d_{\mathbf{w}}$	0.0	Depth to ground water surface parallel to slope (feet)
Output Data	1	
FS		Computed static stability factor of safety
PSFS		Computed pseudo-static stability factor of safety, for seismic coefficient Ψ
K		Yield acceleration

Static or Pseudo-Static Stability and Yield Acceleration (Ref. Matasovic [1989)

FS = {c/(γ z cos²β) + tanφ [1 - γ_w (z - d_w)/(γ z)] - Ψ tanβ tanφ}/ (Ψ + tanβ)

$$K_v$$
 = {c/(γ z cos²β) + tanφ [1 - γ_w (z - d_w)/(γ z)] - tanβ}/ (1 + tanβ*tanφ)

FS = 2.07 PSFS = 1.52 K_y = 0.17 APPENDIX F

DEFORMATION ANALYSIS

APPENDIX F

ANALYSIS OF SEISMICALLY-INDUCED PERMANENT DISPLACEMENT OF LANDFILL SLOPES BY THE MAKDISI AND SEED PROCEDURE

INTRODUCTION

Background: A common procedure for estimating seismically-induced permanent displacements was developed by F. Makdisi and H.B. Seed (1978). This procedure has been extensively used to assess the seismic performance of earthfill slopes during earthquakes using the concept of accumulation of permanent slope displacements from corresponding pulses of strong earthquake loading, as initially proposed by Newmark (1965) for rigid-perfectly plastic materials, but subsequently modified by Makdisi and Seed to simulate the dynamic response of earthfill structures.

Design Philosophy: The engineering community generally recognizes that some permanent displacement or deformation of large fills may occur during major earthquake events, and that designing fills to completely prevent permanent displacements is typically impractical, if not impossible. Rational seismic design criteria consist of limiting displacements to levels which are likely to be tolerable. The use of such a deformation analysis is widely accepted for dams, embankments, landfills, in all of the highest seismicity regions of the country.

Advantages of the Method: It is a simple, yet rational approach, offering a significant improvement over conventional pseudo-static approach because it takes into account factors such as the predominant period and the effective peak horizontal acceleration of a potential sliding mass being analyzed. It also accounts for the variation in effective peak horizontal acceleration with depth and it is considered to give more accurate permanent displacement estimates than the Newmark (1965) method. Available simplified design curves were developed to calculate permanent displacement of earthfill slopes in the range of 100 to 200 feet for different earthquake magnitudes, but it is generally believed to be applicable to higher slopes. The simplified design curves were developed from more rigorous dynamic response analyses at embankments and slopes.

Criteria that had previously been used in engineering practice (namely seismic coefficient (K) and recommended pseudo-static factor of safety for conventional pseudo-static analysis were summarized in Figure F1 (from California Division of Mines and Geology, Special Publication 117, dated 1997). Computation of seismically-induced permanent displacement as originally proposed by Newmark (1965) is conceptually summarized in Figure F2 (from Hynes and Franklin of the USACE, 1984).

Assumptions: It assumes that failure occurs on a well-defined slip surface and that the material behaves near-elastically at stress levels below failure, but develops a perfectly plastic behavior above yield. It involves a number of simplifying assumptions which may lead to some somewhat conservative results. It was developed and calibrated based on the use of equivalent-linear strain-dependent dynamic soil parameters (shear modulus and damping ratio) and the dynamic finite element analysis of slopes. Development of this procedure is conceptually summarized on Figures F3 through F9, from initial research by Makdisi and Seed of University of California at Berkeley, 1978; from supplementary research by Hynes and Franklin of the USACE, 1984 for the analysis of earthfill slopes and embankment dams; and from seismic response studies for several geologic site conditions by Seed and Idriss, 1982.

Applications and Limitations: It is primarily applicable to materials such as compacted cohesive clay and dry sands and dense sands, which are expected to retain most of their static undrained cyclic strength, so that the resulting post-earthquake behavior is usually limited permanent deformation of the embankment, not catastrophic or flow failure. This excludes relatively loose cohesionless granular materials which are or can become saturated, and that might develop very large cyclic strains and a rapid buildup of excess pore water pressure during a strong earthquake shaking.

PRIMARY STEPS IN THE ASSESSMENT OF SEISMICALLY-INDUCED DISPLACEMENTS

The following three primary steps are involved in the applications of this simplified procedure (based on design charts), as follows:

Step I - Assessment of Yield Acceleration (Ky) of the Slope

Yield acceleration is defined as that average acceleration producing a horizontal inertial force on a potential sliding mass so as to produce a factor of safety of 1.0, and thus to cause it to experience permanent displacements. This value is a function of geometric conditions and undrained shear strength (reduced strength due to shaking or "cyclic strength") along the potential sliding mass and it is calculated using conventional limit equilibrium analyses.

Step II - Assessment of Maximum Acceleration of a Potential Sliding Mass

This step refers to evaluation of the maximum value (k_{max}) of the earthquake-induced average acceleration-time history $[k_{av}(t)]$ of a potential sliding mass within earthfill slopes. This evaluation of a deformable earth structure, rather than a "rigid block" (shown on Figure F2), has been simplified by the use of design charts developed based on analyzed cases of dynamic response analyses of embankments subjected to earthquake-induced acceleration, for various potential sliding masses.

The procedure requires evaluation of peak crest acceleration, as well as an approximate distribution of peak acceleration versus depth (shown on Figures F3, F4 and F5), and an estimate of natural period of the slope being analyzed. Seed and coworkers evaluated the dynamic performance of earth structures based on both, simple close-form one-dimensional wave propagation models as well as comprehensive numerical modeling studies based on two-dimensional dynamic finite element analysis of embankments (Figure F6).

For the development of those simplified charts (Figures F7 and F9), Makdisi & Seed used:

- Strain-dependent dynamic soil parameters (shear modulus and damping ratio) which were calculated based on equivalent-linear techniques, and
- Calculated stresses acting on each element of the dynamic finite element model at each time step throughout the entire earthquake acceleration-time history (as shown in Figure F6). Normal and shear stresses along the boundary of a potential sliding mass were calculated at every time step, and their calculated resultant force, divided by the weight of the potential sliding mass to give the average acceleration acting on the sliding mass at that instant of time [k_{av}(t)].

The process was repeated for every time step to calculate the entire time history of the average acceleration. This acceleration is also called "effective peak acceleration" of the overall sliding mass.

Step III - Calculation of Seismically-Induced Permanent Displacements

Computation of accumulated permanent displacement along the direction of a potential sliding surface (for the initial development of these simplified design charts) was based on simple double-integration procedures (of average sliding mass acceleration-time history, where it exceeds the yield acceleration).

Based on the simplified design charts developed by Makdisi and Seed (based on previous detailed dynamic analysis for several earthfill slopes and earthquake loading conditions), accumulated permanent displacements were simply calculated based on the yield acceleration, the maximum value of acceleration of a potential sliding mass (or effective peak acceleration), and the magnitude of the earthquake for which the earthfill/landfill response is being evaluated.

PROCEDURE

The procedure involves the determination of:

Slope Geometry, Shear Wave Velocity and Natural Period

Calculation of maximum height of earthfill or refuse fill (H) at the section being considered. Section to be considered for seismic response analyses should be those resulting in the lowest static factor of safety. Evaluation would typically be made of the approximate value of shear wave velocity for the earthfill and/or refuse fill (V_s). For compacted earthfill materials, V_s is on the order of 1,000 feet per second (ft/s), and approximately 700 ft/s for refuse fill near surface, increasing with depth to approximately 900 ft/s at approximately 50 feet of depth. A simplified procedure for computing maximum crest acceleration and natural period for embankments was proposed by Makdisi and Seed (1977). The fundamental natural period of an embankment is approximated by 2.62 H/ V_s .

For the RFETS project, the anticipated maximum height and thickness of the earthfill was approximately 45 feet, which based on an estimated shear wave velocity of the refuse soil mixture of 700 feet/second, resulted in a maximum first natural period of the earthfill/landfill of approximately 0.17 seconds.

Peak Horizontal Acceleration at the Base of the Embankment/Landfill

This step requires identification of primary seismic sources (faults, area sources) which are in the proximity of the site, and determine the Richter magnitude of the maximum event that could be generated at that source, and the distance from source to the project site, and calculate peak horizontal ground acceleration using a suitable ground motion attenuation relationship. If other site geologic conditions exist, namely near surface materials consisting of soil sediments instead or rock, the peak ground surface horizontal acceleration can be estimated based on simple correlations with peak rock acceleration developed by Seed and Idriss (1982) available for various typical soil profile types of stiff soil, soft soil, deep soil.

For the RFETS project, the anticipated peak horizontal acceleration in bedrock corresponding the an earthquake event with an acceleration exceedance probability of 2 percent in 50 years, as estimated by Risk Engineering (RE, 1994) and from the 2002 USGS database, are approximately 0.10g and 0.12g (gravity), respectively.

The corresponding RFETS peak horizontal acceleration in soil (at the ground surface, at the base of the earthfill), was estimated by RE at approximately 0.15g for the same probability of exceedance. Similarly, and based on approximate correlations between peak rock acceleration and peak horizontal ground acceleration developed for a stiff soil profile (as shown on Figure F7 per Seed and Idriss, 1982), the later would be on the order of 0.12g to 0.13g, which is consistent with the RE (1995) assessment. A site-specific response spectra may also be performed using the program "shake" in place of the above two spectral relationships.

Peak Horizontal Acceleration at the Crest

The crest acceleration is approximately determined based on the spectral acceleration of the embankment/landfill. For the first mode of vibration displacement, the spectral response acceleration is approximately the peak crest acceleration of the embankment/landfill. This

response should correspond to the site geologic condition, such as stiff soils, soft soils, deep soil profile, or rock, as shown on Figure F8.

Approximate spectral accelerations are available for both mean or mean plus one standard deviation (84 percentile). Seismic spectral acceleration ratios (spectral acceleration divided by the maximum ground acceleration) were developed by Seed and Idriss, 1982; Seed, Ugas, Lysmer, 1974 and 1976).

The corresponding RFETS mean spectral acceleration ratio (corresponding to the acceleration at the top of the earthfill) corresponding to a predominant natural period of 0.17 second for stiff soil condition was estimated to be approximately 2.5 to 2.6 based on Seed et al (1974, 1982). Therefore, the maximum horizontal crest acceleration would be on the order of 0.30g to 0.39g for the design earthquake event. This estimate is generally consistent with spectral acceleration by RE (1995) for 0.2 seconds of 0.39g for soil conditions (and USGS value of 0.235g for rock conditions).

Parameters Needed for Yield Acceleration Evaluations

Cyclic shear strength of a soil differs from static undrained shear strength in that, due the transient nature of earthquake loading, where seismic loads are not only variable, but might even reverse direction within a very short instant of time. Consequently, an earthfill can be subject to a number of stress pulses equal to or higher than its static failure stress, and that simply produces some permanent deformation rather than complete failure stress. Thus, for the purpose of this analysis, the dynamic yield strength is defined as the maximum stress level below which the material exhibits a near-elastic behavior (when subjected to cyclic stresses of number and frequencies consistent to those induced by earthquake shaking), and above which the material exhibits permanent plastic deformation (of magnitude dependent on the number and frequency of the pulses applied).

Extensive studies on the cyclic behavior of soils by special geotechnical testing in the laboratory were conduced by Seed and Chan (1966), which indicated that for conditions of no stress reversals, such as those that commonly apply to earthfill slopes, and for different values of the initial static and cyclic stress, the total stress required to produce large deformations in 10 to 100

cycles typically ranges between 90 and 110 percent of the undrained static shear strength, as shown on Figure F6. Further, studies by Thiers and Seed (1969) indicated that undrained shear strength after cyclic loading may be expected be on the order of 90 percent of its original static shear strength as long as cyclic shear strains are less than half its static failure shear strain (also shown on Figure F6). Consequently, it may be reasonably assumed on the basis of the reported experimental data, and from the value of cyclic shear strains calculated from earthquake response analyses, that the value of cyclic yield strength for a clayey material would be between 80 to 100 percent of the static undrained strength. The later value corresponds to peak cyclic shear strain amplitudes less than one quarter of the static undrained failure strain.

Cyclic Shear Strain. From comprehensive dynamic response analyses of various earthfill dams and embankment slopes in highly seismic regions it was found that, in general, peak cyclic shear strains induced during earthquakes are expected to range from 0.1 percent for magnitude 6-1/2 earthquakes with embankment base accelerations of 0.2g (gravity) to 1 percent for magnitude 8-1/4 earthquakes with base accelerations of 0.75g (Makdisi and Seed, 1978).

In the case of the RFETS-OLF project, and considering the stiff nature of clayey materials encountered at the site, with a peak cyclic strain of less 0.1 percent, and typical static failure shear strain on the order of 3 to 5 percent, the ratio of the cyclic shear strain to the static failure strain is much less than 0.2. Consequently, reduction of the static undrained shear strength as a result of the design seismic loading is considered for all practical purposes to be insignificant. Consequently, the cyclic strength used in subsequent analyses was the same as the static undrained shear strength.

Seismic Slope Stability Analysis to Estimate Yield Acceleration. The cyclic shear strength value may be used in combination with conventional limit equilibrium analysis of slopes to compute the corresponding yield acceleration using both circular and block/wedge type potential sliding surfaces. A pseudo-static type of analysis is used to perform this calculation for several horizontal seismic coefficients. Of the several analyses conducted, the yield acceleration corresponds to the horizontal seismic coefficient resulting in a pseudo-static factor of safety of 1.0. Some interpolation is usually required.

The computed yield acceleration values for the RFETS site ranged from 0.02 to 0.04 for 18-Percent Regraded OLF site without buttress, and from 0.04 to 0.06 for 18-Percent Regraded OLF site with a buttress fill.

Ratio of Maximum Values $[k_{max}]$ of Earthfill/Embankment Average Acceleration Time History $[k_{av}(t)]$ at Various Depths [y] of a Potential Sliding Mass to Crest Acceleration $[\ddot{u}_{max}]$.

Once a relationship showing variations of the maximum acceleration ration $[k_{max}/\ddot{u}_{max}]$ versus depth [y] of the base of a potential sliding mass 'has been established for a range of earthfill and earthquake loading conditions (Figure F5), it would then be sufficient, for design purposes, to estimate the maximum crest acceleration (as described above and using Figure F8) in a given embankment due to a specified earthquake and use this relationship to determine the maximum average acceleration for any depth of the base of a potential sliding mass, as summarized in simplified design charts by Makdisi and Seed (1978).

This simplified procedure was developed by Makdisi and Seed (1978) based on the dynamic response of earthfill with heights ranging from 100 to 600 feet (Martin, 1965), natural periods of 0.25 to 5.2 seconds, which is very similar to the normalized response results published by Ambraseys and Sarma (1967) for embankments with natural periods ranging between 0.25 and 3.0 seconds in terms of average response for eight strong motion records. Another simplified procedure was proposed by Makdisi and Seed (1977) for computing maximum crest acceleration and natural period for embankments.

The shape of average results from dynamic finite element analyses is very similar to that computed based on "shear slice" method, with variations within 10 to 20 percent for the upper portion of the earthfill and 20 to 30 percent for the lower portion of the embankment. The upper bound of the proposed maximum value of the average acceleration ratio (k_{max}/\ddot{u}_{max}) versus depth (y) design curve may be used where a conservative estimate of accelerations is desired (rather than the average curve). For deep seated surfaces (earthfill/landfill founded on weak soils), y/H > 1 a value of 0.35 may be used.

For the RFETS project, assuming that potential slip surface could reach the base of the earthfill (or y/H = 1), k_{max} was found to be approximately 0.10 ± 0.02 .

Earthquake-Induced Permanent Displacement Calculation

The direction of movement of the sliding mass is along the sliding surface, which is assumed to be near horizontal. This assumption is not uncommon for earthfill slopes subject to strong earthquake shaking; further, studies for other directions of the sliding surface have shown that this parameter has relatively little effect on the computed displacements. For example, it has been reported that for a sliding plane with predominantly granular materials at angles of 15 degrees from the horizontal, the computed displacements were 10 to 18 percent higher than those based on horizontal plane assumptions.

Displacements are calculated to occur every time the induced average mass acceleration exceeds the yield acceleration, by a simple numerical integration. As previously indicated, for soil types with undrained strengths not significantly affected by earthquake loading, such as in the case of the RFETS-OLF project, the yield acceleration is considered to be constant.

Simplified design charts (shown on Figure F9), which were computed by Makdisi and Seed, were used for computing earthquake-induced permanent displacement for the RFETS-OLF project, based on studies for earthfill ranging in height from 75 to 150 feet, with varying slopes, and for earthquake magnitudes of 6-1/2, 7-1/2 and 8-1/4. Because the design earthquake event recommended by RE (Risk Engineering/Geomatrix, 1995) for seismically-induced displacement analyses has a magnitude of 5.9, some extrapolation was needed, as shown on Figures F10.

Simplified Design Charts

The above-referenced study showed that ratios of yield acceleration to average acceleration of a potential sliding mass (k_y/k_{max}) at various levels between the crest and base of an earthfill slope when plotted versus computed seismically-induced permanent displacement varied similarly. Further, it was found that the computed displacements varied uniformly from a maximum value (computed from the crest average acceleration time history) to a minimum value (using the base acceleration time history), as shown on Figure F3. Therefore, maximum permanent displacements were summarized by Makdisi & Seed for these two levels.

These design curves (Figure F9) were developed for 6-1/2, 7-1/2 and 8-1/4 earthquake magnitudes and peak horizontal ground accelerations (base of the embankment) of 0.2 to 0.5g, 0.2g to 0.5g, and 0.4g to 0.75g, respectively, corresponding to earthfill slopes ranging in height from 75 to 150 feet, and having fundamental natural periods ranging from 0.6 to 1.1 seconds, 0.75 to 1.2 seconds and 0.8 to 1.5 seconds, respectively.

These simplified design charts have a range of yield acceleration ratios ky/kmax from approximately 0.05 to 0.9, and computed permanent displacements of less than one inch to several tens of feet. For example:

- For magnitude 6-1/2 earthquakes it was found that for relatively low values of yield acceleration, $k_y/k_{max} = 0.2$ for example, the range of computed permanent displacements using these simplified design charts would be on the order of 4 to 28 inches, while for higher values, such as $k_y/k_{max} = 0.5$, displacements were less than 5 inches. It should be noted that for values of $k_y/k_{max} < 0.1$, the basic assumptions of the method, namely the equivalent linear behavior and the small strain theory, become invalid. Similarly,
- For magnitude 7-1/2 earthquakes, it was found that for values of $k_y/k_{max} = 0.2$ and 0.5, the range of computed permanent displacements would be on the order of 12 to nearly 80 inches and less than 25 inches, respectively, and
- For magnitude 8-1/4 earthquakes, it was found that for values of $k_y/k_{max} = 0.2$ and 0.5, the range of computed permanent displacements would be on the order of 6 to nearly 23 feet and less than 3.5 feet, respectively.

Consequently, for the RFETS-OLF project, seismically-induced permanent displacements adjusted for magnitude M-5.9, as shown on Figure F10, are estimated to range from approximately 5 to 10 inches for the 18 percent regraded slope without buttress, and approximately 3 to 5 inches for the 18 percent regraded slope with buttress.

In general, a high static factor of safety will typically result in a relatively low permanent displacement. As the static factor of safety decreases, the calculated seismically-induced permanent displacements increase. Therefore, the static factor of safety, calculated using effective stress parameters, should be checked before performing a seismic response analysis to a get a "feel" for the overall seismic stability of the slope being analyzed.





Figure 1. Approximate range of pseudo-static seismic coefficient "k" for anticipated factor of safety as proposed in the literature (references on the diagram).



e. COMPUTATION OF DISPLACEMENT

Figure 5. Elements of the sliding block analysis

Figure Fz




Figure 9. Computation of average acceleration acting on the sliding mass




Figure 10. Amplification curves for the S 25 W component, Temblor No. 2 Record, Parkfield earthquake of 27 June 1966 (damping = 20 percent)




Figure 11. Amplification factors for linearly viscoelastic embankments at resonance




FIG. 7.—Variation of Maximum Acceleration Ratio with Depth of Sliding Mass





FIG. 1.—Determination of Dynamic Yield Strength



Element i d_{i} $d_$

$$F(t) = \sum_{i=1}^{n} \tau_{hv_i}(t) L_i + \sigma_{h_i}(t) d_i$$

n = number of elements along the sliding surface

$$k_{ov}(t) = F(t)/W$$

FIG. 2.—Reduction in Static Undrained Strength Due to Cyclic Loading (29)

FIG. 3.—Calculation of Average Acceleration from Finite Element Response Analysis




Figure 19. Approximate relationships between maximum accelerations on rock and other local site conditions.

Figure F7

18




Figure 24. Average acceleration spectra for different site conditions.






Figure F9





DRAFT INTERIM MEASURE/INTERIM **REMEDIAL ACTION FOR** THE ORIGINAL LANDFILL (INCLUDING IHSS GROUP SW-2; **IHSS 115, ORIGINAL LANDFILL** AND IHSS 196, FILTER BACKWASH POND)



December 6, 2004

DRAFT INTERIM MEASURE/INTERIM REMEDIAL ACTION FOR THE ORIGINAL LANDFILL (INCLUDING IHSS GROUP SW-2; IHSS 115, ORIGINAL LANDFILL AND IHSS 196, FILTER BACKWASH POND)

December 6, 2004

TABLE OF CONTENTS

EXECUTIVE SUMMARY	X
1.0 INTRODUCTION	1-1
1.1 Need for RFCA Accelerated Action	1-4
1.2 Proposed Accelerated Action - The Municipal Landfill Presumptive Reme	dy 1-5
2.0 SITE BACKGROUND	2-1
2.1 IHSS Group SW-2 Site Description	2-1
2.2 Description and History of IHSS 115 (OLF)	2-1
2.3 Description and History of IHSS 196 (Filter Backwash Pond)	2-4
2.4 Other Disturbances and Structures	2-5
2.5 Historical Interim Response Actions	2-5
2.6. Slone Stability	2-6
2.7 Existing Conditions	2-7
3.0 ENVIRONMENTAL SETTING	3-1
3.1 Physiography	3-1
3.2 Climate	3-1
3.3 Geology	3-2
3.3.1 Rocky Flats Alluvium	3-2
3.3.2 Colluvial Deposits	3-2
3.3.3 Valley-fill Alluvium	3-3
3.3.4 Laramie Formation	3-5
3.3.5 Inferred Faulting	3-5
3.4 Summary of Geotechnical Investigations	3-6
3.5 Groundwater	3-8
3.6 Integrated Hydrologic Model Development and Results	3-9
3.7 Surface Water	3-12
3.8 Ecological Setting	3-13
4.0 ENVIRONMENTAL DATA SUMMARY AND RFCA ACTION LEVEL	
COMPARISON	4-1
4.1 Site Characterization Data	4-1
4.2 Data Compilation and Evaluation	4-2
4.3 Surface Soil	4-3
4.4 Subsurface Soil	4-4
4.5 Groundwater	4-4
4.5.1 Metals	4-4
4.5.2 Radionuclides	4-5
4.5.3 Organics	4-7
4.5.4 Water Quality Parameters	4-8
4.5.5 Groundwater Quality Summary	4-8
4.6 Surface Water	4-8
4.6.1 Ungradient Woman Creek Surface Water Quality	4-9
4.6.2 Downgradient Woman Creek Surface Water Quality	4-9
4.6.3 South Interceptor Ditch Surface Water Quality	4-10
4.7 Sediment	4-11
4.8 Contamination Summary and Action Determinations	4-11

4.9 Risk Assessment	4-12
5 0 REMEDIAL ACTION OBJECTIVES	5-1
6.0 REMEDIAL ACTION ALTERNATIVES EVALUATION	6-1
6.1 Remedial Action Alternatives	6-1
6.1.1 Alternative 1 – No Action	6-1
6.1.2 Alternative 2 – Soil Cover	6-1
6.1.3 Alternative 3 – Soil Cover With Buttress Fill	6-5
6 1 4 Alternative 4 – Removal of Waste	6-6
6.2 COMPARATIVE EVALUATION OF ALTERNATIVES	6-9
6.2.1 Alternative 1 – No Action	6-11
6.2.2 Alternative 2 – Soil Cover	6-12
6.2.3 Alternative 3 – Soil Cover with Buttress Fill	6-15
6.2.4 Alternative 4 – Removal with Offsite Disposal	6-17
6.2.5 Summary	6-20
7.0 PROPOSED REMEDIAL ACTION PLAN	7-1
7.1 Pemoval of Surface Soil Hot Snots	7-1
7.1 Actioval of Surface Soft Flot Specs	7-1
7.3 Engineering Controls	7-2
7.4 Site Monitoring	7-3
7.5 Institutional Controls	7-3
7.6 Worker Health and Safety	7-4
8.0 APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS	8-1
8.1 Landfill Cover Requirements	8-1
8.1.1 Function With Minimum Maintenance	8-2
8.1.2 Accommodate Settling and Subsidence to Maintain Cover's Integrity	8-2
8.2 Air	8-3
8.3 Surface Water	
8.3.1 Stormwater	8-3
8.3.2 Remediation Wastewater	8-4
8.4 Wetlands	8-4
8.5 Wildlife	8-5
9.0 ENVIRONMENTAL IMPACTS	9-1
9.1 Impacts to Air Quality	9-1
9.1.1 Potential Fugitive Dust Emissions	9-1
9.1.2 Potential Equipment Emissions	9-1
9.2 Impacts to Surface Water	9-2
9.3 Impacts to Groundwater	9-3
9.4 Impacts to Wildlife and Vegetation	9-3
9.5 Impacts to Nearby Populations	9-5
9.6 Impacts to Transportation	9-5
9.7 Impacts to Cultural and Historic Resources	9-5
9.8 Impacts to Visual Resources	9-5
9.9 Noise Impacts	9-6
9.10 Cumulative Impacts	9-6
9.11 Irreversible & Irretrievable Commitment of Resources	9-6
10.0 ADDITIONAL LONG-TERM STEWARDSHIP CONSIDERATIONS	10-1

10.1 Information Management	10-1
10.2 Periodic Assessments	10-4
10.3 Controlling Authority	10-4
10.4 Reporting Requirements	
11.0 IMPLEMENTATION SCHEDULE	
12.0 CLOSEOUT REPORT	
14.0 COMMENT RESPONSIVENESS SUMMARY	
15.0 REFERENCES	
	•
LIST OF FIGURES	
Figure 1-1 Site Location	
Figure 1-2 Location of IHSS 115 and IHSS 196	1-3
Figure 2-1 OLF Features	2-2
Figure 3-1 Typical Geological Cross Section of the Original Landfill	3-4
Figure 3-2 Inferred Fault in Original Landfill Area	3-6
Figure 3-3 Surface Water Features	
Figure 3-4 Wetlands and PMJM Areas Near the Original Landfill	
Figure 4-1 Surface Soil Sampling Locations	4 - 28
Figure 4-2 Subsurface Soil Sampling Locations	4-29
Figure 4-3 Groundwater Sampling Locations	4-30
Figure 4-4 Surface Water Sampling Locations	
Figure 4-5 Sediment Locations - Original Landfill Area	4-32
Figure 4-6 Uranium Concentrations Above Background in Surface Soil	4-33
Figure 4-7 Polynuclear Aromatic Hydrocarbons Above Background in Surface Soi	14-34
Figure 4-8 Polynuclear Aromatic Hydrocarbon Concentrations Above Background	
Subsurface Soil	
Figure 4-9 Dissolved Antimony in Groundwater	
Figure 4-10 Dissolved Beryllium in Groundwater	
Figure 4-11 Dissolved Cadmium in Groundwater	
Figure 4-12 Dissolved Lead in Groundwater	
Figure 4-13 Dissolved Manganese in Groundwater	4-40
Figure 4-14 Dissolved Nickel in Groundwater	4-41
Figure 4-15 Dissolved Selenium in Groundwater	
Figure 4-16 Dissolved Thallium in Groundwater	4-43
Figure 4-17 Dissolved Strontium-90 in Groundwater	4-44
Figure 4-18 Dissolved Uranium Concentrations and Isotopic Activity Ratios in Groundwater at Well 61093	4-45

Figure 4-19 Dissolved Uranium Concentrations and Isotopic Mass Ratios in Groundwater at Well 610934-46
Figure 4-20 Total Uranium Concentrations and Isotopic Mass Ratios in Groundwater Measured by ICP MS4-47
Figure 4-21 Dieldrin in Groundwater4-48
Figure 4-22 Bis(2-ethylhexyl)phthalate in Groundwater at Wells with a Tier II Exceedance
Figure 4-23 Tetrachloroethene in Groundwater at Wells with a Tier II Exceedance 4-50
Figure 4-24 Trichloroethene in Groundwater at Wells with a Tier II Exceedance 4-51
Figure 4-25 Most Recent TCE and PCE Concentrations in Groundwater4-52
Figure 4-26 Nitrate Concentrations in Groundwater at Wells with a Tier II Exceedance
Figure 4-27 Total Uranium Concentrations and Uranium Isotopic Ratios for Surface Water at SW-36
Figure 5-1 Subsurface Soil Risk Screen
Figure 6-1 Alternative 2 – Conceptual Grading Plan
Figure 6-2 Alternative 2 – Conceptual Cross-Section
Figure 6-3 Alternative 3 Conceptual Buttress Fill Cross-Section6-7
LIST OF TABLES
LIST OF TABLES
Table 4-1 Surface Soil Data Summary

LIST OF APPENDICES

Appendix A ARARs

Appendix B Environmental Data Tables

Appendix C Summary - Removal of Radiologically Contaminated Surface Soil

Appendix D Accelerated Action Alternatives Cost Estimates

Appendix E Wetland Mitigation Plan

Appendix F Comment Responsiveness Summary

AAESE Accelerated Action Ecological Screening Evaluation

AHA Activity Hazard Analysis

AL action level

ALF Action Levels and Standards Framework for Surface Water, Ground

Water, and Soil

Am americium

AOC Area of Concern

APEN Air Pollutant Emission Notice

AR Administrative Record

AR Administrative Record

ARAR applicable or relevant and appropriate requirement

bgs below ground surface

BMP best management practice

BZ Buffer Zone

CAD/ROD Corrective Action Decision/Record of Decision

CAQCC Colorado Air Quality Control Commission

CCR Code Colorado of Regulations

CDPHE Colorado Department of Public Health and Environment

CERCLA Comprehensive Environmental Response, Compensation, and Liability

Act

CFR Code of Federal Regulations

cfs cubic feet per second

CHWA Colorado Hazardous Waste Act

CID Cumulative Impacts Document

CMS/FS Corrective Measures Study/Feasibility Study

COC contaminant of concern

CRA Comprehensive Risk Assessment

cy cubic yard

DOE U.S. Department of Energy

DOI U.S. Department of Interior

DQO data quality objective

ECOC ecological contaminant of concern

EPA U.S. Environmental Protection Agency

ERA Ecological Risk Assessment

EU exposure unit

FIDLER Field Instrument for the Detection of Low-Energy Radiation

FY fiscal year

GIS Geographic Information System

HAP hazardous pollutant

HASP Health and Safety Plan

HPGe high-purity germanium

HRR Historical Release Report

IA Industrial Area

IABZSAP Industrial Area Buffer Zone Sampling and Analysis Plan

ICP/MS inductively coupled plasma mass spectrometry

IDL instrument detection limit

IGD Implementation Guidance Document

IHSS Individual Hazardous Substance Site

IM/IRA Interim Measure/Interim Remedial Action

IMP Integrated Monitoring Plan

ISMS Integrated Safety Management System

IWCP Integrated Work Control Program

kg kilogram

K-H Kaiser-Hill Company, L.L.C.

LDR Land Disposal Restriction

LHSU lower hydrostratigraphic unit

LRA Lead Regulatory Agency

MDL method detection limit

μg/kg micrograms per kilogram

μg/L micrograms per liter

mg/kg milligrams per kilogram

mg/L milligrams per liter

MOU Memorandum of Understanding

NAAQS National Ambient Air Quality Standard

nCi/g nanocuries per gram

NCP National Oil and Hazardous Substances Pollution Contingency Plan

NEPA National Environmental Policy Act

NESHAP National Emission Standard for Hazardous Air Pollutants

NFAA No Further Accelerated Action

NOI Notification of Intent

NPDES National Pollutant Discharge Elimination System

NPL National Priority List

O+M operation and maintenance

OLF Original Landfill

OSHA Occupational Safety and Health Administration

OU Operable Unit

PAC Potential Area of Concern

PAH polynuclear aromatic hydrocarbon

PCB polychlorinated biphenyl

PCE tetrachloroethene (or perchloroethene)

pCi/L picocuries per liter

PCOC potential contaminant of concern

PMJM Preble's meadow jumping mouse

POC Point of Compliance

PPE personal protective equipment

psf pounds per square foot

Pu plutonium

QA quality assurance

RAO remedial action objective

RCRA Resource Conservation and Recovery Act

RFCA Rocky Flats Cleanup Agreement

RFETS or Site Rocky Flats Environmental Technology Site

RFI/RI RCRA Facility Investigation/Remedial Investigation

RI/FS Remedial Investigation/Feasibility Study

RL reporting limit

SID South Interceptor Ditch

Sr strontium

SVOC semivolatile organic compound

SWD Soil Water Database

SWWB Site-Wide Water Balance

TCE trichloroethene

TCLP Toxicity Characteristic Leaching Procedure

TSP total suspended particulates

U uranium

USFWS U.S. Fish and Wildlife Service

USHU upper hydrostratigraphic unit

VOC volatile organic compound

WQP water quality parameter

WRW wildlife refuge worker

WY Water Year

EXECUTIVE SUMMARY

This Interim Measure/Interim Remedial Action (IM/IRA) Decision Document presents the proposed accelerated action to remediate Individual Hazardous Substance Site (IHSS) Group SW-2 at the Rocky Flats Environmental Technology Site (RFETS or Site). IHSS Group SW-2 consists of two IHSSs: IHSS 115, the Original Landfill (OLF), and IHSS 196, the Filter Backwash Pond.

The OLF is a 20-acre area where construction debris and general facility wastes were placed from 1950 to 1968. The OLF is located on a south-facing slope just south of the Industrial Area (IA) pediment and borders the northern side of Woman Creek.

This IM/IRA summarizes the environmental data for IHSS Group SW-2, compares the data to Rocky Flats Cleanup Agreement (RFCA) action levels (ALs), presents and evaluates accelerated action alternatives, and describes the proposed action. Recent geotechnical data and groundwater modeling at the OLF are also summarized in the IM/IRA.

A review of the environmental data concludes the following:

- Surface Soils: Metals, radionuclides, and organic compounds have been detected above background levels in surface soil; however, only uranium and a few polynuclear aromatic hydrocarbons (PAHs) are present in surface soil above the RFCA ALs. Uranium contamination is present in surface soil above the ALs at four sample locations. PAHs are ubiquitous in surface soil at the OLF; however, only two sample locations have PAH concentrations that exceed the ALs,
- Subsurface Soils: Metals, radionuclides, and organics have been detected above background levels in subsurface soil; however, only PAHs were detected above the ALs and only in an isolated location.
- Groundwater: Metals, radionuclides, and organic compounds have been detected in groundwater at concentrations that are above background and the Tier II ALs. However, the number of detections above background and the Tier II ALs was generally very low for all of these constituents, and their concentrations were also generally very low relative to background and the Tier II ALs. There are no Tier I exceedances for any constituents. Furthermore, chlorinated solvent contamination in groundwater does not extend downgradient of the OLF. The most recent volatile organic compound (VOC) data for these wells (last 3 years) indicate that chlorinated solvents are either not detected, or detected at trace concentrations below 1 μg/L. There is no plume of contaminated groundwater emanating from the OLF. Groundwater fate and transport modeling also indicates that the constituents in groundwater will not reach Woman Creek above detectable levels. Therefore, groundwater quality is not significantly impacted by the OLF.
- Surface Water: Several metals, radionuclides, and organic compounds have been detected above background levels within Woman Creek surface water downgradient of

the OLF. However, the concentrations of many of these analytes were only occasionally above the surface water ALs (approximately 5 percent or fewer of the observations), and were generally low in magnitude relative to the surface water ALs. Several metals and organics detected above background in surface water downgradient of the OLF have not been detected above background in upgradient surface water. However, these analyte concentrations typically were low relative to the surface water ALs, with only infrequent concentrations above the surface water ALs (fewer than 7 percent of any analyte sampled exceeded the AL). This frequency of occurrence is not sufficient to indicate that the OLF has had a significant impact on surface water quality.

• Sediments: A few metals were detected above background in the sediment of Woman Creek and the South Interceptor Ditch (SID) in the vicinity of the OLF; however, concentrations were orders of magnitude below the RFCA ALs.

During the 1995 geotechnical study, historic areas of discrete landslides were identified in the area of the OLF before any waste was placed. However, there are no indications of landsliding at the OLF since waste disposal stopped in 1968. Erosion and sloughing of the hummocky surface due to historic waste placement and faulty stormwater management practices have exposed some waste at the surface of the OLF. Geotechnical testing (conducted in 2004) has provided data to further evaluate the structural stability of the OLF. These data have provided additional information on the strength of the underlying subsoil and weathered bedrock to be used in the design of the accelerated action.

Four accelerated action alternatives have been evaluated in the IM/IRA to address direct contact with the waste materials, control stormwater and erosion, and address the structural stability of the OLF. These four accelerated action alternatives include:

- No Action
- Removal of surface soil "hot spots" and site grading with a soil cover;
- Removal of surface soil "hot spots," and site grading with a soil cover and buttress fill at the toe of the OLF slope (this alternative also includes an evaluation of an upgradient groundwater "cutoff" wall); and
- Removal of surface soil "hot spots," and removal and off-site disposal of the wastes placed at the OLF.

A comparative evaluation has been conducted on these accelerated action alternatives using the criteria of effectiveness, implementability, structural stability, and relative cost. Site grading with a soil cover is the proposed accelerated action for the OLF for the following reasons:

- The surface soil areas with concentrations that exceeded the uranium ALs were removed in August 2004.
- Regrading the site will eliminate the ponding of stormwater at the surface of the OLF and provide for positive runoff and run-on control of stormwater.

- Adding a soil cover will eliminate the exposure and direct contact of the waste materials at the surface of the OLF.
- Reducing the existing surface slopes (regrading) will eliminate surface soil sloughing and erosion, and provide a structurally stable area to contain the waste materials.
- Implementing this proposed accelerated action would not permanently impact the habitat of the Preble's Meadows Jumping Mouse or impact Woman Creek.
- Implementing this proposed accelerated action is cost effective since the data and OLF evaluations indicate the OLF is not now a significant source of contamination to the environment

Actions undertaken to implement the approved accelerated action will be documented in a Closeout Report.

Post-accelerated action monitoring and maintenance are also described in the IM/IRA and include, groundwater monitoring, surface water monitoring, and monitoring of the structural stability of the graded slope.

1.0 INTRODUCTION


This Interim Measure/Interim Remedial Action (IM/IRA) Decision Document presents the proposed accelerated action to remediate Individual Hazardous Substance Site (IHSS) Group SW-2 at the Rocky Flats Environmental Technology Site (RFETS or Site). IHSS Group SW-2 consists of two IHSSs: IHSS 115, the Original Landfill (OLF), and IHSS 196, the Filter Backwash Pond.


RFETS is a Comprehensive Environmental Response, Compensation and Liability Act (CERCLA) National Priority List (NPL) site and is located in rural northern Jefferson County, Colorado, approximately 16 miles northwest of Denver. It is approximately 6,265 acres in area. The developed portion of the Site, referred to as the IA, is centrally located within RFETS and occupies approximately 365 acres. The Rocky Flats Buffer Zone (BZ) surrounds the IA and occupies the remaining 5,900 acres. IHSS Group SW-2 is located in the southern part of the IA Operable Unit (OU) and adjacent to the Buffer Zone OU. Figures 1-1 and 1-2 present the locations of the Site and IHSSs 115 and 196, respectively.

The Rocky Flats Cleanup Agreement (RFCA) (DOE et al. 1996) is a CERCLA federal facility cleanup agreement as well as a compliance order on consent under the Resource Conservation and Recovery Act (RCRA) and the Colorado Hazardous Waste Act (CHWA) between the U.S. Department of Energy (DOE), the U.S. Environmental Protection Agency, Region VIII (EPA), and the Colorado Department of Public Health and Environment (CDPHE). RFCA provides the regulatory framework for cleanup of hazardous substances at the Site. In accordance with RFCA, this IM/IRA is subject to CDPHE, EPA, and public review and comment, and also approval by CDPHE, the Lead Regulatory Agency for RFCA accelerated actions in the IA OU.

This IM/IRA presents the environmental data for IHSS Group SW-2, compares the data to RFCA action levels (ALs), presents and evaluates accelerated action alternatives, and describes the proposed actions. Actions undertaken to implement the approved accelerated action will be documented in a Closeout Report.

116.61





1.1 Need for RFCA Accelerated Action

Between 1952 and 1968, approximately 74,000 cubic yards of solid waste consisting of construction and other debris and general plant waste contaminated with or commingled with small amounts of wastes with hazardous constituents were disposed in the approximately 20-acre OLF, IHSS-115. The OLF is located on the southern-facing slope just south of the IA pediment and borders the northern side of Woman Creek. Because of the slope angle and underlying bedrock characteristics, this area has been identified as susceptible to landslides and erosion.

From the early 1950s until 1971, filter backwash wastewater generated by the raw water treatment process in Building 124 to make potable water was discharged to settling and evaporation ponds located roughly in the center of IHSS 115, designated the Filter Backwash Pond, IHSS 196. A soil cover was placed over the disposed waste when the OLF was closed in 1968. Some of the wastes and debris have become exposed through erosion of the soil cover over the wastes that were placed at steep slopes. Besides the soil cover, soil fill material was used in the waste disposal operation. The volume of disposed waste and commingled soil is estimated at 160,000 cubic yards.

IHSSs 115 and 196 were formerly part of OU 5, the Woman Creek Priority Drainage, which was consolidated into the IA OU when RFCA became effective in July 1996. Prior to this consolidation, a Phase 1 RCRA Facility Investigation/Remedial Investigation (RFI/RI) for OU-5 was conducted pursuant to an RFI/RI Work Plan, which was approved by CDPHE and EPA in 1992 (EPA 1992a, 1992b; CDPHE 1992). For purposes of the investigation work the OU-5 IHSSs (and Potential Areas of Concern [PACs]) were separated into specific Areas of Concern (AOCs). The IHSSs 115 and 196 were designated AOC 1.

One of the purposes of the OU-5 Phase 1 RFI/RI for the OLF was to gather sufficient geotechnical information to evaluate landslide mechanisms in the OLF. The OU-5 Phase 1 RFI/RI also included source and environmental media characterization for the OLF and a human health and ecological risk assessment for Area 1. The OU-5 Phase 1 RFI/RI Report was completed in 1996 (Kaiser-Hill 1996).

Section 2.0, Site Background, Section 3.0, Environmental Setting, and Section 4.0, Environmental Data Summary and RFCA Action Level Comparison of this IM/IRA, provide detailed information about the OLF and Filter Backwash Pond history and the OU-5 Phase 1 RFI/RI.

In addition to the problems posed by inadequate soil cover, which allows possible direct contact with the disposed wastes, sampling and analysis of soil, surface water, and groundwater have shown some contamination above background levels. Some organic compounds and metals (including depleted uranium) contamination is present at levels greater than action levels and/or standards applicable to these media contained in the *Action Levels and Standards Framework for Surface Water, Ground Water and Soils* (ALF), RFCA Attachment 5. Pursuant to RFCA, if ALF action levels or standards are exceeded, an evaluation, remedial action, and/or management action is triggered.

DOE proposes to conduct a remedial action for the OLF and Filter Backwash Pond. Pursuant to RFCA, remedial actions taken for one or more IHSSs will be conducted as a RFCA accelerated action. Because this accelerated action is estimated to take longer than six months from the time of commencement of physical work to complete, RFCA requires that the work will be conducted pursuant to an IM/IRA. Section 11.0, Implementation Schedule of this IM/IRA, provides an informational schedule for the major work activities, which are expected to take just over 6 months to complete.

1.2 Proposed Accelerated Action - The Municipal Landfill Presumptive Remedy

EPA has published two directives regarding the application of the "source containment" presumptive remedy to municipal and military landfills (EPA 1993a, 1996).

"Presumptive remedies are preferred technologies for common categories of sites based on historical patterns of remedy selection and EPA's scientific and engineering evaluation of performance data on technology implementation. By streamlining site investigation and accelerating the remedy selection process, presumptive remedies are expected to ensure consistent selection of remedial actions to reduce the cost and time required to clean up similar sites. Presumptive remedies are expected to be used at all appropriate sites. Sitespecific circumstances dictate whether a presumptive remedy is appropriate at a given site."

Application of the CERCLA Municipal Landfill Presumptive Remedy to Military Landfills, OSWER Directive No. 9355.0-67FS, December 1996, p.1. The directive recognizes that military landfills may contain waste types that are different from those found in municipal landfills but that pose a hazard profile similar to that of municipal landfills. The directive provides criteria for evaluating whether the landfill contents have characteristics similar to municipal landfill contents. If the characteristics are similar, then the presumptive remedy should be considered and implemented if appropriate. Although, the OLF is not on a military base, because of its size and waste types, it is similar to military landfills at other NPL Sites where the presumptive remedy has been implemented.

EPA has also published several directives regarding conducting and streamlining Remedial Investigations/Feasibility Studies at CERCLA municipal landfill sites (EPA 1991a; 1994). The presumptive remedy process involves using existing data to the extent possible and limiting the characterization of the landfill contents, conducting a streamlined risk assessment, and developing a focused feasibility study to analyze only those alternatives consisting of appropriate components of the presumptive remedy.

The OU-5 Phase 1 RFI/RI Report and groundwater and surface water monitoring provide sufficient information to evaluate the OLF in accordance with the military and municipal landfill presumptive remedy guidance. Section 5.0, Remedial Objectives of this IM/IRA, provides a discussion of whether the "source containment" remedy is appropriate. Section 6.0, Remedial Action Alternatives Evaluation, and Section 7.0, Proposed Remedial

Action Plan, provide details regarding the components of the proposed source containment remedy. Section 6.0 also evaluates the "no action" and removal alternatives.

Section 8.0, Applicable or Relevant and Appropriate Requirements (ARARs), along with Appendix A, provides a discussion of the regulations pertaining to this accelerated action. Section 9.0, Environmental Impacts, presents an analysis of the environmental consequences associated with the proposed action. Section 10.0, Additional Long-Term Stewardship Considerations, identifies additional post-accelerated action activities to be implemented.

Section 13.0, Administrative Record, identifies the documents considered by DOE, CDPHE, and EPA in proposing this accelerated action, which are available for public review at the Rocky Flats Reading Room.

2.0 SITE BACKGROUND


2.1 IHSS Group SW-2 Site Description

IHSS Group SW-2 covers approximately 20 acres and includes two IHSSs: IHSS 115, the OLF, and IHSS 196, the Filter Backwash Pond. IHSS 115 is located south of the RFETS IA pediment on a south-facing hill slope north of Woman Creek. IHSS 196 lies approximately in the center of IHSS 115. Approximately 1,000 ft of the South Interceptor Ditch (SID), and storm drain and building footer drain discharge pipes and other disturbed areas lie within IHSS 115. (See Figure 2-1) These IHSSs were formerly part of OU 5, Woman Creek Priority Drainage. An OU 5 Phase I RFI/RI was conducted in accordance with an approved work plan; a final report was issued in April 1996 (Kaiser-Hill 1996).

2.2 Description and History of IHSS 115 (OLF)

The OLF was used to dispose of solid sanitary and construction debris wastes generated at the Rocky Flats Plant from 1952 to 1968 (Rockwell 1988). The landfill was not designed or operated as an engineered landfill. Aerial photographs indicate that the landfill was operated as an area fill (EG&G 1994). Waste was merely dumped in the area vertically below and just south of the southern edge of the alluvial pediment on which the RFETS IA is located. The waste disposal area lies north of Woman Creek. The waste was generally spread over the south-facing hillside, serving to fill in the area below the pediment edge. No liner or other collection barrier was installed between the waste and the existing surfaces.

In the waste placement process, the waste material was mixed with soil materials. The volume of disposed waste and commingled soil is estimated at 160,000 cubic yards. Because of the slope angle, and the geological mapping and characterization of the colluvial and weathered bedrock material making up the hillside, the hillside in this area has been identified as susceptible to sliding even before the slope was covered with waste fill (Metcalf & Eddy 1995).



Disposal operations at the OLF ceased by the fall of 1968 possibly due to the Present Landfill (IHSS 114, located north of the IA) which began operation on August 17, 1968 (EG&G 1992a). The OLF waste material was covered with a soil layer after disposal operations ceased (EG&G 1994). Details on the placement of the soil cover layer, including exactly when it was constructed, are not available. Portions of the slope on the southern side of the landfill were later regraded to correct sloughing and erosion problems. Accurate and verifiable records of the wastes placed in the landfill are not available. However, approximately 74,000 cubic yards of sanitary waste and construction debris were disposed in the landfill (Kaiser-Hill 1996). These types of wastes likely included relatively small quantities of organics, paint and paint thinner, oil, pesticides, and cleaners (Rockwell 1988). Commonly used organics from 1952 to 1968 may have included trichloroethene, carbon tetrachloride, tetrachloroethene, petroleum distillates, 1,1,1-trichloroethane, dichloromethane, and benzene (Kaiser-Hill 1996). In the 1960s, the landfill may have received polychlorinated biphenyls (PCB) wastes (DOE 1992), such as carbonless copy paper, transformer and vacuum pump cleanup paper and rags, and small capacitors and fluorescent light bulbs. Metals such as beryllium, lead, and chromium, may also have been placed in the landfill (Rockwell_1988).

There is no information indicating that the OLF was used for routine disposal of radioactive material or other hazardous substance waste streams. During the period of operation of the OLF, several other areas within RFETS were used for the management and disposal of hazardous plant wastes, including radioactive waste. For example, some uranium wastes were buried in the east trenches, and drums with cutting oils and solvents were stored at the 903 Pad. These areas are described in the Historical Release Report (HRR) (EG&G 1992a) and subsequent annual updates. The majority of radioactive solid waste generated on site was disposed off site. Various controls and practices were used to segregate and manage radioactive wastes separately from plant sanitary waste and construction debris. Although the OLF was not operated for management or disposal of radioactive waste, information in the HRR and characterization results indicate that some waste contaminated with radioactive material, most notably wastes from buildings where depleted uranium (DU) operations were conducted, were disposed in the OLF. In addition, in 1965, 60 kilograms (kg) of DU were placed in the landfill after the DU, which was left on a pallet, reportedly ignited on a truck flatbed. The DU was probably covered with soil to extinguish the fire. Efforts were later made to retrieve the DU, however, only 40 kg were recovered. Further use of the affected area of the landfill was avoided (EG&G 1992a; DOE 1992). No record of any similar incident was found and workers have reported none. Further removal of DU in contaminated surface soil was completed in August 2004 leaving all surface soils below the ALs.

Activities listed for the OLF in October 1954 include its use as a burning pit for the plant (EG&G 1992a). Ash from the plant incinerator, graphite, used caustic drums, and general trash may have been dumped in the burn pit; however, no records of waste types have been found. Incinerator ash, for at least the first decade of plant operation, included ash derived from the incineration of combustible paper and other trash contaminated with low levels of DU surface contamination from Building 444, in addition to other combustible plant wastes (EG&G 1992a). Although some incinerator ash may have been disposed of in the OLF, the ash was routinely disposed of in several pits west of the OLF,

namely, IHSS-133, the Incinerator Ash Pits. Based on investigation and characterization of the Incinerator Ash Pits, a RFCA No Further Accelerated Action (NFAA) determination was approved. (EPA 2003) Backwash water discharged from the water treatment plant passed through a drainage channel on the western side of the burn pit, and flowed down to Woman Creek. No information is available identifying the period of operation for the burn pit.

In 1995, Metcalf and Eddy conducted geotechnical investigations at the OLF as part of the OU-5 Phase 1 RFI/RI and described the fill material encountered during the investigation. The material consisted of waste mixed with varying amounts of sandy, clayey gravel and cobbles derived from colluvium and Rocky Flats Alluvium. The waste materials in the fill included sheet metal, wood, broken glass, plastic, rubber, metal shavings, graphite sand, solid blocks of graphite, concrete, asphalt, and portions of 55-gallon steel drums. The waste fill ranged in thickness from 2 ft to over 11 ft.

Seepage emerging from the OLF after a major rainstorm in July 1986 was traced to an outfall pipe from the Building 460 footing drains (EG&G 1992a). Sloughing of material in the area of the outfall occurred as a result and the hillside materials may have been washed into the South Interceptor Ditch (SID). To prevent migration of materials, a containment embankment was constructed to prevent flow into Woman Creek (EG&G 1992). The outfall piping was also extended to the east to discharge beyond the landfill boundary (refer to Section 2.4).

Street cleaning wastes were apparently dumped in the OLF area. The duration of use of this area for street cleaning wastes is not known. In March 1991, EPA requested that the dumping cease because it may exacerbate any groundwater and soil contamination and it was inconsistent with the planned CERCLA response (EPA 1991b). In July 1991, the contractor notified DOE that it had instructed the appropriate departments not to use the landfill as a dumping site for street sweeping litter or concrete truck washout (EG&G 1991).

2.3 Description and History of IHSS 196 (Filter Backwash Pond)

The water treatment plant Filter Backwash Pond was located on the hillside north of Woman Creek, approximately 800 ft south of the water supply treatment plant in Building 124 (EG&G 1992). The treatment plant treats water that is delivered from the Denver Water Board reservoir and ditch system to the raw water pond located north of the West Access Road to produce the plant's potable water. The Filter Backwash Pond, also known as Pond 6, was used as a retention pond to allow sampling of filter backwash water. It was also described as an evaporation and settling pond (EG&G 1992b). There is no record of sludge or sediment removal from the pond (DOE 1992b).

Pond 6 was constructed in 1955. However, water from the water treatment plant was discharged at the OLF before the pond was constructed. The HRR (EG&G 1992a) refers to an October 1954 reference that indicates backwash water from the water treatment plant flowed through the western side of the burning pit and down to Woman Creek. It is possible that Pond 6 was constructed in the location of the burning pit (EG&G 1992a). It



is unclear when the Filter Backwash Pond was abandoned. By 1964, Pond 6 was no longer present, and the area was covered with fill (Kaiser-Hill 1996).

The effluent from the water treatment plant was discontinuous and probably made up of filter backwash, filter pre-wash, sludge blowdown, and other discharges from the water treatment process (EG&G 1992). It contained filterable solids removed from the raw water, as well as chemical flocculants (aluminum sulfate or lime) and residual chlorine (EG&G 1992).

2.4 Other Disturbances and Structures

Other disturbances and structures associated with IHSS Group SW-2 include a large surface disturbance located east of the landfill area, the SID, and two outfall pipes and their associated surface disturbances. An area of suspected surface disturbance and a possible pit were identified west of the landfill from a review of aerial photographs (EG&G 1994) (See Figure 2-1).

The surface disturbance area east of the landfill waste disposal area was also identified from review of aerial photographs for the OLF site (EG&G 1994). The area was active in the 1964 photography. Little historical information is available for this area; however, the area may have served as a storage yard for pipes and scrap metal (EG&G 1994). In the 1969 and 1971 aerial photographs, the area contains mounds of debris (EG&G 1994).

In 1980, the SID was built across the southern portion of the landfill (EG&G 1994). The purpose of the SID was to intercept runoff from the southern portions of the Rocky Flats Plant and divert the flow to Pond C-2. Two outfall pipes cross the OLF site. The original outfall pipe, constructed in 1986 (EG&G 1994), discharged storm water directly onto the landfill. This caused sloughing and sliding of the fill material. Slide material may have been removed from the SID and placed on the southern side of the gravel road constructed south of the SID (Metcalf & Eddy 1995). Sometime between 1986 and 1988, the original outfall pipe was abandoned and a new outfall pipe was constructed southeast across the OLF to discharge to the SID east of the landfill boundary. The buried outfall pipe discharges into a collection basin located east of the OLF. Sloughing, erosion, and construction of the outfall pipes may have exposed landfill waste at the surface.

2.5 Historical Interim Response Actions

Three separate response actions have been undertaken at the OLF. On July 23, 1979, contractors grading a road southwest of Building 444 outside the perimeter fence uncovered a portion of the landfill (EG&G 1992). The area was surveyed and three locations of depleted uranium were identified. One box of contaminated soil was removed (EG&G 1992).

The reach of Woman Creek adjacent to the western portion of the landfill was relocated because the creek threatened to erode into landfill materials (Singer 2002). Specific information on the relocation of Woman Creek, including when the creek was relocated, is not available.

On June 7, 1990, EPA, CDPHE, and DOE staff conducted an inspection to evaluate previously identified exposed radioactive debris in the northwestern part of the OLF (EPA 1990). It is not known exactly when the debris became exposed; however, the area apparently was identified in April 1990 as a barrel containing radioactive materials (DOE 1990). A radioactive materials survey near the barrel encountered low levels of depleted uranium (EG&G 1990a). The area was roped off and access was restricted. Soil and water samples were collected and a requested radiological survey of the entire OLF area was subsequently conducted (EG&G 1990b). A gamma radiation survey conducted in late 1990 identified ten locations of elevated gamma radiation (Kaiser-Hill 1996).

A radiological survey with a Field Instrument for the Detection of Low-Energy Radiation (FIDLER) was also conducted at the OLF in 1993 as part of the OU-5 Phase 1 RFI/RI (EG&G 1994). Of the ten areas identified in 1990, the FIDLER survey did not identify any anomalous levels of radiation at seven of the locations. Within the bounds of two areas in the center of the OLF identified by the 1990 survey, nine areas of anomalous levels of radiation were found. These areas were posted as Radiologically Controlled Areas. Several pieces of radioactive material were removed from these areas on May 28, 1993, during an emergency removal action. The material removed included a 4- to 6-inch-diameter piece of concrete coated with a corroded metallic material, and several small (1- to 2-inch-diameter) spherical pieces of rusty material. The materials were removed for subsequent management as radioactive material (EG&G 1994). Analyses indicated that the materials contained depleted uranium. In those areas where a specific source of the anomalous radioactivity could not be identified, surface soil samples were collected.

Annual walkdowns of the landfill surface have been conducted each spring to search for classified items since 2000. No classified items have been found; however, several carbon molds have been removed from the area and appropriately dispositioned. Some of the items have exhibited very low levels of depleted uranium activity.

2.6 Slope Stability

Landslides have historically occurred at the OLF site within the colluvium and weathered bedrock prior to waste placement. During the 1995 geotechnical study, these historic areas of discrete landslides were identified in the OLF, as well as general areas of sliding (Kaiser-Hill 1996). In addition, the geotechnical study identified three potential slope failure mechanisms operating in the OLF area. These mechanisms are:

- Shallow landslides consisting of waste fill sliding on severely weathered claystone;
- Shallow landslides consisting of colluvium sliding on or with severely weathered claystone; and
- Deeper landslides consisting of movement within moderately weathered claystone at depths up to or approximately 35 ft, especially in areas of steeper slopes.

Landslides on the claystone bedrock slopes beneath the alluvial surface probably commenced after the slopes were initially exposed by continued stream erosion through the pediment, rendering the overlying materials unstable and predisposing them toward movement. Aerial photographs of the Woman Creek drainage prior to the waste disposal support this theory by indicating that most landslides occurred prior to fill deposition. There is no indication of current landsliding or mass movement of the waste and soil fill. Additional geotechnical data have been gathered to further evaluate the stability of the OLF (see Section 3.4).

2.7 Existing Conditions

It has been approximately 36 years since disposal operations ceased at the OLF. The area now has well-established grasses and forbs, several stands of large trees, and several small areas of wetland vegetation. Most of the waste is currently covered by soil up to several feet thick; however, the surface of the area is hummocky, and some disposed materials are protruding from the ground in some areas. This indicates uneven waste and cover soil layer placement resulting in erosion and sloughing processes that uncover the wastes. The thickness and final grading and cover soil layer appears to be inadequate in a few places. There is no indication of current landsliding or mass movement of the waste and soil fill. There are no seeps in the area. Stormwater ponding occurs in several areas because of the surface topography. Several radionuclide contamination "hot spots" have been identified via surface soil sampling (refer to Section 4.3) and were removed in August 2004 (see Appendix C).

3.0 ENVIRONMENTAL SETTING

3.1 Physiography

RFETS is located on the western margin of the Colorado Piedmont section of the Great Plains Physiographic Province at an elevation of approximately 6,000 ft (Kaiser-Hill 1996). The Colorado Piedmont is characterized as an area of dissected and denuded topography, representing an old erosion surface along the eastern margin of the Rocky Mountains. Several pediments (broad sloping planes formed by coalescing alluvial fans along a mountain front) developed across bedrock in the RFETS area during the Quaternary Period (Scott 1963). The Rocky Flats pediment is the most extensive of these pediments.

The RFETS IA is located on a relatively flat surface of the Rocky Flats pediment. The pediment surface has been eroded by Walnut Creek on the north and Woman Creek on the south. As a result, the pediment surface is located at an elevation of 50 to 150 ft above the creeks. The grade of the gently eastward-sloping surface of the Rocky Flats pediment ranges from one percent in the IA of RFETS to approximately two percent just east of the IA. Further east, the pediment's nearly flat-lying surface gives way to lower, gently rolling terrain of the High Plains section of the Great Plains Physiographic Province (Kaiser-Hill 1996).

Four ephemeral creeks drain the surface water from RFETS. Surface water that flows from the northern portion of RFETS is drained by Rock Creek, which is a northeast-trending tributary of Coal Creek. The central and southern portions of the site are drained by Walnut Creek, South Walnut Creek, and Woman Creek. These drainages are all tributaries of Big Dry Creek that flows eastward. Coal Creek separates all of the streams on the Rocky Flats pediment from the Front Range foothills. Surface water flow in these creeks is generally ephemeral; however, some reaches may support intermittent or perennial flow.

3.2 Climate

The climate at RFETS is characterized as semiarid (Kaiser-Hill 1996) with a mean annual precipitation of approximately 15.5 inches, based on 20-year means for Boulder and Lakewood, Colorado. The wettest season is spring (March through May), which accounts for approximately 40 percent of the annual precipitation, much of which is snow. Thunderstorms during the summer months provide another 30 percent of the annual precipitation. The precipitation gradually declines through the summer, fall, and winter (Kaiser-Hill 1996). Average annual pan evaporation in central Colorado is approximately 55 inches (DBS 2001).

The predominant wind direction at RFETS is northwesterly, and average wind speeds are under 15 miles per hour. Daytime heating causes upslope winds to form, with northeasterly winds common over the broad South Platte River Valley. More localized southeasterly winds also occasionally occur during the day at the Site because the terrain is oriented southeast toward Standley Lake and the city of Arvada. The winds reverse at



night with a shallow, westerly drainage wind forming over the Site and a broad, southerly drainage wind forming over the South Platte River Valley (DOE 1999).

RFETS is noted for its strong winds. Gusty winds frequently occur with thunderstorms and the passage of weather fronts. The highest wind speeds occur during the winter as westerly windstorms, known as chinooks. The windstorm season at the Site extends from late November into April, with the height of the season usually occurring in January. The windstorms typically last 8 to 16 hours, with wind speeds exceeding 75 miles per hour in almost every season. Wind gusts exceeding 100 miles per hour are experienced every three to four years (DOE 1999).

3.3 Geology

Geologic units beneath the OLF consist of unconsolidated Quaternary deposits that lie unconformably over Cretaceous claystone bedrock. Six north-south cross sections were developed during the 1995 geotechnical study. One cross section, Figure 3-1, is typical of the other cross sections developed in the study. (EG&G, 1995; Kaiser-Hill, 1996) The unconsolidated surface deposits include the Rocky Flats Alluvium that dominates the surface of RFETS, colluvial materials that form the slopes of the Woman Creek valley, and valley fill materials on the bottom of the Woman Creek valley. These materials overlie the Laramie Formation bedrock (Metcalf & Eddy 1995). Geologic units in the OLF area are described below.

3.3.1 Rocky Flats Alluvium

The Rocky Flats Alluvium was deposited by a system of coalescing alluvial fans aggraded by debris flows and braided streams along the base of the Front Range at the mouth of Coal Creek Canyon (EG&G 1995). The alluvial deposits generally consist of beds and lenses of poorly sorted, clast- and matrix-supported, white-to-pink, sandy, cobbly gravel, gravelly sand, and silty sand (Kaiser-Hill 1996). The thickness of this unit ranges from about 3 to 30 ft in the areas where the pediment deposits overlie Cretaceousaged bedrock (Kaiser-Hill 1996).

3.3.2 Colluvial Deposits

Colluvial deposits along the valley slopes at RFETS are middle Pleistocene to recent in age (Kaiser-Hill 1996). The colluvial material commonly consists of dark-gray to light, reddish-brown, silty sand, sandy silt, clayey silt, and silty clay that contains minor amounts of boulders and cobbles. The unit locally includes clast- and matrix-supported boulders and cobbles, and coarse to fine gravel in a silty-clay matrix. These materials are well graded to poorly graded and unstratified to poorly stratified. Clasts are typically subangular to subrounded, and their sedimentological composition reflects that of the bedrock and surface deposits from which they were derived. The thickness of the colluvial deposits ranges from 3 to 15 ft.

In the OLF area, the unconsolidated colluvial deposits consist of sandy, clayey gravel (derived from the adjacent Rocky Flats Alluvium) to sandy clay (Metcalf & Eddy 1995). The colluvium is frequently mixed with fill material in the landfill. Soil borings indicate


the thickness of the colluvium ranges from 1 to 13 ft. The colluvium is damp to moist, although it can be wet near its contact with the Laramie Formation (Metcalf & Eddy 1995).

3.3.3 Valley-fill Alluvium

Valley-fill alluvium, located along the Woman Creek drainage, includes channel and terrace deposits related to the modern stream. These recent alluvial deposits are commonly grayish-brown, slightly cobbly, silty sand to sandy, clayey silt in the upper part, and poorly sorted, clast-supported, slightly cobbly, gravel in a light yellowish brown, clayey, silty sand matrix in the lower part (Kaiser-Hill 1996). Clasts are mostly subangular quartzite, with a minor amount of subrounded sandstone derived from older Quaternary deposits. The thickness of these deposits ranges from approximately 3 to 15 ft, with an average of about 10 ft.

During geotechnical investigations at the OLF (Metcalf & Eddy 1995), valley fill alluvium was encountered in three boreholes along the toe of the landfill. The alluvium consisted of medium dense-to-dense, sandy, silty, clayey gravel with cobbles. The alluvium ranged from 5 to 7 ft thick, and groundwater was encountered as shallow as two feet below ground surface (bgs).

Figure 3-1 Typical Geological Cross Section of the Original Landfill



3.3.4 Laramie Formation

Bedrock in the OLF area is Laramie Formation (Kaiser-Hill 1996). The Cretaceous-aged Laramie Formation is approximately 600 to 800 ft thick. It has been informally divided into upper and lower members (Kaiser-Hill 1996). The upper Laramie Formation is dominantly composed of fine-grained sedimentary rocks (primarily claystone with no thick sandstone beds). The upper part of the upper Laramie Formation is approximately 300 to 500 ft thick, and consists primarily of olive-gray to yellowish-orange claystone with large ironstone nodules. A few thin, discontinuous coal seams occur in the upper Laramie Formation. Lenticular beds of platey laminated or friable, calcareous, fine-grained, light olive-gray sandstone occur in the upper Laramie Formation, particularly in the upper portions of the formation.

In the OLF area, the Laramie Formation is a weak claystone formation that underlies the soil-bearing slopes in the OLF (Metcalf & Eddy 1995). It is severely weathered (soft, plastic, and moist) in its near-surface aspect and underlies surficial materials in over 50 percent of borings. Moderately weathered Laramie Formation underlies the severely weathered Laramie Formation and is locally plastic, soft, damp, and fractured. It was encountered underlying surficial material in approximately 35 percent of the borings, indicating that the severely eroded Laramie Formation was sometimes displaced through sliding or erosion. The unweathered Laramie formation is the deepest component of the upper member and is similar to the moderately weathered Laramie Formation, although somewhat drier (Metcalf & Eddy 1995).

3.3.5 Inferred Faulting

Several inferred faults had been identified during site-wide geological investigations at RFETS (EG&G 1995). The longest of these is a northeast-trending reverse fault that extends from Woman Creek to Colorado Highway 128 across the western part of the IA. The fault plane is assumed to dip to the west. A borehole drilled into this fault, or fault zone, in another portion of RFETS filled with water within a few hours of drilling (EG&G 1995). The Geological Characterization Report (EG&G 1995, Figure 7-6) shows the fault trace going through the western side of the OLF.

The geotechnical investigation of the OLF (Metcalf & Eddy 1995) considered the presence of this fault. Metcalf & Eddy (1995) identified the bedrock fault as trending southwest from the vicinity of Building 371 through the OLF between borings 59794/71194 and 57194. The general location of the fault is shown on Figure 3-2. The location identified by Metcalf & Eddy (1995) and presented in the Final OU 5 RFI/RI Report (K-H 1996) goes through the center of the landfill. This location is based on the Systematic Evaluation Program (Geomatrix 1995). An evaluation of inferred faults in the vicinity concluded that this fault was not capable of generating future earthquakes (Geomatrix 1995). The fault is not expected to disrupt the engineering features or impact the structural integrity of the landfill, and does not appear to impact groundwater hydrogeology.




Figure 3-2 Inferred Fault in Original Landfill Area

3.4 Summary of Geotechnical Investigations

A geotechnical investigation conducted at the OLF in 1995 (Metcalf & Eddy, 1995) indicates some uncertainty of the stability of the landfill, and that landsliding of the soils, bedrock and/or waste may be possible. Within the scope and limitations detailed in the 1995 investigation, the work is considered quite thorough and comprehensive. Detailed field investigation of the landfill site was conducted; enabling sound geologic and geotechnical interpretation of site conditions, subsurface materials, and landsliding conditions. However, the laboratory strength testing of samples retrieved from the field investigation appeared somewhat limited, probably due to the preliminary nature of the study and also some sample recovery and disturbance problems in the weaker materials most desired for testing. Critical strength parameters for historical sliding at interface surfaces could not be determined through laboratory testing. Therefore, a back-calculation procedure was used in specific analyses, with an assumed factor of safety of 1.0 at failure for slope geometry and geotechnical parameters. Therefore, to further define the level of landfill stability and to support design of the accelerated action, a topographic survey of the current surface was obtained and a follow-up geotechnical investigation was conducted in 2004. The purpose of this second geotechnical investigation was as follows:

• Obtain and conduct geotechnical testing on materials that most affect the overall stability of the OLF area;

- Assess the stability of the OLF and underlying soil and bedrock using the new geotechnical data;
- Assess the impact of groundwater on the underlying soil and bedrock stability; and
- Collect the required geotechnical information to design a long-term landfill stability monitoring plan.

The new geotechnical investigation data were also used to assess the structural stability impact of a buttress fill at the toe of the landfill slope. The following paragraphs summarize the follow up geotechnical investigation. A detailed presentation of the geotechnical data and stability analysis can be found in Geotechnical Investigation, Phase 3 Stability Analysis, Technical Support Memorandum (Earth Tech 2004).

There is no current evidence of landsliding or mass movement of the waste fill and soil; however, aerial photographs of the area prior to waste disposal suggest that the pre-landfill slope exhibited signs of previous instability and natural erosion. The current surface is uneven, with areas of sloughing and erosion resulting from historic landslides in the area prior to waste placement, poor waste management practices, and erosion and subsequent slope instability caused by poor surface water controls during and after waste placement operations.

The slope is approximately 90 to 100 ft high, as measured from the base of the landfill to the pediment surface. The upper 40 to 50 ft of the section consists of Rocky Flats Alluvium covered by 10 to 15 ft of waste and soil cover. The remaining 40 to 50 ft of the slope consists of moderately to severely weathered claystone overlain by various thicknesses of waste, constructed fill, and colluvium from past sliding.

The moderately to severely weathered claystone beneath and beyond the toe of the slope varies from 10 to 20 ft in depth and then transitions into unweathered claystone. At and beyond the toe of the slope, the weathered claystone is typically overlain by 5 to 10 ft of alluvium derived from the Woman Creek floodplain.

Groundwater within the slope generally occurs at or slightly above the claystone interface. It is locally higher near the middle of the fill due to ponding in closed depressions behind the fill and the poorly drained SID approximately located one-third the way up the OLF slope.

Waste was generally mixed with Rocky Flats Alluvium materials. The waste/soil matrix varies in consistency and generally consists of a range of silty gravel, clayey sand, and low-plasticity inorganic clay materials. Plasticity index values range from 17 to 31 percent. Effective shear strength values, estimated from soil descriptions, are estimated to be in the range of a friction angle of 30 degrees with a cohesion of 50 pounds per square foot.

Rocky Flats Alluvium is a generally dense, sandy, clayey gravel material with cobbles. However, it sometimes contains beds of stiff to hard clays and sandy clays, as well as fine, medium-dense to very dense clean to clayey sands. Laboratory tests by Metcalf and Eddy indicated the presence of low plasticity inorganic clay and high-plasticity inorganic clay materials with the low-plasticity inorganic clay materials having a plasticity index value of approximately 17 percent. Effective shear strength parameters are estimated, from soil

descriptions and Metcalf and Eddy laboratory testing, to be in range of a friction angle of 37 degrees.

Colluvium located along and near the toe of the slope consists of a variety of materials from waste, Rocky Flats Alluvium, and weathered claystone materials. Tests by Metcalf and Eddy on clayey colluvium materials derived mainly from the weathered claystone materials indicated the presence of high-plasticity inorganic clay materials with plasticity index values in the range of 31 to 51 percent.

Moderately to severely weathered claystone is predominately classified as a high-plasticity inorganic clay material. Metcalf and Eddy laboratory tests indicated plasticity index values in the range of 30 to 52 percent.

Effective shear strength parameters for the colluvium and weathered bedrock from the recent geotechnical testing estimates a friction angle equal to 20 degrees (drained strength) and 15 degrees (undrained strength). These strengths are the lower bound of all the test data and assume no cohesion. However, these soils do exhibit cohesion ranging from an average of 410 to 510 pounds per square foot.

Tests were not conducted on the unweathered claystone materials because any sliding is expected to occur within the weaker weathered claystone layers above.

Further details of the followup geotechnical investigation are presented in the A detailed presentation of the geotechnical data and stability analysis can be found in Geotechnical Investigation, Phase 3 Stability Analysis, Technical Support Memorandum (Earth Tech 2004).

3.5 Groundwater

The uppermost groundwater is shallow, unconfined groundwater that occurs within the Rocky Flats Alluvium, colluvial deposits, valley fill alluvium, and weathered Laramie Formation. This water-bearing zone is referred to as the Uppermost Hydrostratigraphic Unit (UHSU) (EG&G, 1995). The UHSU is not an "aquifer" because it is not capable of yielding significant and usable quantities of groundwater to wells or springs (EG&G, 1995b). Soil borings in the Rocky Flats alluvium indicate that groundwater appears hydraulically disconnected from the lower hydrostratigraphic unit (LHSU) groundwater.

Characteristics and dynamics of the UHSU groundwater flow system at RFETS have been described in detail in the former Site-Wide Water Balance (SWWB) modeling work (KH, 2002). Results showed that UHSU groundwater at RFETS typically flows towards the nearest stream. Local flow rates and directions are strongly affected by the hydraulic properties of unconsolidated material, and the morphology and orientation of the underlying claystone bedrock and topographic surfaces. The shallow groundwater system is recharged mostly by direct infiltration of precipitation that is then mostly lost via evapotranspiration. As groundwater moves from higher elevations towards streams, an increasing amount is lost through evapotranspiration, and only a small amount actually contributes as baseflow to streams. Groundwater elevations typically vary seasonally less than 5 ft, mostly in response to direct precipitation recharge in wetter periods and evapotranspiration in warmer months. Water levels above the weathered bedrock range from 0 to 5 ft along Woman Creek; below the bedrock in the

east-central waste area; 5 to 10 ft in the central waste area; 0 to 5 ft in the western waste area; and from 10 to more than 40 ft above the bedrock north of the OLF.

3.6 Integrated Hydrologic Model Development and Results

A fully integrated hydrologic flow model was developed to support evaluation of several possible closure configurations for the OLF (Integrated Hydro Systems 2004). The approach in developing a model for the OLF is similar to that described in the Site-Wide Water Balance (SWWB) modeling (K-H 2002). Current system flows are first simulated to demonstrate that assumed model parameter values are reasonable. Then specific changes are made in the model to simulate the integrated hydrologic system response to closure configuration modifications. The MIKE SHE code, developed by DHI (1999), is used to simulate integrated flows at the OLF. The code couples subsurface flows, unsaturated and saturated zone, with surface flows, overland and channel flow. Effects of evapotranspiration and snowmelt are also considered in the model, and output is generated subhourly over a full year.

Available geologic, hydrologic, and chemical data in the OLF and surrounding area were reviewed and then compiled into a spatial Geographic Information System (GIS) database to support model development. Most of this information was obtained from the former SWWB modeling, although several new datasets were prepared. Available field geologic borehole logs were carefully reviewed to define approximate waste and bedrock surface contacts. Recent logs for the area, along with a higher-resolution surface topography, were then used to construct more accurate weathered and unweathered bedrock surfaces in the OLF area than previously prepared (K-H 2002). Refinement of the weathered bedrock surface is important because this was found to strongly control groundwater flow gradients and levels in hillslope areas.

Thicknesses of unconsolidated material from the Building 440 area, south through the waste to Woman Creek, range from over 20 to less than 5 ft. Thickness of the waste material is also variable, ranging from less than 5 ft in the east-central area to more than 12 ft to the west. The unweathered bedrock thickness is generally about 20 ft through the OLF area.

More than 10 years of groundwater level data in the area, including recent 2004 data, were also reviewed. Groundwater level fluctuations within the OLF range from 5 to 10 ft over the year, reflecting seasonal recharge, evapotranspiration and drainage effects. The lack similarity between fluctuations in the OLF and those adjacent to the OLF suggests that unsaturated and saturated zone hydraulic properties of the waste area are similar to nonwaste areas. Groundwater depths in the UHSU range from about 20 to 30 ft below ground near the Building 440 area on the mesa to about 15 ft below ground within the waste, to less than about 5 ft below ground along Woman Creek. In the Lower Hydrostratigraphic Unit (LHSU) wells in the OLF area groundwater depths are significantly lower than in nearby UHSU wells (57194, 71194 are greater than 100 ft, suggesting the LHSU and UHSU are hydraulically disconnected in the area. Finally, a potentiometric surface map constructed using time-averaged water level information indicates there is a west-east groundwater divide just north of Building 444. Therefore, groundwater south of this divide slowly flows toward Woman Creek.

Several steps were involved in constructing the integrated flow model. First, a 25-ft numerical grid was prepared to better simulate local flow conditions associated with the OLF (a 200-ft grid

resolution was used in the SWWB model.) Several GIS techniques were used to then convert spatial hydrogeologic GIS information onto the finer grid. Spreadsheet algorithms were then used to convert gridded GIS information into model input. Unsaturated and saturated zone hydraulic properties determined through integrated model calibration conducted for the original SWWB model and subsequent VOC fate and transport modeling (K-H 2004) were specified in the localized model. However, new values for drain conductances and hydraulic properties for the waste had to be determined through initial OLF model simulations.

The integrated model of the current system configuration, using climate data from October 1999 through September 2000 reproduces observed flow conditions well. Model simulations require that the Water Year (WY) 2000 climate sequence is cycled for three consecutive years to stabilize effects of prescribed initial conditions. Model performance is assessed by comparison of simulated and observed time-averaged water levels at well locations within the model area. Results indicate that average difference between simulated and observed levels within the OLF are less than one foot, and over the model area differences are just over a foot. At some well locations differences are greater than one foot, but can attributed to local scale effects not captured by the resolution of the model. Simulated annual surface flow at gage GS22, though less than observed, indicates most surface events are captured in peak flow, timing of events, snowmelt and baseflow. Additional adjustment of drain conductances would only improve the comparison between observed and simulated surface flows. Ultimately, the drain conductance values are not important in evaluating impacts of closure configurations on system flows because the drains are removed in these simulations.

Several closure configurations were evaluated as summarized below, including assumptions:

- Scenario 1 IA Regrade-only
 - o IA undergoes closure configuration (as per above)
 - No changes made to existing OLF area,
 - o Typical climate year sequence assumed (WY2000).
- Scenario 2 IA & OLF Regrade
 - o IA undergoes closure configuration (as per above)
 - o OLF area is regraded,
 - o OLF area is re-vegetated,
 - o Fill material is used as part of regrade (assume Qrf),
 - o Typical and Wet Year (100-year basis) climate year sequences are assumed.
- Scenario 3 IA & OLF Regrade, Fill Buttress, and Drain
 - o Same as Scenario 2,
 - o Includes Fill Buttress and Drain on Upgradient side.
 - o Typical climate year sequence assumed (WY2000)

- Scenario 4 IA & OLF Regrade, Fill Buttress, Drain, and Slurry Wall
 - Same as Scenario 3, but includes slurry wall immediately north of the waste area footprint.

Scenario 1 was simulated to show the relative effects of regrading the OLF for a typical climate year sequence (that is, WY2000). Within the OLF, simulated average-annual groundwater levels change less than one foot. Locally they adjust less than three feet. The west-central area generally increases, while the east-central area tends to decrease in response to IA closure modifications. For example, pavement, buildings, drains and water supply lines are removed and then the IA is regraded and revegetated.

In Scenario 2 (basecase) OLF closure configuration scenario, both the IA and OLF are reconfigured. North of the OLF, the IA is closed as described above. Within the OLF, the ground surface is regraded and assumes a mature stand of vegetation. Regrading the OLF surface causes areas within the OLF waste to be filled up to 20 to 30 ft, and cut up to 20 ft. As a result, the depth to bedrock becomes both shallower and deepens throughout the OLF waste area, causing adjustments in groundwater levels in the area. Both a typical and 100-year wet-year climate sequence are simulated to show average hydrologic conditions within the model area as well as conservatively high levels.

Results of simulating the OLF regrade show an average increase in groundwater levels over the IA. Locally, levels increase up to seven feet and decrease less than 4 feet. The model also shows that average annual simulated depths in shallow bedrock areas rise to near ground surface (west-central area) for typical climate conditions. For wetter periods of a typical climate year, groundwater can discharge as seeps to the ground surface. Depths are greatest toward the eastern and western ends of the waste area because these areas represent fill areas associated with the regrade. Saturated heights above the weathered bedrock surface increase from 3 to 7 feet compared to Scenario 1. A water balance of the waste area to unweathered bedrock indicates that most of the direct precipitation infiltrates the surface soil, and then either evapotranspires or enters the groundwater system as recharge. Model results also show that variability in groundwater levels and flow within the hillslope are controlled by direct recharge and evapotranspiration, rather than by lateral inflow. Most of the discharge from the OLF occurs by evapotranspiration rather than lateral subsurface flow.

In the wet-year climate sequence average annual groundwater levels increase 0 to 0.4 meter over the waste area. This increases the saturated heights above the weathered bedrock a similar amount.

In the third scenario, effects of adding the fill buttress and upgradient drain have a limited affect on upgradient groundwater levels. For example, levels decrease an average of less than one foot over the waste area, but locally decrease more than 10 feet along the drain assumed to extend to the top of the weathered bedrock. Simulated drain discharge rates are less than 1 gpm. Effects of adding a slurry wall in the fourth scenario down to the top of the weathered bedrock also show only limited effects on both upgradient and downgradient groundwater levels. Average levels within the OLF decrease less than one foot. Locally, levels on the upgradient side increase less than three feet, and levels on the downgradient (south) of the slurry wall decrease less than three

feet. The areal extent of change due to the slurry wall ranges from about 200 to 300 ft on either side.

3.7 Surface Water

The OLF is located within the Woman Creek drainage basin, which extends eastward from the base of the foothills near the mouth of Coal Creek Canyon to Standley Lake (Figure 3-3). The long-term average annual yield generated by this basin is 32.1 acre-ft, with average storms producing surface flows of 4 to 7 cubic ft per second (cfs). During extreme precipitation events (greater than the 15-year return occurrence based on precipitation), surface flows up to 40 cfs have been generated. Although seasonal flows can be low, Woman Creek receives continuous flow from Antelope Springs Creek. The reach of Woman Creek adjacent to the OLF is a gaining reach of stream (groundwater discharges to surface water); however, this inflow is likely due to inflow from the southern side of the valley and seepage from the old orchard area (Kaiser-Hill 1996).

The Woman Creek drainage basin has an artificial water control structure, the South Interceptor Ditch (SID), which intercepts runoff and routes it to Pond C-2. This runoff would normally flow into Woman Creek or percolate into the underlying subsurface materials of the basin. The Woman Creek diversion dam routes all Woman Creek flows less than the 100-year flood peak around Pond C-2 (Kaiser-Hill 1996). With the completion of the Woman Creek Reservoir, located just east of Indiana Street and operated by the city of Westminster, Woman Creek flows are detained in cells of the reservoir until the water quality has been ensured by monitoring of RFETS discharges via Woman Creek Reservoir into the Walnut Creek Drainage below Great Western Reservoir.




Figure 3-3 Surface Water Features

In the past, most natural flows in Woman Creek were diverted to Mower Reservoir and did not exit RFETS via Woman Creek. This is no longer the case. The Mower Ditch headgates were upgraded, and water in Woman Creek leaves RFETS via Woman Creek (at GS01) and enters the Woman Creek Reservoir. In the past, water from Pond C-2 (located off-channel in the Woman Creek drainage) was sampled and then pumped to the off-site Broomfield Diversion Ditch. Currently, RFETS discharges water from Pond C-2 directly into Woman Creek via a pump (at GS31); the water then flows to the Woman Creek Reservoir.

3.8 Ecological Setting

Even though the OLF is a highly disturbed industrial site, the area includes the Preble's Meadow Jumping Mouse (PMJM) protection area and wetland areas associated with surface water in the area. PMJM is listed as threatened by the U.S. Fish and Wildlife Service (USFWS). This listing provides special protection for the species under the Endangered Species Act, and potential remedial actions at the OLF must be evaluated for potential impacts to PMJM.

PMJM have been identified in all the major drainages of RFETS: Rock Creek, Walnut Creek, and Woman Creek, and the Smart Ditch drainages. Native plant communities in these areas provide a suitable habitat for this small mammal. PMJM at RFETS are restricted to riparian areas and pond margins, apparently requiring multistrata vegetation with abundant herbaceous cover. PMJM populations at RFETS are found in association with the riparian zone and seep wetlands across RFETS. The vegetation communities that provide PMJM habitat include the

Great Plains riparian woodland complex, tall upland shrubland, wetlands adjacent to these communities, and some of the upland grasslands surrounding these areas. Recent studies have produced a better understanding of population centers of the species, and studies over the past several years have provided data to help estimate numbers of individuals within each population unit (RFETS 2000).

PMJM have been captured along Woman Creek in the area of the OLF where a significant amount of suitable habitat occurs. The PMJM were captured in riparian areas with well-developed shrub canopies and a relatively lush understory of grasses and forbs. This is typical of habitats occupied by the subspecies throughout its range (Kaiser-Hill 1996). The PMJM habitat and buffer area (Figure 3-4) includes a portion of the OLF area below the SID. The PMJM habitat and buffer area continues east-west along Woman Creek.

Jurisdiction wetlands in the OLF area are also shown on Figure 3-4, and include the area directly surrounding the SID. South of the landfill, wetland areas are associated with springs and riparian fringe in the Woman Creek drainage. The SID wetlands were created when the ditch was built, and may be considered isolated wetlands. The SID wetlands is a narrow, linear system, dominated by cattails and coyote willows and, as such, has lower functional integrity than the natural wetlands associated with Woman Creek.




Figure 3-4 Wetlands and PMJM Areas Near the Original Landfill

4.0 ENVIRONMENTAL DATA SUMMARY AND RFCA ACTION LEVEL COMPARISON

This section summarizes environmental data that have been collected at the OLF for surface soil, subsurface soil, groundwater, surface water, and sediment. Analyte concentrations are compared to Site background levels to determine potential contaminants, and are compared to RFCA Action Levels (ALs) to render accelerated action determinations in accordance with RFETS Action Levels and Standards Framework for Surface Water, Ground Water and Soils, RFCA Attachment 5 (ALF).

4.1 Site Characterization Data

The data used to characterize the nature and extent of contamination in and around the OLF were collected primarily in the early 1990s and are documented in the Operable Unit 5 (OU 5) Phase 1 Remedial Investigation/RCRA Facility Investigation (OU-5 Phase 1 RI/RFI) (Kaiser-Hill 1996). The OLF coincides with OU-5 Phase 1 RFI/RI Area of Concern 1 (see Figure 2-1).

Additional sampling of groundwater and surface water at or in the proximity of the OLF has occurred since that time. This additional sampling and analysis was planned and documented in accordance with the RFCA Integrated Monitoring Plan (IMP) (DOE et al. 1997). The RFCA Parties evaluate the IMP annually for adequacy and changes based on previous monitoring results, and changed conditions; planned activities and public input are made with the approval of CDPHE and EPA.

The scope of the OU 5 Phase 1 RFI/RI is presented in the OU 5 Phase 1 RFI/RI Work Plan (OU 5 Work Plan) (EG&G 1992). The OU 5 Work Plan includes the rationale for the number and location of samples. It was reviewed by EPA and CDPHE and subsequently approved and issued on February 28, 1992. Development of the OU 5 Work Plan included a Data Quality Objective process to describe the quantity and quality of data required. Data needs were identified to characterize the physical and hydrogeologic setting, assess the presence of contamination at each site, characterize the nature and extent of contamination, and support the evaluation of remedial alternatives based on effectiveness, implementability, and cost. The type, number, and location of samples were based on meeting these needs. Results of these investigations are contained in the 1996 RFI/RI Report for the OU 5 Woman Creek Priority Drainage (Kaiser-Hill 1996).

Sampling locations were selected based on earlier investigations and reviews of historical records, which included earlier groundwater and surface water analytical data, aerial photographs, site records, a magnetometer survey, and radiation surveys. All sampling and analysis activities were conducted in accordance with the Quality Assurance requirements of the OU 5 Work Plan. Data gaps were identified based on results of the earlier investigations, and additional sampling and geotechnical investigation was performed to fill these gaps.

The RFI/RI sampling program resulted in the following data related to the OLF:

- Surface soil: 7,568 validated analyses from 70 surface locations;
- Borehole samples to bedrock: 24,964 validated analyses from 175 soil samples;
- Groundwater: 31,171 validated analyses from 213 samples from 50 wells; and

• Surface water: 25,384 validated analyses from 15 locations.

Investigations also included geotechnical evaluations, groundwater investigations, hydrogeologic testing, storm sewer sampling, and air monitoring. Other investigations conducted in the same time frame included the following:

- Field Instrument Detection Low Energy Radiation and High Purity Germanium gamma radiation surveys to detect and identify near-surface areas of contamination from radioactive materials;
- Magnetometer survey to locate ferrous materials and anomalies;
- Electromagnetic survey to delineate dump boundaries, saturated materials, and anomalies;
- Cone penetrometer tests to gather geotechnical information on the waste fill, alluvium, and bedrock.; and
- Soil gas survey for VOCs and combustible gases to locate possible sources of these constituents.

4.2 Data Compilation and Evaluation

The OU 5 Phase 1 RFI/RI Report fully compiles, discusses, and evaluates the results of all sampling activities at the OLF, as well as downslope/downgradient of the OLF. To simplify and focus the evaluation of the source containment presumptive remedy, only the RFI/RI analytical data that are directly relevant to the OLF IHSS were used in the action level comparison. These data include OU 5 RFI/RI surface and subsurface soil data for all sample locations within or immediately adjacent to the IHSS (Figures 4-1 and 4-2), groundwater data for Upper Hydrostratigraphic Unit (UHSU) wells within and downgradient of the IHSS (Figure 4-3), and surface water and sediment data for Woman Creek and the South Interceptor Ditch sampling locations closest to the IHSS (Figures 4-4 and 4-5). Groundwater and surface water data also include data that have been collected since the RFI/RI during routine sampling in accordance with the IMP. All data were extracted from the RFETS Soil Water Database (SWD).

Analytical data for surface soil (ending depth for the sample interval is 6 inches or less), subsurface soil (ending depth for the sample interval is greater than 6 inches), groundwater, surface water, and sediment have been compared to RFETS background levels. Background levels for metals and radionuclides in subsurface soil (geologic material of the UHSU), groundwater (total and dissolved concentrations for the UHSU), surface water (total and dissolved concentrations for streams), and sediment are from the Background Geochemical Characterization Report (DOE 1993). Background values for surface soil are from the Geochemical Characterization of Background Surface Soils: Background Soils Characterization Program (DOE 1995). Because of difficulties in determining the appropriate background concentrations for organic compounds, any detection of an organic compound is considered an above-background observation. Results were determined to be "detect" or "nondetect" based on the result qualifier flags supplied by the laboratory.

The OLF data are summarized in Tables 4-1 through 4-7 for surface soil, subsurface soil, groundwater, upgradient Woman Creek surface water (stations SW039, SW040, SW041, and SW506), downgradient Woman Creek surface water (stations SW032, SW033, SW10295,

¹ For water, samples were split into "dissolved" and "total" based on whether the samples were filtered.

SW50193, and SW50293), SID surface water (stations INT. DITCH, SW036, SW038, SW129, and SW500), and sediment (stations INT. DITCH, SW036, SED506, SED507, SED41400, and SED51693), respectively. These summary tables present only those analytes that were detected above background and the Method Detection Limit² in order to limit the tables to analytes that are potentially contaminants at the OLF. The entire analytical program for the samples addressed in Section 4.0 is summarized in Appendix B.

4.3 Surface Soil

As detailed in Table 1 of Appendix B, surface soil samples were analyzed for metals, radionuclides, volatile organic compounds (VOCs), semi-volatile organic compounds (SVOCs), pesticides, and PCBs. As shown in Table 4-1, metals, radionuclides, and organic compounds have been detected above background levels in surface soil; however, only uranium and a few polynuclear aromatic hydrocarbons (PAHs) are present in surface soil above the RFCA ALs.

Uranium contamination is present in surface soil above the ALs at four sample locations. As shown on Figure 4-6, one sample location is on the northwestern boundary of the OLF. This area was initially identified by gamma radiation surveys, which indicated it was a small, localized area of contamination. The uranium contamination at this location coincides with the action discussed in Section 2.5 for debris that became exposed at the surface in April 1990, which was surveyed and determined to be contaminated with depleted uranium. It was further investigated in accordance with the OU-5 Work Plan.

The other three sample locations where uranium concentrations are above the ALs are at the center of the landfill (Figure 4-6). Elevated gamma radiation in this area was initially identified by the 1990 gamma radiation survey and was further investigated in accordance with the OU 5 Work Plan. The OU 5 Work Plan gamma survey identified nine areas of elevated radiation roughly bounded by the surface soil locations with the above AL uranium concentrations. As discussed in Section 2.5, debris was removed from this area in May 1993 during the OU 5 gamma survey. The uranium contamination at this location could also be a remnant of the depleted uranium cleanup operation that occurred in response to the dumping of 60 kg of burnt depleted uranium, as discussed in Section 2.2.

Examination of the uranium isotope concentrations shown on Figure 4-6 indicates that the four sample locations with uranium isotope concentrations above the ALs have a uranium-238/uranium-234 activity ratio of approximately 10, which is indicative of depleted uranium. The other above-background concentrations of uranium in the area have associated uranium-238/uranium-234 activity ratios that are lower, in some cases as low as approximately 1, which is indicative of natural uranium.

² For the Section 4 summary tables, an analyte is not listed if the maximum concentration does not exceed background and the Method Detection Limit (MDL) listed in Appendix E of the Industrial Area and Buffer Zone Sampling and Analysis Plan (IABZSAP) (DOE 2004). This MDL may differ from the reported sample MDL. The IABZSAP MDLs are considered representative of what most laboratories can achieve and have been used because the MDL originally reported could have been either an Instrument Detection Limit (IDL), MDL, or Reporting Limit (RL) (supporting documentation is unclear). A "U qualified" result is always considered a non-detect regardless of whether the value exceeds the IABZSAP Appendix E MDL because the laboratory reported it as a nondetect.

³ The U238/U234 ratio of 10 is based on the weight fractions of the isotopes in depleted uranium as provided in the 1988 DOE Publication 1 "Health Physics Manual of Good Practices for Uranium Facilities" (Bryce et al. 1988). They are as follows: uranium-238 – 0.9975; uranium-235 – 0.0025; uranium-234 – 0.00005. These were converted to activity fractions using the specific activities of the isotopes. The activity fractions are as follows: uranium-238 – 0.903; uranium-235 – 0.015; and uranium-234 – 0.083. As can be seen, the uranium-238/uranium-234 activity ratio is approximately 10.

Surface soil removal and confirmation sampling have been conducted at these four locations with uranium isotope concentrations above the ALs. A description of the soil removal and confirmation sample results are presented in Appendix C.

With respect to the PAHs, as shown on Figure 4-7, these compounds are ubiquitous in surface soil at the OLF. However, two sampling locations have PAH concentrations that exceed the ALs, and one of these locations shows an exceedance with a wide margin above the AL (benzo[a]-pyrene at SS10593). PAHs are largely confined to the surface (Section 4.4), likely due to PAH-contaminated runoff from paved areas in the IA that contacted the soil or from the dumping of street sweeping materials on the surface of the OLF, as discussed in Section 2.2.

4.4 Subsurface Soil

As detailed in Table 1 of Appendix B, subsurface soil samples (soil mixed with buried waste) were analyzed for metals, radionuclides, VOCs, SVOCs, pesticides, and PCBs. As shown in Table 4-2, metals, radionuclides, and organics have been detected above background levels in subsurface soil; however, only PAHs were detected above the ALs. PAHs were detected in subsurface soil in a relatively isolated location as shown on Figure 4-8. Unlike the widespread detection of PAHs in surface soil that probably indicates runoff from asphalt-paved areas in the IA as a potential source, the isolated occurrence of PAHs in subsurface soil appears to indicate the presence buried wastes and possibly asphalt and street sweepings.

4.5 Groundwater

As detailed in Table 2 of Appendix B, groundwater samples were analyzed for metals, radionuclides, VOCs, SVOCs, pesticides, PCBs, and water quality parameters (WQPs). Seventeen years of data exist for radionuclides, VOCs, and WQPs (1986 to 2003). There are metals data from 1991 to 2003, and SVOC and PCB/pesticide data mostly from 1991 to 1995. The SVOC and PCB/pesticide data collection was discontinued because these compounds were largely not detected. As shown in Table 4-3, metals, radionuclides, and organic compounds have been detected in groundwater at concentrations above background and the Tier II ALs. However, the number of detections above background and the Tier II ALs was generally very low for all of these constituents, and their concentrations were also generally very low relative to background and the Tier II ALs. This is further evaluated below.

4.5.1 Metals

Antimony, beryllium, cadmium, lead, manganese, nickel, selenium, and thallium were detected above the Tier II AL at least once in groundwater at the OLF (Table 4-3). Metal concentrations did not exceed the Tier I AL. The metal concentration distributions over time for those wells where there was one or more detections above the Tier II ALs are discussed below.

Antimony As shown on Figure 4-9, wells 5786, 59593, and P416689 had concentrations of antimony that were above the Tier II AL. However, concentrations were above background only

⁴ Dissolved concentration data are presented in Table 4-3 for metals and radionuclides because these data are representative of the mobile fraction of these constituents in groundwater. Total concentration data are presented for organics because these samples are not field filtered in accordance with standard operating procedures.



once for each well, and the most current data for each well indicate concentrations were below the Tier II AL.

<u>Beryllium</u> Figure 4-10 indicates well 7086 had concentrations of beryllium that were above the Tier II AL. There were two occurrences in the late 1980s and all subsequent measurements have been non-detects or at trace levels well below the Tier II AL.

<u>Cadmium</u> Figure 4-11 shows that wells 7086 and 10994 had concentrations of cadmium that were above the Tier II AL. There was one occurrence in each well in the early to mid-1990s and all subsequent measurements have been nondetects or at trace levels well below the Tier II AL.

<u>Lead</u> Figure 4-12 indicates well 5786 had a concentration of lead that was above the Tier II AL. There was one occurrence in 1990 and all subsequent measurements have been nondetects or at trace levels well below the Tier II AL.

Manganese As shown on Figure 4-13, four wells had manganese concentrations above the Tier II AL. With the exception of well 59493, each well had concentrations that were either inconsistently above the Tier II AL or within a factor of 2 of the Tier II AL. Manganese concentrations in groundwater at well 59493 had consistently exceeded over the Tier II AL, and the concentration was over 10 mg/L in 1993. However, subsequent measurements indicate the concentrations are within a factor of 2 of the Tier II AL (approximately 3 mg/L).

<u>Nickel</u> As shown on Figure 4-14, four wells had nickel concentrations above the Tier II AL. However, for two of these wells (5786 and P416689), the concentrations were inconsistently above the Tier II AL. For the other two wells (57994 and 58194), there was only one sample for each well, and the concentrations were within the range seen at well P416689, which is an upgradient well.

Selenium As shown on Figure 4-15, two wells had selenium concentrations above the Tier II AL. The concentration in well 59793, located within the OLF, was just above the Tier II AL (and background); this was the only sample for this well. The other location where the selenium concentration was above the Tier II AL is well 10994, an IMP Plume Extent monitoring well, located east of the OLF (Figure 4-3). As shown on Figure 4-15, dissolved selenium concentrations were relatively high, averaging approximately 0.6 mg/L. These concentrations are 10 times the Tier II AL and background. Well 10994 is sidegradient to the OLF. Therefore, the OLF does not appear to be the source for the selenium observed at this location.

Thallium As shown on Figure 4-16, eight wells had thallium concentrations above the Tier II AL. However, in every well, rarely did the concentrations exceed background (background is over 2 times higher than the Tier II AL), and every above-background concentration was within a factor of 2 of the background value.

4.5.2 Radionuclides

Americium-241, strontium-90, uranium-235, and uranium-238 were detected above background and the Tier II AL at least once in groundwater at the OLF (Table 4-3). Uranium-234, plutonium-239/240, radium-226, radium-228, cesium-137, and tritium were not detected above background and the Tier II AL. Because americium-241 was only detected above the Tier II AL

(and background) once in 26 samples, and at a relatively low activity (0.74 pCi/L), the occurrence of this radionuclide in groundwater at the OLF is not evaluated further⁵. The activity distributions over time for the other radionuclides in wells that had one or more detections above the Tier II ALs are discussed below:

<u>Strontium-90</u> As shown on Figure 4-17, five wells had strontium-90 activities above the Tier II AL. However, in all the wells, the concentrations were inconsistently above the Tier II AL, and the most recent samples had activities below the Tier II AL.

<u>Uranium</u> Uranium-235 exceeded background and the Tier II AL, and uranium-238 exceeded background and the Tier I AL in well 61093. Uranium isotope concentrations in all other wells were below background.

To further evaluate whether the uranium in groundwater is naturally occurring, the total uranium concentrations (sum of uranium-234, uranium-235, and uranium-238) and the U-238/U-234 activity ratios for well 61093 were plotted (Figure 4-18). As shown on Figure 4-18, a trend of increasing U-238/U-234 ratio with increasing concentration exists, which indicates the presence of depleted uranium. (Depleted uranium has a U-238/U-234 activity ratio of approximately 10, whereas natural uranium has an activity ratio of approximately 1.) On Figure 4-19, the total uranium concentrations and the U-235/U-238 mass ratios are plotted. (The U-235/U-238 mass ratios were calculated from alpha spectrometer data for the two uranium isotopes.) This figure indicates the U-235/U-238 mass ratio decreased significantly when the total uranium concentration increased significantly. This also suggests the presence of depleted uranium because natural uranium has a U-235/U-238 mass ratio of 0.0072, and ratios significantly less than this value indicate a lesser proportion of uranium-235 is present, that is, depleted uranium.

As part of a Sitewide study on the occurrence of uranium in groundwater, sample from wells 59393, 59793, and 61093 were collected and analyzed for uranium-234, uranium-235, uranium-236, and uranium-238 using Inductively Coupled Plasma/Mass Spectrometry (ICP/MS) (data not included in Table 4-3). This analytical method provides uranium isotope concentrations in parts per billion (ppb). Samples from these three wells were collected on June 22, 1999, December 7, 1999, February 8, 2000, and June 12, 2000. The average total uranium concentrations and the average uranium-235/uranium-238 mass ratios are plotted for these wells on Figure 4-20. The results indicate the average total uranium concentrations were low in wells 59393 and 59793 (< 100 ppb), and the average uranium-235/uranium-238 mass ratio was approximately 0.0072, indicating the presence of natural uranium. In contrast, in well 61093, the average total uranium concentration was much higher (approximately 600 ppb or 200 pCi/L),6 and the average uranium-235/uranium-238 ratio was much lower (0.0024), indicating depleted uranium is the source of the observed higher uranium concentrations. Also, uranium-236 was not detected in wells 59393 and 59793, but was detected in the groundwater samples from well 61093. The uranium-236 concentrations reported for the sample collection dates noted above were 0.015 ppb, 3.701 ppb, 0.027 ppb, and 0.017 ppb, respectively. Because uranium-236 is not a naturally

⁵ The single occurrence of americium-241 above the Tier II AL was in well 7086, a downgradient well. It occurred during the first sampling of the well in 1987; the four subsequent samples from the well indicated nondetectable americium-241 activities. ⁶ Dissolved concentration data were not collected in 1999 and 2000. Therefore, the results presented on Figure 4-20 (total concentrations in 1999 and 2000) cannot be compared to results presented in Figures 4-18 and 4-19 (dissolved concentrations in 1995).

occurring isotope of uranium, this further suggests the presence of depleted uranium at well 61093.

Considering the above results and the location of well 61093 within the bounds of the depleted uranium "hot spot" in surface soil, the "hot spot" appears to be the source of the depleted uranium contamination in groundwater. However, for perspective, it is noted that the dissolved uranium concentrations at well 61093 are at or near background concentrations (approximately 100 pCi/L of dissolved uranium).

4.5.3 Organics

Table 4-3 indicates that organic compounds, primarily chlorinated solvents, are occasionally detected in groundwater in or near the OLF, generally at very low concentrations (<10 μ g/L). Compounds with concentrations that have been above the Tier II AL include dieldrin, bis(2-ethylhexyl)phthalate, 1,1,2,2-tetrachloroethane, 1,1-dichloroethene, methylene chloride, tetrachloroethene (perchloroethene or PCE), and trichloroethene (TCE). The organic compound concentration distributions over time for those wells that had one or more concentrations above the Tier II AL are discussed below. [Note that the concentration distributions over time for 1,1,2,2-tetrachloroethane and 1,1-dichloroethene are not shown or discussed because only a single occurrence above the Tier II AL for each compound was detected, and the concentrations were less than 10 μ g/L. The concentration distribution over time for methylene chloride is also not shown because the seven concentrations above the Tier II AL are isolated occurrences in seven different wells. Methylene chloride is also a common laboratory contaminant.

<u>Dieldrin</u> Four occurrences of dieldrin, a pesticide, were reported at concentrations above the Tier II AL. As shown in Figure 4-21, all four occurrences were in well 10994, and they represent all the dieldrin data for this well. The data were collected in 1994 – 1995, and they appear to indicate a decreasing concentration trend. Regardless, the well is sidegradient (to the east) of the OLF (see Figure 4-3) and, therefore, the OLF is not the source of the apparent dieldrin contamination.

Bis(2-ethylhexyl)phthalate Bis(2-ethylhexyl)phthalate was detected above the Tier II AL in wells 58194, 59393, and 59493 (Figure 4-22). The three exceedances are not representative of the balance of the data at these wells, which indicate the compound is rarely detected or detected at a very low level below the Tier II AL. Furthermore, the qualifier code on the data for the three concentrations above the Tier II AL indicates the compound was detected in the laboratory blanks. It is concluded that the OLF is not a source for bis(2-ethylhexyl)phthalate in groundwater.

<u>Tetrachloroethene</u> As shown on Figure 4-23, seven wells contained PCE concentrations above the Tier II AL (see Figure 4-3 for well locations). In three of the wells (60893, 63193, and P416689), the PCE concentrations were near or below the Tier II AL over time. Because P416689 is an upgradient well (to the north, up the hillside [see Figure 4-3]), it appears the

 $^{^{7}}$ 1,1,2,2-Tetrachloroethane was detected in well 58094 at a concentration of 3 μ g/L in 1994. This compound was not detected in this well again, or in any other well at the OLF. The 1,1-dichloroethene concentration above the Tier II AL was for a sample collected from well 61093 in 1993 (31 μ g/L). Two subsequent samples from this well in 1995 contained 1,1-dichloroethene concentrations of 5 μ g/L and nondetected.

source of this low-level PCE contamination is the IA. The four other wells at the OLF with PCE concentrations above the Tier II AL had significantly higher levels of this VOC. Three of these wells are located within the OLF (58693, 59194, and 59794 [west-northwest of the OLF center]). There is one data point each for wells 58693 and 59794, and three data points for well 59194. Concentrations of PCE are in the 8 to 150 µg/L range. The fourth well with significantly higher PCE concentrations (62893) is located sidegradient of the OLF (to the east) and has an apparent steadily increasing concentration of PCE in the same concentration range noted above. Because of the sidegradient position of the well, it appears the source of the PCE contamination at this location is the IA. In summary, PCE contamination in groundwater at the OLF results from IA activities; there may be additional minor PCE contamination arising from the OLF.

Trichloroethene Similar to the occurrence of PCE in groundwater, eight wells contained TCE concentrations above the Tier II AL (Figure 4-24) (see Figure 4-3 for well locations). In five of the wells (20697, 59594, 62893, 63193, and P416689), TCE concentrations were near or below the Tier II AL over time. Because 62893 is a sidegradient well and P416689 is an upgradient well [see Figure 4-3]), it appears the source of this low-level TCE contamination is the IA. The three other wells (60993, 61093, and 59794) contained significantly higher concentrations of TCE. Although well 61093 had a maximum TCE concentration of 140 μ g/L, the concentrations continually dropped off in the subsequent three sampling events at this well, with only 2 μ g/L of TCE reported in the last sample collected from this well (June 2004). There is one datum for well 60993 (85 μ g/L) and well 59794 (20 μ g/L). In summary, TCE contamination in groundwater at the OLF arises from the IA, and there may be additional minor TCE contamination arising from the OLF.

4.5.4 Water Quality Parameters

Nitrate was the only WQP with concentrations above the Tier II AL. As shown on Figure 4-25, nitrate was detected above the Tier II AL once in well 7086. This occurrence of nitrate above the Tier II AL was back in the late 1980s, and all subsequent occurrences were near the detection limit or not detected. The data indicate the OLF is not a source for nitrate contamination of groundwater.

4.5.5 Groundwater Quality Summary

In summary, groundwater quality is not significantly impacted by the OLF. The OLF does not appear to be a source for metal contamination. Uranium concentrations are near background levels even though there appears to be depleted uranium contamination at well 61093, and there may be minor chlorinated solvent contamination arising from the OLF. Furthermore, as shown in Figure 4-25, chlorinated solvent contamination in groundwater does not extend downgradient of the OLF. The most recent VOC data for these wells (last 3 years) indicate chlorinated solvents are either not detected or detected at trace concentrations below 1 μ g/L, that is., a chlorinated solvent plume is not emanating from the OLF.

4.6 Surface Water

As detailed in Table 3 of Appendix B, surface water samples were analyzed for metals, radionuclides, VOCs, SVOCs, pesticides, and WQPs. Surface water quality data have been

evaluated through comparison to RFETS background levels and surface water ALs, and also through comparison to upgradient conditions. The latter analysis was performed to evaluate local changes in surface water quality in Woman Creek as it passes beside the OLF.

4.6.1 Upgradient Woman Creek Surface Water Quality

As shown in Table 4-4a, several metals, radionuclides, and organic compounds have been detected within Woman Creek with total concentrations above background levels in surface water upgradient of the OLF. The concentrations of some of these constituents were occasionally above the surface water ALs. The highest frequency of concentrations above the surface water ALs was for methylene chloride (approximately 20 percent), followed by lead (approximately 15 percent). The frequencies of concentrations above the surface water ALs were less than 5 percent for the remaining analytes. Methylene chloride is a common laboratory contaminant, and was present in the associated laboratory blank for most of the reported methylene chloride detections. The surface water AL and background value for lead are virtually the same, explaining the occasional concentrations that were above the surface water AL.

As expected, there were fewer dissolved metals and radionuclides with concentrations that exceeded the surface water ALs (Table 4-4b). The frequencies of concentrations above the surface water ALs were less than approximately 5 percent for these analytes.

In summary, there are no significant impacts to Woman Creek water quality upgradient of the OLF.

4.6.2 Downgradient Woman Creek Surface Water Quality

As shown in Tables 4-5a and 4-5b, similar to upgradient Woman Creek water quality, several metals, radionuclides, and organic compounds have been detected above background levels within Woman Creek surface water downgradient of the OLF. The concentrations of many of these analytes were occasionally above the surface water ALs (approximately 5 percent or fewer of the observations), and were generally low in magnitude relative to the surface water ALs. Comparing Tables 4-4a and 4-5a, several metals and organics that were detected above background in surface water downgradient of the OLF have not been detected above background in upgradient surface water. However, these analyte concentrations typically were low relative to the surface water ALs, with only infrequent concentrations above the surface water ALs. If these additional detections can be attributed to the OLF, fewer than 7 percent of any analyte sampled exceeded the AL. This frequency of occurrence is not sufficient to indicate the OLF has a significant chronic impact on surface water quality.

Even though TCE and PCE are present in groundwater at the OLF, the following observations regarding these compounds in Woman Creek surface water are noted to underscore the lack of a chronic impact, if any, from the OLF on Woman Creek water quality:

• PCE (2 μg/L) and TCE (3 μg/L) were detected at SW033 on April 11, 1990. These compounds were not detected at this station in 10 previous and 19 subsequent sampling events.

• TCE (26 μg/L) was detected at SW032 on November 11, 1987. TCE was not detected at this station in 3 previous and 28 subsequent sampling events.

4.6.3 South Interceptor Ditch Surface Water Quality

As shown in Tables 4-6a and 4-6b, similar to upgradient and downgradient surface water quality in Woman Creek, several metals, radionuclides, and organic compounds have been detected above background levels in the South Interceptor Ditch (SID) surface water. Generally, the concentrations of many of these analytes have been occasionally above the surface water ALs (approximately 5 percent or less of the time), and are low in magnitude relative to the surface water ALs. However, a notable difference between SID surface water quality and Woman Creek surface water quality is evident in the occurrence of barium and the uranium isotopes.

Of the metals, barium has the highest frequency of exceeding background in SID surface water at well over 50 percent of all observations. However, the barium concentrations exceed the surface water AL in only one observation. Table 4-3 indicates barium concentrations are also frequently above background in groundwater. Groundwater infiltration to the SID may be a plausible explanation for the above-background barium concentrations in SID surface water. Barium concentrations in OLF groundwater rarely exceed the Tier II groundwater AL.

Unlike Woman Creek surface water, a relatively high frequency of above-background concentrations for the uranium isotopes (total and dissolved concentrations [Table 4-6a and 4-6b]) exists in the SID, which occur at SW036 only (see Figure 4-4 for station location). The other stations on the SID have low concentrations of uranium (< 5 pCi). Uranium-238, particularly the total concentration (see Table 4-6a), also has frequently exceeded the surface water AL. (The surface water AL is for the sum of the isotopes.) As shown on Figure 4-27, uranium concentrations (sum of the isotopes) at SW036 are typically 30 to 40 pCi/L (total, as opposed to dissolved concentrations), and are rarely below the drainage-specific surface water AL of 11 pCi/l. Also shown on Figure 4-27 are the U-238/U-234 ratios, which are typically about 3. As discussed in Section 4.5 for groundwater, this elevated ratio indicates a depleted uranium component in surface water at this station. As discussed previously, depleted uranium contamination exists in surface soil and in groundwater at well 61093. The depleted uranium contamination at SW036 probably arises from both contaminated runoff and discharge of groundwater to the SID (interflow).

Data presented by K-H (2004) provides perspective on the uranium contamination at SW036. The median concentration of total uranium at SW036 is 30.43 pCi/L. At station SW027, located downstream of SW036 on the SID and upstream of Pond C-2, the median concentration of total uranium is 1.62 pCi/L. At the discharge of Pond C-2, Point of Compliance (POC) GS31, the median concentration is 2.28 pCi/L. These data indicate significant attenuation of the total uranium concentration through settling of particulate uranium and/or by dilution from downstream runoff or groundwater discharge to the SID. The volume of water discharged at SW036 is less than 1 percent of the volume discharged in Woman Creek at Indiana Street. Thus, the uranium load contributed to the Woman Creek watershed by the SW036 watershed is relatively small. The median concentration of total uranium at station GS01 (POC for Woman Creek at Indiana Street) is 2.5 pCi/L, well below the surface water AL of 11 pCi/L.

As a final note, even though TCE is present in groundwater at the OLF, the following observation regarding this compound in SID surface water is provided to underscore the lack of a chronic impact:

• TCE (8 μg/L) was detected at SW036 on April 8, 1991. This compound was not detected at this station in 15 previous (except for 1 μg/L on August 8, 1990) and 7 subsequent sampling events.

4.7 Sediment

As detailed in Table 4 of Appendix B, sediments samples were analyzed for metals, radionuclides, VOCs, SVOCs, pesticides, and PCBs. As shown in Table 4-7, only a few metals were detected above background in the sediment of Woman Creek and the South Interceptor Ditch in the vicinity of the OLF. Concentrations were orders of magnitude below the RFCA ALs.

4.8 Contamination Summary and Action Determinations

Contamination of environmental media at the OLF can be summarized as follows:

- Depleted uranium "hot spots" (concentrations above wildlife refuge worker (WRW) ALs) were present in surface soil. The presence of the uranium contamination in surface soil is consistent with the instances of placing depleted uranium on the surface of the OLF. Surface soil removal and confirmation sampling have been conducted at the four uranium isotope "hot spots." A description of the soil removal and confirmation sample results are presented in Appendix C.
- PAH concentrations in surface soil are widespread, some of which exceed the WRW AL.
 PAH concentrations in subsurface soil are more isolated, some of which also exceed the WRW AL. It appears the source of the contamination is PAH-contaminated runoff from asphalt within the IA, and/or the burial of asphalt and street sweepings in the OLF.
- Groundwater is contaminated with uranium (at one location) and with low concentrations of TCE and PCE (more widespread arising from an upgradient source). There is no definitive contamination of groundwater by metals or other radionuclides and organics. That is, the number of detections above background and the Tier II ALs were very low for these constituents, and their concentrations were also very low relative to background and the Tier II ALs. Well 61093 is the only location where groundwater is contaminated with uranium. It appears the contamination arises from depleted uranium at the surface of the OLF. Surface water in the SID is impacted by this source of contamination from groundwater discharge and/or runoff. Low-level TCE and PCE contamination exists in groundwater at the OLF that appears to emanate from the IA. The OLF may be contributing additional, albeit minor, TCE and PCE contamination to groundwater; however, the groundwater and surface water data indicate this contamination is not migrating downgradient of the OLF and is not contaminating surface water. Therefore, the OLF is not a significant source for groundwater contamination.

• Surface water in the SID at SW036 is contaminated with uranium. Otherwise, SID (and Woman Creek) surface water immediately downgradient of the OLF has very low frequencies of analyte concentrations above the surface water ALs, which indicates the OLF does not have a significant chronic impact on these streams. It appears the depleted uranium contamination in the SID arises from the depleted uranium contamination at the surface of the OLF or from the discharge of depleted uranium-contaminated groundwater. However, uranium concentrations quickly attenuate downstream, and the uranium concentrations at the downgradient Woman Creek POCs (GS31 and GS01) are well below the surface water AL.

Given the above observations, the following action determinations have been made for the OLF:

- An action determination in accordance with ALF, Section 5.3 has been made for surface soil with uranium concentrations above the WRW ALs. These "hot spots" have been removed as approved by the CDPHE. Appendix C presents the description of the soil removal and confirmation sampling results.
- An action determination in accordance with ALF, Section 4.2 has been made for the PAH-contaminated surface and subsurface soil. The proposed accelerated action of source containment (soil cover) will be conducted in accordance with this IM/IRA (see Section 7.0).
- An action determination in accordance with ALF, Section 3.3 has been made for the uranium and chlorinated solvent groundwater contamination. The uranium-contaminated groundwater may be contributing to surface water AL exceedances at SW036 on the SID; however, it has not caused surface water ALs to be exceeded at the downgradient POCs on Woman Creek despite uncontrolled groundwater discharge from the OLF after the waste disposal operations ceased. There is no indication that PCE and TCE in groundwater at the OLF are migrating downgradient and contaminating surface water. In addition, groundwater fate and transport modeling indicates constituents in the groundwater will not reach Woman Creek above detectable levels. Monitoring (as a part of the accelerated actions) in accordance with the IMP, will evaluate contaminant concentration changes or trends.

4.9 Risk Assessment

As part of the OU 5 Phase I RFI/RI, a baseline human health risk assessment was conducted for Area of Concern 1, which is identical to the OLF area (Kaiser-Hill 1996). Although risk and health effect calculations were made for several receptors and exposure pathways, those most relevant to the future anticipated land used for RFETS are the open space user and the ecological researcher. The total estimated risk for the open space user was calculated as 6E-6 and for the ecological researcher as 1E-6.

An ecological risk assessment was conducted for several RFETS areas, including the Woman Creek Watershed, which is also contained in the OU 5 Phase I RFI/RI Report (Kaiser-Hill 1996). The methodology was developed to support risk management decisions for individual Operable Units. The approach used for the assessment is consistent with a screening-level risk assessment appropriate for sites where ecological effects have not been observed, but contaminant levels

have been measured and can be compared with concentrations considered protective of ecological receptors.

Relevant to the OLF source area, the evaluated receptor groups and related ecological contaminants of concern (ECOCs) are as follows:

- Aquatic Life Metals and organics in sediment;
- Aquatic feeding birds Mercury in fish tissue and antimony in sediment;
- Small mammals- Uranium 233/234 and 238 in soils; and
- Vegetation Metals in soils and sediments.

In summary, the assessment concluded:

- PAHs were the primary risk to aquatic life; however, no toxicity was detected in sediment toxicity tests using a *Hyalella azteca*.
- Risks from mercury to aquatic feeding birds were significant only if the birds obtained all their food from Pond C-1.
- Risks from antimony to aquatic feeding birds assumed 100 percent site use; however, the streams support a small fish population and risks were not significant if adjusted for realistic site use factors.
- Radionuclides do not present a significant risk to terrestrial receptors.
- The risk to vegetation communities is minimal because of the small source areas and the vegetation growth in contaminated sediment in littoral zones appears normal.

Based on the risk assessment information, baseline risks appear to be well within CERCLA threshold criteria. The presumptive remedy of source containment is expected to maintain or lower the baseline risks.

However, ecological impacts at the OLF will be evaluated by the Accelerated Action Ecological Screening Evaluation (AAESE). The AAESE will be applied to the Upper Woman Drainage Exposure Unit (EU) (DOE 2004, DOE 204a), which includes the OLF, to determine whether an additional accelerated action is required for the EU because of risk to ecological receptors. Because of the large size of the EU relative to the OLF, it is not anticipated the AAESE would indicate adverse ecological effects to the entire EU arising solely from the OLF. Therefore, an impact to the remedy selection for the OLF is also not anticipated.

The OLF will be evaluated as part of the Sitewide Comprehensive Risk Assessment, which is part of the RFI/RI and Corrective Measures Study/Feasibility Study (CMS/FS) that will be conducted for the Site. The need for and extent of long-term stewardship activities will be reanalyzed in the RFI/RI and CMS/FS and will be proposed, as appropriate, as part of the preferred alternative in the Proposed Plan for the Site. Institutional controls and other long-term

stewardship requirements for Rocky Flats will ultimately be contained in the Corrective Action Decision/Record of Decision (CAD/ROD) and in any post-RFCA agreement.

Table 4-1 Surface Soil Data Summary

	ACCRECATION AND A CONTRACT OF	Carrier Const.	Many Vancor and Land	200 X 1 20 X 20 X 30	No. and Company	Maximum	BG∑	Wildlife	Unit
Analyte Group	Analyte	Total Number	Number of	Number of	Average Conc.	Conc.	Mean	Refuge	O.III.
3.0		Samples'	Samples	Samples			Plus 2SD	Worker AL	
		Analyzed	above BG but below	above the			230	ζĽ	
			the AL						1.5
Metal	Aluminum	51	2	0	19450 -	20000	16902	228000	mg/kg
Metal	Antimony	44	2	0	44.8	49.8	0.47	409	mg/kg
Metal	Barium	51	6	0	160	177	141	26400	mg/kg
Metal	Beryllium	51	15	. 0	1.18	1.7	0.966	921	mg/kg
Metal	Cadmium	45	2	0	3.25	4.1	1.61	962	mg/kg
Metal	Chromium	51	5	0	19.7	24.2	17.0	268	mg/kg
Metal	Cobalt	51	3	0	12.4	13.6	10.9	1550	mg/kg
Metal	Copper	51	20	. 0	57.8	184	18.1	40900	mg/kg
Metal	Iron	51	3	0	19667	20600	18037	307000	mg/kg
Metal	Lead	51	1 .	0	129 -	129	54.6	1000	mg/kg
Metal	Lithium	51	3	0	13.8	15.3	11.6	20400	mg/kg
Metal	Manganese	51	5	0	513	829	365	3480	mg/kg
Metal	Mercury	51	12	0	0.253	0.38	0.134	25200	mg/kg
Metal	Nickel	50	20	0	17.6	26.3	14.9	20400	mg/kg
Metal	Strontium	51	3	0	54.8	62.4	48.9	613000	mg/kg
Metal	Tin	51	2	0	18.9	30.9	2.9	613000	mg/kg
Metal	Zinc	51	10	0	119	199	73.8	307000	mg/kg_
PCB	Aroclor-1254	51	12	0.	1481	3900	-	12400	ug/kg
Pesticide	4,4'-DDT	51	1	0	21	21	_	100000	ug/kg
Pesticide	Dieldrin	51	1	0	34	34	-	1720	ug/kg
Pesticide	Endosulfan sulfate	51	1	0	24	24	-	4420000	ug/kg
Radionuclide	Americium-241	57	9	0	0.0447	0.0865	0.0227	76	pCi/g
Radionuclide	Plutonium-239/240	58	. 11	0	0.144	0.338	0.066	50	pCi/g
Radionuclide	Uranium-234	59	k Higgs		293	₹ 2800 ₺	2.25	300	pCi/g
Radionuclide	Uranium-235	59	9	4	84.5	670	0.0939	8 4 4	> pCi/g
Radionuclide	Uranium-238	59	16	4	2620	38000	* 2	⅓ 351 ∻ ⊴	pCi/g
svoc	2-Methylnaphthalene	48	2	0	6395	12000	-	20400000	ug/kg
SVOC	Acenaphthene	49	2	0	23300	44000 ·		40800000	ug/kg
svoc	Anthracene	49	3	0	16903_	47000	-	204000000	ug/kg
svoc	Benzo(a)anthracene	48	8	rody, Anny	7215	45000	-	34900	ug/kg
svoc	Benzo(a)pyrene	49	8	2	6765	43000	2	3490	ug/kg
svoc	Benzo(b)fluoranthene	49	10	1	6677	49000		34900	ug/kg
svoc	Benzo(k)fluoranthene	49	7	0	4008	25000		349000	ug/kg
svoc	Chrysene	48	8	0	7461	46000	-	3490000	ug/kg
SVOC	Dibenz(a,h)anthracene	36	2	1, 1	5150	9200	-	3490	ug/kg
svoc	Dibenzofuran	49	2	0	10650	20000	•	2950000	ug/kg

Group		Samples Analyzed	Samples above BG but below the AL	Of Samples above the AL	Conc.	Conc.	Mean Plus 2SD	Refuge Worker AL	
SVOC F	Fluoranthene	49	14	0	12551	140000	-	27200000	ug/kg
SVOC F	Fluorene	49	2	0	20650	39000	-	40800000	ug/kg
	Indeno(1,2,3- cd)pyrene	38	3	. 0	12067	32000	-	34900	ug/kg
SVOC F	Pyrene	49	14	0	10767	120000	-	22100000	ug/kg
VOC N	Naphthalene	49	2	0	22000	41000	•	3090000	ug/kg

Above the Wildlife Refuge Worker Action Level

Note: Analytes shown are those that were detected at least once above background levels and have a Wildlife Refuge Worker Action Level.

The maximum concentration is the maximum detected value, and the average concentration is the average of the data that exceed background.

BG – Background AL - Action Level

Table 4-2 Subsurface Soil Data Summary

		Subsuii	ace Soll I	Jata Sun					₩ ₩ W 18V
Analyte Group	Analyte	Total	Number	Number of	Average Conc.	Maximum Conc.	BG Mean	Wildlife Refuge	Unit »
		Number Samples	Samples	Samples	g- Conc.	E COIIC.	Plus	Worker	
્રાસ્ત્રી છે. ્રેક્ટ્સ્ટ્રેક્ટ્રેક્ટ્રેક્ટ્સ્ટ્રેક્ટ્રેક્ટ્રેક્ટ્રેક્ટ્રેક્ટ્રેક્ટ્રેક્ટ્રેક્ટ્રેક્ટ્રેક્ટ્સ્ટ્રેક્ટ્રેક્ટ્સ્ટ્રેક્ટ્સ્ટ્રેક્ટ્સ્ટ્રેક્ટ્સ્ટ્રેક્ટ્રેક્ટ્રેક્ટ્સ્ટ્રે	The Rolling St. Backson	Analyzed	above BG	above the			2SD	AL	
			but below the AL	AL					
The state of the	4. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.	Arran Y	3 . sk	1	14				
Metal	Antimony	51	11	0	19.5	19.5	16.97	409	mg/kg
Metal	Arsenic	62	1	0	18.9	18.9	13.14	22.2	mg/kg
Metal	Barium	62	1	0	387	387	289.38	26400	mg/kg
Metal	Cadmium	61	1	0	2.3	2.3	. 1.7	962	mg/kg
Metal	Chromium	62	3	0	118	165	68.27	268	mg/kg
Metal	Copper	62	11	0	779	6920	38.21	40900	mg/kg
Metal	Iron	62	2	0	64200_	78900	41047	307000	mg/kg
Metal	Lead	62	12	0	105	304	24.97	1000	mg/kg
Metal	Manganese	62	3	0	1273	1540	902	3480	mg/kg
Metal	Molybdenum	60	1	0	190	190	25.61	5110	mg/kg
Metal	Nickel	62	6	0	93.6	118	62.21	20400	mg/kg
Metal	Silver	60	1	0	36	36	24.54	5110	mg/kg
Metal	Zinc	62	10	0	342	673	139.1	307000	mg/kg
PCB	Aroclor-1254	53	7	0	694	960		12400	ug/kg
PCB	Aroclor-1260	54	3	0	887	1300		12400	ug/kg
Radionuclide	Americium-241	60	7	0	0.117	0.46	0.02	76	pCi/g
Radionuclide	Plutonium-239/240	62	18	0	0.340	3.2	0.02	50	pCi/g
Radionuclide	Uranium-234	62	4	0	13.0	30	2.64	300	pCi/g
Radionuclide	Uranium-235	62	6 _	0	0.606	2.3	0.12	8	pCi/g
Radionuclide	Uranium-238	62	20	, 0	2.69	12	1.49	351	pCi/g
svoc	2-Methylnaphthalene	54	1	0	15000	15000		20400000	ug/kg
svoc	Acenaphthene	54	5	0	6936	31000		40800000	ug/kg
svoc	Anthracene	54	9	0	6143	46000		204000000	ug/kg
svoc	Benzo(a)anthracene	54	. "9	1	6918	48000		34900	ug/kg
svoc	Benzo(a)pyrene	- 54	9	. ↓2	6243	43000	1 4	3490	ug/kg
SVOC	Benzo(b)fluoranthene	54	10	1	6431	48000	i i	34900	ug/kg
svoc	Benzo(k)fluoranthene	54	10	0	2545	19000		349000	ug/kg
SVOC	Butylbenzylphthalate	54	2	0	1400	1400		147000000	ug/kg
svoc	Chrysene	54	9	0	7412	53000		3490000	ug/kg
SVOC	Dibenz(a,h)anthracene	54	1	0	700	700		3490	ug/kg
svoc	Dibenzofuran	. 54	1	0	20000	20000		2950000	ug/kg
svoc	Fluoranthene	54	13	0	15145	160000		27200000	ug/kg
SVOC	Fluorene	54	5	0	7802	35000		40800000	ug/kg
svoc	Indeno(1,2,3- cd)pyrene	54	9	0	3369	22000		34900	ug/kg
svoc	Pyrene	54	12	0	14952	150000		22100000	ug/kg_
voc	Acetone	126	2	0	265	280		102000000	ug/kg
voc	Chloroform	128	1	0	19	19		19200	ug/kg
voc	Ethylbenzene	128	1	0	66	66		4250000	ug/kg
VOC	Methylene chloride	128	2	0	82	150		2530000	ug/kg


Analyte Group	Analyte	Samples Analyzed	Number of Samples above BG but below the AL	Number of Samples above the AL	Average Conc.	Maximum Conc.	BG Mean Plus 2SD	Wildlife Refuge Worker AL	Unit Towns
VOC	Naphthalene	54	5	0	12914	61000		3090000	ug/kg
VOC	Tetrachloroethene	128	14	0	256	900		615000	ug/kg
VOC	Toluene	126	37	0	40	220		31300000	ug/kg
VOC	Trichloroethene	128	10	0	97.8	390		19600	ug/kg
voc	Xylene	128	1	0	150	150		2040000	ug/kg

Above the Wildlife Refuge Worker Action Level

Note: Analytes shown are those that were detected at least once above background levels and have a Wildlife Refuge Worker Action Level. The maximum concentration is the maximum detected value, and the average concentration is the average of the data that exceed background.

BG - Background


AL - Action Level



Analyte	Analyte	Total	Number	Number	Number	Average	Maximum	BG	Tier II	Tier I AL	Unit
Group		Number Samples	of - Samples	of Samples	of Samples	Conc.	Conc.	Mean Plus	AL		
		Analyzed	above BG	above	above 💸			2SD			
			but below the Tier II	Tier II AL but below	Tier I AL						
			AL¹	the Tier I							
Metal	Aluminum	201	9	0 -	0	2.21	4.9	0.234	36.5	3650	mg/L
Metal	Antimony*	200	6	3	0	0.0631	0.0719	0.03954	** 0.006	0.6	mg/L »
Metal	Arsenic	202	12	0	0	0.0101	0.0197	0.00531	0.05	- 5	mg/L
Metal	Barium	210	67	0	0	0.241	0.647	0.153	2	200	mg/L
Metal	Beryllium	202	0	2	0	0.00615	0.007	0.00267	0.004	0.4	mg/L
Metal	Cadmium	ం∞203 ^{్ర} ా	2. 1 0.65	2	0	0.0054	0.0064	0.00425	0.005	0.5	mg/L
Metal	Chromium	209	1	0	. 0	0.018	0.018	0.0124	0.1	10	mg/L
Metal	Copper	201	15	0	0	0.0198	0.0317	0.0139	1.3	130	mg/L
Metal	Lead	203	(VI)	16.8	0	0.0505	0.087	0.0110	0.015	1.5	mg/L
Metal	Lithium	197	2	0	0	0.157	0.166	0.143	0.73	73	mg/L
Metal	Manganese	204	63	15	. 0	1.02	10.5	0.162	1.72	172	mg/L
Metal	Mercury	196	. 4	0	0	0.00044	0.0006_	0.00025	0.002	0.2	mg/L
Metal	Nickel	210	24	13	0	0.152	0.654	0.0214	0.14	14 5 😤	∞mg/L
Metal	Selenium	208 😹	0 3	24	× 0 :===	- 0.521	1.02	0.0437	0.05	5	mg/L
Metal	Silver	202	5	0	0	0.01076	0.0122	0.00708	0.183	18.3	mg/L
Metal	Strontium	201	19	0	0	1.28	1,97	0.931	21.9	2190	mg/L
Metal	Thallium	199	9	12	2 C 0 3 F	0.00645	0.0083	₹0.0049	0.002	0.2	mg/L
Metal	Zinc	202	5	0	0	0.294	1.03	0.0498	11	1100	mg/L
Pesticide	Dieldrin	29		4	0	0.183	0.24	11:5:12	0.00532	0.532	μg/L
Radionuclide	*Americium-241	26	0	1	. 0	0.74	0.74	× 0.03	0.145	14.5	pCi/L
Radionuclide	Plutonium-239/240	27	2	0	0	0.022	0.033	0.01	0.151	15.1	pCi/L
Radionuclide	Radium-226	50	13	0	0	0.74	1.2	0.48	20	2000	pCi/L
Radionuclide	Strontium-90*	111	8	. 8	0	1.64	3.4	0.96	0.852	85.2	pCi/L

Draft Interim Measure/Interim Remedial Action for the Original Landfill (Including IHSS Group SW-2; IHSS 115, Original Landfill and IHSS 196, Filter Backwash Pond)

Unit	pCi/L	pCi/L	μg/L	µg/L	µg/L	µg/L	μg/L	μg/L	µg/L	μg/L	µg/L	µg/L	μg/L	µg/L	μg/L	µg/L	µg/L	, µg/L	ηg/L	µg/L	ug/L	µg/L	µg/L	μg/L
Tier PAL	101	76.8	73000	183000.	18300	219000	1100000	. 600	730000	365000	73000	14600	2920000	146000	146000	110000	20000	42.6	500	365000	₹ 700€	7000	7000	7500
AL :	1.01	.892.0	730	1830	183	2190	11000	9	7300	3650	730	146	29200	1460	1460	100	200	0.426	5	3650		70	70	75
BG Mean Plus 2SD	1.48	40.2	•	•	•	•	•		•	•		•	•	•	•	•	•		•					•
Maximum Com.	1.547	80.83	2	-	10		0.5	150	3	2	9	3	14	4	4	£,	37	. 3	2	3	31	0.7	4.	0.4
Average. Conc.	1.55	80.83	2	-	6.5	3.1	0.5	.12.65	1.83	2.00	2.48	1.82	6.40	1.89	2.38	1.60	2.76	3.00	2.00	0.95	191	0.70	2.88	0.40
Number of Samples above Tier I'AL	. 0	5, to 15, 25	0	0	0	0	0		0	0	0	0	0	0	0	0	0	.0	0	0		0.	0	0
Number of Samples above Tief II AL but below the Tier II AL	1	0	0	0	0	0	0	4	0	0	0	0	.0	0	0,	0	0	1	0	0		0	. 0	0
Number of Samples above BG but below the Tier III	4	129	1	1	2	10	. 1	33	9	-	13	22	. 5	6	8	•	22	0	. 1	6	52	1	8	1
Total Number Samples Analyzed	188	188	80	80	80	81	81		80	08	81	80	80	81	81	81	300	296	300	596	300	261	118.	261
Analyie	Uranium-235*	Uranium-238*	2,4-Dimethylphenol	2-Methylphenol	4-Methylphenol	Acenaphthene	Anthracene	bis(2- Ethylhexyl)phthalate	Butylbenzylphthalate	Di-n-butylphthalate	Di-n-octylphthalate	Dibenzofuran	Diethylphthalate	Fluoranthene	Fluorene	Pyrene	1,1,1-Trichloroethane	1,1,2,2. Tetrachloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	I,1-Dichloroethene	1,2,4- Trichlorobenzene	1,2-Dichloroethene (total)	1,4-Dichlorobenzene
Analyte Group,	Radionuclide	12	SVOC	svoc	SVOC	SVOC	svoc	SVOC	svoc	svoc	svoc	SVOC	SVOC	SVOC	svoc	SVOC	voc	voc	voc	voc	voc	voc	voc	voc



Note: Analytes shown are those that were detected at least once above background levels and have a Groundwater Action Level. The maximum concentration is the maximum detected value, and the average concentration is the average of the data that exceed background. Metals and radionuclides are dissolved concentrations. Organics are total concentrations.

^{*}Background exceeds the AL.

BG - Background

AL - Action Level

¹ This column includes the number of samples exceeding the Tier II AL but less than BG when the BG value for an analyte exceeds the Tier II AL.

Table 4-4a
Upgradient Woman Creek Surface Water Data Summary (Total Concentrations)

Analyte Group	Analyte	Number Samples Analyzed	Number of Samples above BG but below the AL	Number of Samples above AL	Average Conc.	Mäximum Conc.	BG Mean Plus 2SD	Surface Water AL	Unit
Metal	Aluminum*	51	23	3	5.08	5.52	3.45	0.087	mg/L
Metal	Barium	52	2	0	0.136	0.136	0.12688	0.49	mg/L
Metal	Beryllium	46	0	1	0.0084	0.0084	0.00234	0.004	mg/L
Metal	Lead*	52	0	8	0.01	0.016	0.00658	0.0065	mg/L
Metal	Mercury*	49	4	1	0.0011	0.0011	0.00041	0.00001	mg/L
Metal	Nickel	49	1	0	0.0359	0.0359	0.01987	0.123	mg/L
Metal	Silver*	£ 52	- 6	Sep 1, 1, 2, 5, 5, 5	0.0079	0.0079	0.00591	0.0006	mg/L
Radionuclide	Americium-241	o 43	5	2	0.0809	0.162	0.02	0.15	pCi/L
Radionuclide	Plutonium-239/240	43	4	0	. 0.0653	0.146	0.02	0.15	pCi/L
Radionuclide	Tritium	44	0	2	1580	2170 ·	494	500	pCi/L
Radionuclide	Uranium-234**	35	1	1	6.61	11.5	1.59	10	pCi/L
Radionuclide	Uranium-235**	34	3	0	0.35	0.43	0.19	10	pCi/L
Radionuclide	Uranium-238**	35	4	0	2.07	2.81	1.22	10	pCi/L
svoc	Diethylphthalate	12	1	0	2	2	-	5600	μg/L
VOC	1,2-Dichloroethane	50	0	1	117	11.	-	0.38	μg/L
VOC	2-Butanone	44	1	0	12	12	·-	21900	μg/L
VOC	4-Methyl-2- pentanone	46	1	0	31	31		2920	μg/L
VOC	Acetone	47	16	0	9.75	23	-	3650	μg/L
VOC	Carbon Disulfide	46	1	0	6	6	-	3650	μg/L
VOC	Carbon Tetrachloride	50	0	1	6	6		0.25	μg/L
VOC	Chloroform	50	. 1	0	3	3	-	5.7	μg/L
VOC	Methylene chloride	49	12	9	6.95	29		4.7	μg/L
VOC	Tetrachloroethene	50	0	1	10	10	•	0.8	μg/L
VOC	Toluene	48	2	0	10.5	12	•	1000	μg/L
VOC	Trichloroethene	50	0	1	8	8		2.7	μg/L

Note: Data are for surface water stations SW039, SW040, SW041, and SW506. Analytes shown are those that were detected at least once above background levels and have a Surface Water Action Level. The maximum concentration is the maximum detected value, and the average concentration is the average of the data that exceed background.

^{*}Background exceeds the AL.

^{**} The uranium surface water AL is for total uranium (sum of the isotopes).

BG - Background

AL - Action Level

This column includes the number of samples exceeding the AL but less than BG when the BG value for an analyte exceeds the AL

Table 4-4b Upgradient Woman Creek Surface Water Data Summary (Dissolved Concentrations)

			(100011)			,			
Analyte Group	Analyte	Total Number Samples Analyzed	Number of Samples above BG but below the AL!	Number of Samples above the AL	Average Conc.	Maximum Conc	BG Mean Plus 2SD	Surface Water AL	Unit
Metal	Aluminum*	49	2	2	1.57	2.5 	0.421	0.087	mg/L
Metal	Copper	56	1.	\$ 12 de	0.022	0.028	0.0158	0.016	mg/L
Metal	Lead	₹52 🐇	0	3.	0.0073	0.008	0.00459	0.0065	mg/L
Metal	Mercury*	51	0	· · · · · 2	0.000385	0.00044	0.00026	0.00001	mg/L
Metal	Zinc	54	4	0	0.0693	0.0757	0.0499	0.141	mg/L
Radionuclide	Uranium-234**	21	1	0	2.28	2.28	1.08	10	pCi/L
Radionuclide	Uranium-238**	21	1	0	1.44	1.44	0.82	10	_pCi/L

Above the Surface Water Action Level

Note: Data are for surface water stations SW039, SW040, SW041, and SW506. Analytes shown are those that were detected at least once above background levels and have a Surface Water Action Level. The maximum concentration is the maximum detected value, and the average concentration is the average of the data that exceed background.

*Background exceeds the AL.

BG - Background

AL - Action Level

^{**} The uranium surface water AL is for total uranium (sum of the isotopes).

This column includes the number of samples exceeding the AL but less than BG when the BG value for an analyte exceeds the AL

Table 4-5a Downgradient Woman Creek Surface Water Data Summary (Total Concentrations)

ote: Data are	for surface water stations S/	NU33 CMU33	SOCULMS	E0102W2	6705MS P	ls satvienA 8	nown are the	ose that were	
	Above the Surface Water	lava I noitaA							
30 .	Xylene	LL	7	0	7	3	-	10000	J/84
, OC	SinstheoroldoirT	.89	0	7	S'#[*	397		% L'7	7/8n
30 .	Toluene	99	7	0	L	15	-	1000	<u></u>
" 20	Tetrachloroethene	89	*0*	ा	7 **	7	1. 188 <u>4</u> 10.	8.0	7/8n
) 00.	Styrene	99	1	0	Ī	Ī	-	100	
) 00	Methylene chloride	99	01	9	8L'S	70	786 - 18 200 - 18	Salt 1	J/84
)	Ethylbenzene	99	I	0	I	I	6.56K.55+ 16	002	∕7/ ∄ ਜ
.:: J. 30	Carbon Tetrachloride	<i>L</i> 9	0	I was	9300	9	44 8.3 355.2	\$Z.0	7/8tl
)	Carbon Disulfide	1 -9	I	0	<u> </u>	l	0.068208(*0.50 -	3920	_7/8µ
20.	Acetone	9\$	L	0	1.21	LS	-	3650	7/ 3 11
) 00	1,2-Dichloropropane	99	0	l.	E	€	•	25.0	J\94
0C:	. 1,2-Dichloroethane	89	0	7	S:8	†I	-	86.0	7/ 3 1
20	l,1-Dichloroethene	89	I	0	ς	S	-	L	<u>√34</u>
)	1,1-Dichloroethane	99	ī —	0	ε	ε	· ·	3650	
VOC	n-Nitrosodiphenylamine	.61	7	0	ε	ç	-	S	
adionuclide	Vranium-238**	43	7	. 0	18.1	90.2	1.22	01	PCi/L
adionuclide	**č£S-muinsrU	017	ε	0	LVV 0	₽ 7.0	61.0	10	PCi/L
adionuclide	**b£S-muinsıU	£þ	ε	0	21.41	5.9	65.1	01	DCi/L
adionuclide	Plutonium-239/240	19	8	7	£01.0	97.0	20.0	S SIO	DCi/L
adionnoiba	Americium-241	6 \$	S	t t	0:115	86.0	20.0	\$1:0	PCiAL
. esticide	Loxaphene	61	0	1	I	1.		2000.0	
(ctal	Zinc•	£9	I sa	I	\$15.0°	715.0	* SS1.0	*I†I'0	J\gm "
ctal	Silver	19	S	1	20.0	70.0	16500.0	9000 0	J\gm
etal	Selenium	6 S	0	S	8110.0	20.0	\$9\$00.0	91/00:0	J/gm
ctal	Lead*	6 S	0	(A) (A) (A) (A) (A) (A) (A) (A) (A) (A)	\$1100	Section Visiting	No. 1886 A CONTRACTOR	William Control	J\gm _n
etal	Copper	09	0	7	\$10.0	8420.0	85900.0	\$900.0	
[stal	•muimbs 2	LS	l ·	C .	8900.0	8900:0	£\$10.0	910'0	J\gm Dom
letal	Beryllium	the second second	The state of the s	Mir. Addison.	18265E	Mary Maria	£6£00.0	\$100.0	in and the second
N. S. 17.30	Barium	19	0	1	**************************************	1100:0	. AES00.0	100.0	
[eta]		£9	I	0	.867.0	0.238	721.0	64.0	
etal	*ynomilnA	85*	7	7	. 2020.0	6580.0	.02E0.0	900:0	
etal	*munimulA	19	57	1	8.42	24.8	. S.A.E		J\gm
			woled the AL!						
			BG but	T∀	27			100	
		Samples Analyzed	apove Samples	Samples above the			SINS SZD		
100 CARROLL 1		Number	10	Jo	Conc	Conc	Mean	JA steW	

Note: Data are for surface water stations SW032, SW033, SW10295, SW50193, and SW50293. Analytes shown are mose maximum detected at least once above background levels and have a Surface Water Action Level. The maximum concentration is the maximum detected value, and the average concentration is the average of the data that exceed background.

*Background exceeds the AL.

4-23

^{**} The uranium surface water AL is for total uranium (sum of the isotopes).

BG - Background

AL - Action Level

This column includes the number of samples exceeding the AL but less than BG when the BG value for an analyte exceeds the AL.

Table 4-5b

Downgradient Woman Creek Surface Water Data Summary
(Dissolved Concentrations)

Analyte Group	Analyte	Total Number Samples Analyzed	Number of Samples above BG but below the AL	Number of Samples above the AL	Average Conc.	Maximum Conc.	BG Mean Plus 2SD	Surface Water AL	Unit
Metal	'Aluminum*	63	3	1	0.583	0.583	0.421	0.087	mg/L
Metal	Barium	65	1	0	0.123	0.123	0.116	0.49	mg/L
Metal	Beryllium*	57	∜ o	Security.	0.09	0.09	0.00504	0.004	mg/L
Metal	Cadmium*	61	0	. 2	0.00505	0.0051	0.00308	0.0015	mg/L
Metal	Copper	. 59	0	2 . 2 .	0.0315	0.04	0.01584	0.016	mg/L
Metal	Mercury.*		* 4	33	0.000353	0.00047	0.00026	0.00001	mg/L
Metal	Selenium*	63	1	3	0.0127	0.015	0.0095	0.0046	mg/L
Metal	Silver*	63	. 8	2001	0.0103	0.0103	0.00816	0.0006	mg/L
Metal	Zinc	66	6	0	0.0612	0.074	0:0499	0.141	mg/L
Radionuclide	Americium-241	12	0.		0.44	₹3.0.44	0.33	0.15	pCi/L
Radionuclide	Uranium-234**	31	5	0	3.00	5.72	1.08	10	pCi/L·
Radionuclide	Uranium-238**	. 32	6	0	2.04	4.81	0.82	10	pCi/L

Above the Surface Water Action Level

Note: Data are for surface water stations SW032, SW033, SW10295, SW50193, and SW50293. Analytes shown are those that were detected at least once above background levels and have a Surface Water Action Level. The maximum concentration is the maximum detected value, and the average concentration is the average of the data that exceed background.

^{*}Background exceeds the AL.

^{**} The uranium surface water AL is for total uranium (sum of the isotopes).

BG - Background

AL - Action Level

¹ This column includes the number of samples exceeding the AL but less than BG when the BG value for an analyte exceeds the AL

Table 4-6a
South Interceptor Ditch Surface Water Data Summary (Total Concentrations)

Analyte Group	Analyte	Total Number Samples Analyzed	Number of Samples above BG but below	Number of Samples above the AL	Average Conc	Maximum Conc.	BG Mean Plus 2SD	Surface Water AL	Unit
		\$	the AL1						
Metal	Aluminum*	81	39	4	32.636	99.6	3.45	0.087	mg/L
Metal	Arsenic*	79	16	3	0.00727	0.0094	0.00525	0.000018	mg/L
Metal	Barium	81	60	1	0.189	1.47	0.127	0.49	mg/L
Metal	Beryllium	79	. 0	1	0.00780	0.0078	0.00234	0.004	mg/L
Metal	Cadmium*	77	2	1	0.00900	0.009	0.00393	0.0015	mg/L
Metal	Copper	80	0.	2	0.075	0.122	0.0153	0.016	mg/L
Metal	Lead*	81	, 0	. 4	0.045	0.084	0.00658	0.0065	mg/L
Metal	Mercury*	74	6	» 1	0.00053	0.00053	0.00041	0.00001	mg/L
Metal	Nickel	75	3	0	0.059	0.105	0.0199	0.123 -	mg/L
Metal	Selenium*	79	0	i	0.020	0.02	70.00565	0.0046	mg/L
Metal	Silver*	80	5	6	0.009	0.0133	0.00591	0.0006	mg/L
Metal	Zinc*	.79		. 2	0.431	0.448	0.155	0.141	mg/L
Radionuclide	Americium-241	53	5	2 `	0.204	0.936	0.02	0.15	pCi/L
Radionuclide	Plutonium-239/240	68	. 5	2	0.172	0.612	0.02	0.15	pCi/L
Radionuclide	Tritium	47	0	3_	1563	2990	494	500	pCi/L
Radionuclide	Uranium-234**	54	45	~2	5.27	13.77	1.59	10	pCi/L
Radionuclide	Uranium-235**	52	26	0	0.426	1.03	0.19	10	pCi/L
Radionuclide	Uranium-238**	54	11	30	16.9	74	1.22	10	pCi/L
svoc	bis(2- Ethylhexyl)phthalate	23	1	2 .	2	. 3	. (%) (%)	1.8	μg/L
SVOC	Diethylphthalate	23	1	0	4	4	-	5600	μg/L
svoc	n- Nitrosodiphenylamine	23	1	0	4	4	<u>-</u>	5	μg/L
VOC	2-Butanone	51	2	0	7.5	12	-	21900	μg/L
VOC	Acetone	52	5	0	49.54	210	-	3650	μg/L
VOC	Bromoform	59	1	0	1.9	1.9		4.3	
VOC	Chloroform	59	4	0	2.36	4	· -	5.7	μg/L
VOC	Methylene chloride	59	10	3	3.08	7		4.7	μg/L
VOC	Toluene	59	2	0	2	3	-	1000	μg/L
VOC	Trichloroethene	59	1	1	4.5	8	•	2.7	μg/L
	Above the Surface Water	- A - 4 ! T	-1 :						

Above the Surface Water Action Level

Note: Data are for surface water stations INT. DITCH, SW036, SW038, SW129, and SW500. Analytes shown are those that were detected at least once above background levels and have a Surface Water Action Level. The maximum concentration is the maximum detected value, and the average concentration is the average of the data that exceed background.

^{*}Background exceeds the AL.

^{**} The uranium surface water AL is for total uranium (sum of the isotopes).

BG-Background

AL - Action Level

This column includes the number of samples exceeding the AL but less than BG when the BG value for an analyte exceeds the AL.

Table 4-6b South Interceptor Ditch Surface Water Data Summary (Dissolved Concentrations)

					-	Level	Water Action	Above the Surface	
J\iDq -	01	28.0	52.9	Lt L	b.	SI	97	**862-muins1U	Radionuclide
DGi/L	· 01	80.1 ¥	8.11 : %	81.5	1,377		97,	**AES-muins1U	Radionuclide
	141.0	6610.0	I care	867.0	7	ε ,	IS.	Sinc	Metal
J\gm	£21.0	9810.0	£90.0	£90'0	0	I	IS	Nickel	Metal
. 7]/gm	100000.0	97000.0	100.0	L000.0	E	J.	87	.Mercury*	Metal
J\gm	\$900.0	65400.0°	2T0.0	72E0.0	7	1	- 75	Lead	Metal :
7/8w	9100	8210.0	101.0	101.0	-I	0.00	IS	Copper	Metal
/J/8w	\$100.0	80500.0	81/00.0	2400.0	7	Pogra.	Ltr	Cadmium*	Metal
. Лувт	Þ 00 0	\$0500°0	60.0	60:0	(I = 2)	1	£\$	Beryllium* :	Metal
J\gm	6 þ .0	911.0	871.0	S41.0	0	9€	£\$	Barium	Metal
J\gm	0.000018	28500.0	\$00.0	S#00.0	7	L	Lt	*Arsenic*	Metal
J\gm;	₹. 780.0	* 124.0	6'97	6.94	T. # 18.3	ε .	IS.	**. *munimulA	Metal : 1
	2.77					'UA' ətb	75		1.0
					JA əti	BG but			
		SZD.			SPOVE	> Syods.	Analyzed		
	Water AL	Mean	Conc.	ouo	Samples	Samples Ot	Number Samples		Gronb
, jinU	Surface	BC	mumixeM	Average	Mumber	Number	latoT.	Analyte :	Analyte

value, and the average concentration is the average of the data that exceed background.

Agine, and the average concentration is the average of the data that exceed background.

^{*}Background exceeds the AL.

^{**} The uranium surface water AL is for total uranium (sum of the isotopes).

BG - Background AL - Action Level

¹ This column includes the number of samples exceeding the AL but less than BG when the BG value for an analyte exceeds the AL.


Table 4-7
Sediment Data Summary


Analyte	Total Number Samples Analyzed	Number of Samples above BG but below the AL	Number of Samples above the AL	Average: Conc	Maximum Conc.	Bkg Mean Plus 2SD	Wildlife Refuge Worker AL	Unit
Aluminum	4	1	0	17400	17400	15713	228000	mg/kg
Antimony	3	1	0	36.5	36.5	13.01	409	mg/kg
Cadmium	4	1	0	2.8	2.8	1.88	962	mg/kg
Copper	4	1	0	125	125	27.3	40900	mg/kg
Mercury	4	1	0	3.8	3.8	0.34	25200	mg/kg
Nickel	4	1	0	21.3	21.3	17.9	20400	mg/kg
Silver	4	1	0	7.7	7.7	2.28	5110	mg/kg
Zinc	4	2 .	0	513.5	681	104	307000	mg/kg
	Above the Wildlife Refuge Worker Action Level						-	


Note: Analytes shown are those that were detected at least once above background levels and have a Wildlife Refuge Worker Action Level. The maximum concentration is the maximum detected value, and the average concentration is the average of the data that exceed background.


BG - Background


AL - Action Level





















Figure 4-9 Dissolved Antimony in Groundwater



425

Figure 4-10 Dissolved Beryllium in Groundwater




Figure 4-11 Dissolved Cadmium in Groundwater




Figure 4-12 Dissolved Lead in Groundwater




Figure 4-13 Dissolved Manganese in Groundwater




Figure 4-14 Dissolved Nickel in Groundwater




Figure 4-15 Dissolved Selenium in Groundwater




Figure 4-16 Dissolved Thallium in Groundwater




Figure 4-17 Dissolved Strontium-90 in Groundwater




Figure 4-18 Dissolved Uranium Concentrations and Isotopic Activity Ratios in Groundwater at Well 61093




Figure 4-19 Dissolved Uranium Concentrations and Isotopic Mass Ratios in Groundwater at Well 61093




Figure 4-20 Total Uranium Concentrations and Isotopic Mass Ratios in Groundwater Measured by ICP MS




Figure 4-21 Dieldrin in Groundwater






Figure 4-22 Bis(2-ethylhexyl)phthalate in Groundwater at Wells with a Tier II Exceedance







Figure 4-23 Tetrachloroethene in Groundwater at Wells with a Tier II Exceedance



19-Sep-91 31-Jan-93 15-Jun-94 28-Oct-95 11-Mar-97 24-Jul-98 06-Dec-99 19-Apr-01 01-Sep-02 14-Jan-04 28-May-05

Figure 4-24 Trichloroethene in Groundwater at Wells with a Tier II Exceedance








Draft Interim Measure/Interim Remedial Action for the Original Landfill (Including IHSS Group SW-2; IHSS 115, Original Landfill and IHSS 196, Filter Backwash Pond)

Figure 4-26 Nitrate Concentrations in Groundwater at Wells with a Tier II Exceedance



U-238/U-234 Ratio 0.0 5.0 3.0 2.0 6.0 0. Figure 4-27 Total Uranium Concentrations and Uranium Isotopic Ratios for Surface Water at SW-36 50,107 Sample Date School of School 16.10N.VO 06.06.06.06.06.06.66.67. is South of the so 9 100 9 8 8 8 8 2 20 Uranium Conc. (pCi/L)

☐☐ U Total — — U-238/U-234 Ratio

5.0 REMEDIAL ACTION OBJECTIVES

Based upon an evaluation of the OLF operation and associated waste types as well as the risks posed by exposure pathways from the OLF, an accelerated action consistent with the municipal and military landfill presumptive remedy of source containment after hot spot removal (completed in August 2004) is appropriate for the OLF. The streamlining features for evaluating the contamination source and baseline risks posed to human and ecological health afforded by the landfill presumptive remedy directives have been met by conducting the OU 5 Phase I RFI/RI (K-H 1996). However, the information obtained by the investigation and subsequent monitoring substantiates the application of specific source containment components necessary to address the OLF exposure pathways.

Guidance in the Application of the CERCLA Municipal Landfill Presumptive Remedy to Military Landfills, OSWER Directive No. 9355.0-67FS, December 1996, was used to evaluate the characteristics of the OLF in relation to those that affect application of the source containment remedy. The following characteristics are consistent with the relevant guidance for the presumptive remedy:

- Risks are low-level, except for uranium surface "hot spots" (uranium surface soil "hot spots" were removed in August 2004, see Appendix C);
- Treatment of waste is impractical due to its volume and heterogeneity of waste; and unnecessary because the OLF presents limited, to no risk to human health and the environment from waste materials exposed at the surface.
- Waste types include household, commercial (for example, construction debris), nonhazardous sludge, and industrial solid wastes (for example, process wastes, VOCs, paints).
- Small amounts of wastes with hazardous constituents were disposed of in the OLF and the amounts are very small compared with a typical municipal waste landfill.

The guidance notes that some military facilities (for example, weapons fabrication and testing) have a high level of industrial activity compared to overall site activities such that there may be a higher proportion and wider distribution of industrial wastes than at less industrialized facilities. The guidance also notes that some wastes specific to military landfills (for example, low-level radioactive wastes) as long as they are not predominant, can be considered low-hazard and no more hazardous than other waste found in municipal landfills. Other military wastes, such as munitions, chemical warfare agents, and chemicals, are high-hazard wastes and require special consideration. These types of wastes were not disposed of in the OLF.

As described in the OU 5 Phase I RFI/RI Report and Sections 2.0 and 4.0 of this IM/IRA, the types of wastes, levels of contamination, and risks posed by the OLF are similar to those deemed appropriate to implement a presumptive source containment remedy. It is also important to note that the OLF has been closed for approximately 35 years with an inadequate soil cover, limited stormwater run-on and runoff controls, and very little

maintenance applied, and yet the levels and extent of contamination in environmental media are quite low.

Some surface and subsurface soil samples contained contamination above specific Soil Action Levels in RFETS Action Levels and Standards Framework for Surface Water, Ground Water and Soils, RFCA Attachment 5 (ALF), Table 3, Soil Action Levels. ALF Sections 4.0 and 5.0 require removal of contaminated surface soils to depths specified for non-radioactive and radioactive contaminants. At the OLF, these areas are surface soil "hot spots" that were removed with the approval of the CDPHE, as documented in a RFETS Regulatory Contact Record (see Appendix C).

Deeper soil that are contaminated above soil action levels must be evaluated in accordance with the ALF Figure 3, Subsurface Soil Risk Screen and ALF Section 4.2 and 5.3 to determine whether an action is required. For convenience, ALF Figure 3 is included as Figure 5.1. Because soils action levels are exceeded, the OLF fails Screen 1. Since the OLF lies in an erosion area and the waste and commingled soil have become exposed on the surface, the OLF also fails Screen 2. It is assumed that some subsurface soil may exceed soil action levels for depleted uranium, particularly below the surface hot spots, given this, it is likely the OLF fails Screen 3. Under Screen 4, it appears the uranium contamination found at SW-036 could be caused at least in part by surface run off into the SID. While this sampling point is not an ALF Section 2 surface water Point of Compliance or Point of Evaluation, an accelerated action evaluated under Screens 2 and 3 should adequately address this potential contaminant source. For Screen 5, the baseline Ecological Risk Assessment for the Woman Creek Priority Drainage discussed in Section 4. 9 of this IM/IRA concluded that there is not an unacceptable risk to ecological receptors. Additional ecological action levels are being developed and ecological risks will be evaluated in the Accelerated Ecological Screening Process and the Comprehensive Risk Assessment.

The OU 5 Phase I RFI/RI concluded that the OLF does not generate hazardous concentrations of landfill gas, thus gas collection or treatment action is not required.

Groundwater at the OLF contains concentrations of some organic compounds and metals, including depleted uranium, greater than background and ALF Table 2, Action Levels for Groundwater. However, this contamination does not generate an expanding plume of groundwater contamination outside of the OLF source area and does not adversely impact surface water quality or present an exposure pathway outside of the OLF source area. In accordance with ALF, Section 3.3.C.2, groundwater plumes that can be shown to be stationary and do not therefore present a risk to surface water, regardless of their contaminant levels, do not require mitigation or management. They do require continued monitoring to demonstrate that they remain stationary. Groundwater at the OLF is not a drinking water source and could not sustain any prolonged use, such as for a drinking water.

Based upon the foregoing evaluation, risks posed by the OLF will be addressed by the proposed accelerated action. The proposed action is to implement "hot spot" removal (completed August 2004) and the presumptive remedy of source containment. There are two pathways of exposure to be addressed by the accelerated action:

direct exposure to disposed waste and commingled soil; and

• surface erosion and runoff of contaminants into surface water.

Therefore, the Remedial Action Objectives (RAOs) for the OLF are to:

- Prevent direct contact with landfill soil and commingled waste and
- Control erosion caused by Stormwater run-on and runoff.

In addition to the "hot spot" removal (completed in August 2004), components of the source containment remedy that are necessary to address the RAOs are:

- a stable landfill cover to prevent direct contact with landfill soil or debris;
- a landfill cover that adequately controls erosion caused by stormwater runon and runoff; and
- institutional controls to supplement engineering controls to appropriately monitor and maintain the landfill cover.

In addition to these components, groundwater and surface water monitoring will be conducted. Additional evaluation and a description of the presumptive remedy components and alternatives are presented in Sections 6.0 through 10.0.




Figure 5-1 Subsurface Soil Risk Screen

6.0 REMEDIAL ACTION ALTERNATIVES EVALUATION

This section describes the remedial action alternatives considered for the OLF (IHSS 115) and Filter Backwash Pond (IHSS 196) and presents a comparative analysis of the alternatives in accordance with the CERCLA guidelines, the remedial action objectives, and applicable or relevant and appropriate requirements (ARARs).

6.1 Remedial Action Alternatives

This section presents four remedial action alternatives for the OLF. The alternatives include leaving the waste in an undisturbed state, leaving the waste in place with a protective soil cover, combining a buttress fill with a soil cover, and total removal.

6.1.1 Alternative 1 – No Action

Alternative 1 minimizes direct contact of wastes remaining at the site by limiting access to the OLF. All waste would be left in place as is currently the situation and site features, such as Woman Creek and the SID, would not be disturbed. The PMJM protection area would also not be disturbed. Because waste would be left in place, institutional controls and site monitoring are considered part of this alternative.

Institutional Controls

Institutional controls would be used at the site to provide short- and long-term protection of human health and the environment. Institutional controls include administrative and/or legal controls that minimize the potential for human exposure to contamination by limiting land or resource use. Land use restrictions would be required to restrict use of the area. In addition, advisories, or warnings that provide notice to potential users of the land, surface water, or groundwater would be necessary.

Site Monitoring

The current conditions of surface water, groundwater and soil erosion at the OLF would be monitored to track any changes that might result in an adverse condition. Monitoring would be instituted through the current RFETS Integrated Monitoring Program (IMP) and ultimately in Sitewide post-closure regulatory documents. Additional monitoring wells could be installed, if needed, to provide sufficient coverage to monitor changes in groundwater quality. In addition, an annual inspection of the area would be conducted to identify any visual changes at the OLF. An annual ground topographic survey would be completed to monitor slope stability.

6.1.2 Alternative 2 – Soil Cover

This alternative consists of the removal of surface soil "hot spots," (soil removal complete) clearing and grubbing of the landfill area, limited area grading, and implementing the presumptive remedy by placement of a soil cover, cover revegetation, monitoring, and institutional controls.


Removal of Surface Soil Contaminants


The contaminants exceeding soil action levels are discussed in Section 4.3.

The surface soil hot spots were removed in August 2004. Appendix C describes the removal efforts and presents the confirmation sampling results

Area Grading & Soil Cover

The waste fill area would be graded to generally an 18-percent (5.5:1) slope, or less, using a cut-and-fill approach that would be as balanced as possible. A conceptual grading plan and cross-section are shown on Figures 6-1 and 6-2, respectively. Standard earth-moving equipment, such as dozers, hoes or scrapers, would be used to cut areas where the slope exceeds the desired 18 percent and fill those areas where the slope is less than the desired 18 percent slope. It is estimated that approximately 55,000 cy of waste fill material would be moved during the process and 105,000 cy of fill would be required to reach the 18-percent grade before placing the 2-ft cover.





Control measures would be implemented during the grading process to control the spread and release of waste materials in the OLF. The control measures would include the establishment of work zones, decontamination procedures, dust suppression methods, traction mats, visual inspections, and radiological surveys. Work would be suspended when environmental conditions could greatly increase the possibility of the spread of contaminated materials. Monitoring would be performed, as necessary, to verify that there has been no release of contaminated materials.

After the grading of the landfill surface is complete, a soil cover will be placed over the landfill to a minimum thickness of 2 ft. About 65,000 cubic yards of local or onsite soil will be used to construct the cover. The soil cover will be compacted sufficiently to provide a stable cover system to promote surface water runoff, reduce surface water ponding, increase overall slope stability, and provide a suitable soil surface for revegetation.

Revegetation of the soil cover with native species will reduce infiltration and control erosion. The seeding will be conducted ,along with erosion control matting or mulch to prevent erosion of the cover while allowing the vegetation to establish a strong stand.

Institutional Controls

Post-accelerated action institutional controls will be implemented. These controls consist of access controls, continued DOE jurisdiction, and controls to prevent drilling, excavation, or disruption of the cover or sampling stations. Routine monitoring and inspection of implemented controls will be performed.

6.1.3 Alternative 3 – Soil Cover With Buttress Fill

All the components of Alternative 2 (Section 6.1.2) are included in Alternative 3. Additional features of Alternative 3 include the construction of a buttress fill at the toe of the regraded surface of the OLF and the possible construction of an upgradient groundwater "cutoff" wall immediately north of the OLF.

Buttress Fill

A structural soil fill would be built at the toe of the OLF regraded surface as conceptually depicted on Figure 6-3. The buttress fill would be either placed on top of the weathered bedrock or just beneath the weathered bedrock on top of the unweathered bedrock. The buttress fill would be built by placing specified structural fill soil in loose lifts and compacting thelifts to a desired relative compaction requirement.

If it was determined during the design of the buttress fill that the buttress would be placed through the weathered bedrock on top of the unweathered bedrock, trench boxes or other structural support methods could be required to allow excavation of the weathered bedrock. These special construction provisions would be needed to prevent movement of the waste fill above the weathered bedrock excavation into the buttress construction area.

A rock layer and strip drains would be placed under and upgradient of the buttress fill to reduce and control the hydraulic head behind the buttress fill. These drainage layers are

needed to prevent water saturation of the fill soil and eliminate any seepage flow through or around the buttress fill.

Upgradient Groundwater "Cut-off" Wall

An upgradient groundwater "cut-off" wall would be considered with this alternative to further control the lateral inflow of groundwater into the OLF. A wall for this purpose would be constructed of a soil/bentonite type slurry keyed into the weathered bedrock. However, the groundwater modeling indicates that the impact on groundwater levels in the OLF from the construction of such a wall would be very minimal and on the order of less than 3 ft.


6.1.4 Alternative 4 – Removal of Waste

The objective of this alternative is to remove the entire waste fill from within the OLF area and restore the hill slope. The remedial measures would consist of the following five activities:

- Preparation of the site;
- Excavation of contaminated debris and soil;
- Characterization and segregation of waste fill debris and soil;
- Off-site disposal of waste fill debris and contaminated soil; and
- Restoration of disturbed areas.
- It is estimated that approximately 192,000 cubic yards (bulking of 160,000 cubic yards of commingled soil) of waste fill debris and soil would be excavated, characterized, and transported to an off-site, licensed disposal facility. The volumes of radioactive and nonradioactive contamination in the waste fill are currently unknown, but would be determined during implementation. These remedial measures would be completed in approximately 3 years. Specific activities to implement this alternative are described below.

Site Preparation

Prior to excavation of the waste fill debris and soil, the site would be prepared. First, access roads and storage areas would be constructed. Second, the area to be excavated would be cleared and grubbed, and surface water control features would be constructed. The procedures used to complete these tasks are described below.



Construction of Storage Areas and Access Roads

A storage area would be located north of the OLF boundary. It is estimated that three to four acres would be required to accommodate the required equipment, supplies, and construction offices to stage and characterize the removed waste materials and soil.

In addition, this alternative would require the construction of three new access roads. The first new access road would be constructed to connect the existing access road that runs east-west through the center of the OLF to the waste fill area located in the northeastern section of the landfill. The second new access road would be located south of the OLF boundary to connect the existing access road to the waste fill area located in the southern section of the landfill. The third new access road would be located on the western edge of the OLF boundary to connect the existing access road to the stockpile area. The combined length of these new access roads would be approximately 2,000 ft. The maximum grade of the new roads would not exceed 7 percent, and the design would allow for drainage of surface water while the roads were in use.

Clearing, Grubbing, and Stockpiling

A stockpile area would be located on the terrace immediately northwest of the IHSS boundary. It would be approximately two acres in size and would accommodate up to 20,000 cubic yards of waste fill material at any given time during the project.

The area within the OLF boundary would be cleared and grubbed of vegetation, debris, loose rocks, and other items that would interfere with the waste fill removal process. The cleared materials would be transported to the stockpile area for characterization prior to disposal. Surface water would be directed around the stockpile and excavated areas.

Excavation of Contaminated Waste Fill Debris and Soil

The area that would be excavated is shown on Figure 1-2. The waste fill within this area would be stripped and placed into temporary stockpiles using standard equipment, such as crawler-type dozers, track-type loaders, and track-mounted excavators. The machines utilized would be small enough to ensure a high degree of cut accuracy and a minimum amount of over excavation. Trucks or large-capacity wheel loaders would be used to move the waste fill from temporary stockpiles to the primary stockpile area located immediately northwest of the OLF boundary.

Excavated areas would be carefully inspected visually and with field instrumentation to determine the outer limits of the waste fill area. Confirmation sampling and analysis would be then conducted to verify that radioactive and nonradioactive waste materials have been adequately removed.

Characterization of Waste Fill Debris and Soil

The waste fill material removed from the OLF during the grubbing and excavation processes would be characterized at the stockpile area using a two-step process. First, field screening techniques would be used to determine the radioactivity of the stockpiled materials. Second, samples would be collected and analyzed to determine if the material is a characteristic RCRA

hazardous waste. Potential hazardous waste would be further characterized using the Environmental Protection Agency (EPA) TCLP analysis.

Disposal of Waste Fill Debris and Soil

Following characterization, each pile of waste fill material would be classified for disposal. Items determined to be radiologically contaminated or that exhibit a toxicity characteristic would be transported to an appropriately licensed facility for final disposal. Items determined not to be radiologically contaminated or that do not exhibit a toxicity characteristic would be managed as solid waste. Waste material classified as solid waste and meeting disposal facility waste acceptance criteria would be disposed of at a local sanitary landfill.

Restoration of Disturbed Areas

Following completion of remediation activities, the disturbed areas would be reclaimed. This process would require some grading and backfilling of the area prior to seeding and revegetation. The seeding and revegetation process would be the same as described in Section 6.1.2.

6.2 COMPARATIVE EVALUATION OF ALTERNATIVES

This section provides a comparative evaluation of the remedial alternatives using the criteria of effectiveness, implementability, slope stability, and relative cost. A summary of the comparative evaluation is provided in Table 6-1.

The relative cost estimates provided in this report are preliminary, and are provided primarily for the purpose of comparing the various remedial action alternatives. The final actual costs of a remedial alternative will depend upon the labor and material costs, site conditions, productivity, and competitive market conditions for contractors at the time of implementation, as well as the final project scope, final project schedule, final engineering design, and other variable factors. As a result of these uncertainties, the final costs will vary from the estimates provided herein.

Estimated costs of the alternatives include indirect capital costs, direct capital costs, and annual costs. Estimated costs were prepared utilizing estimated volumes, vendor quotes, available literature, Means Cost Data guides (R.S. Means Company 2001), and other sources deemed appropriate.

Table 6-1
Summary of Comparative Evaluation of Potential Remedial Alternatives

Summ	iary oi Comparat	ive Evaluation of	Potential Remedial	Alternatives
Criteria	Alternative 1 No Action	Alternative 2 Limited Grading & Soil Cover	Alternative 3 Limited Grading, Soil Cover & Buttress Fill	Alternative 4 Removal with Off-Site Disposal
Effectiveness	Low	Moderate	Moderate	High
Protection of Public Health and Environment	Current wastes remain exposed and potential erosion continues; however, OLF currently exhibits limited to no impact on public health and the environment.	Exposed wastes are covered and further slope erosion is eliminated to exposed wastes in the future.	Exposed wastes are covered and further slope erosion is eliminated to exposed wastes in the future. Buttress fill provides some increase in overall slope stability but impacts more of the PMJM habitat and wetlands areas	All waste removed from area.
Long-Term Effectiveness and Permanence	No long-term protection provided due to exposed waste.	Proven technologies over the long term implemented.	Proven technologies over the long term implemented.	Removes all waste from the area.
Short-Term Effectiveness	Low due to exposed waste; however, PMJM and wetlands would not be affected.	Moderate to High short-term effectiveness since risks associated with some limited movement of waste materials. PMJM and wetlands mitigation required.	Additional risk to workers during construction of buttress fill. Additional PMJM and wetlands mitigation required.	Low short-term effectiveness due to the potential to release contamination from the excavation and movement of waste materials. PMJM and wetlands mitigation required.
Compliance with Remedial Action Objectives	Would not comply RAOs.	Will comply with RAOs.	Will comply with RAOs.	Will comply with RAOs.
Implementability	High	Moderate/High	Moderate/Low	Low
Technical Feasibility	Technically feasible	Technically feasible	Technically feasible	Technically feasible
Maintenance and Monitoring Requirements	Annual inspection, maintenance, and repair on as-needed basis	Periodic inspection, maintenance, and repair on as-needed basis	Periodic inspection, maintenance, and repair on as-needed basis	No maintenance or monitoring required
Construction Feasibility	Construction is feasible	Construction is feasible	Construction feasible, but more difficult.	Construction is feasible but much more difficult and time consuming
Availability of Services and Materials	All materials locally available	All materials locally available	All materials locally available	Disposal facilities available in U.S
Administrative Feasibility	Not administratively feasible	Administratively feasible	Administratively feasible	Administratively feasible
Stability	Moderate	High	High	Moderate
Static Factor of Safety	1.3 – 1.5	1.5 – 1.7	1.7 – 1.9	Not applicable
Seismic Factor of Safety	0.7 - 0.8	0.9	0.9 – 1.0	Not applicable
Estimated Deformation	10" - 12"	5" – 10"	3" - 5"	Not applicable
Capital Cost*	\$50,000 to \$60,000	\$4.0 MM to \$4.6 MM	\$6:0 MM to \$6.9 MM	\$100 MM to 260 MM
O&M Cost (\$/yr)	***\$25,000	\$31,000	\$31,000	\$0
Present Worth Cost**	\$800,000 to \$810,000	\$4.93 MM to 5.53 MM	\$6.93 MM to \$7.83 MM	\$100 MM to 260 MM
Regulatory/ Community Acceptance	Low	Moderate	High	Moderate

Costs are in 2004 dollars.

^{**} Assumes 30 years of O&M without an escalation factor

6.2.1 Alternative 1 – No Action

This alternative, as presented in Section 6.1.1, consists of only institutional controls and monitoring.

Effectiveness

Effectiveness considers whether the alternative provides protection of human health and the environment, and achieves the remedial objectives.

Protectiveness

The No Action Alternative would leave the waste in place as it exists today and allow for potential release of contaminants; however, as presented in Section 4.0, the OLF currently exhibits limited to no impact on human health and the environment. Alternative 1 would attain all Applicable and Relevant and Appropriate Requirements (ARARs), except those relative to the landfill cover. Institutional controls, such as signs and other barriers would help to reduce human exposure to the waste materials. However, wildlife workers and trespassers may occasionally enter the area and could potentially come in contact with the OLF debris.

In the short term, there would be low risks to the workers and public during the implementation of this alternative, and no impact on the Preble's Meadow Jumping Mouse habitat south of the OLF or to wetlands within the OLF.

Alternative 1 is not considered effective in the long term. Potential exposure to OLF debris and continued surface erosion would remain; however, as presented in Section 4.0, the OLF currently exhibits limited to no impact on human health and the environment. Alternative 1 would continue to provide existing habitat for the PMJM without disruption, and would not disturb or destroy the wetlands at the OLF. Institutional controls and monitoring would provide for some continuing protection.

Achieve Remedial Objectives

Alternative 1 would not comply with the RAOs of preventing direct contact with the landfill waste or controlling the existing surface erosion patterns. However, as presented in Section 4.0, the OLF currently exhibits limited to no impact on human health and the environment.

Implementability

Implementability addresses the technical and administrative feasibility of implementing an alternative using the required equipment, services, and materials.

Technical Feasibility

Alternative 1 is technically feasible because no construction activities would be required except for the fabrication and installation of signs and possibly barriers. With this limited construction, the PMJM habitat and wetlands would remain undisturbed. However, Alternative 1 would provide monitoring of the long-term physical features

of the OLF to identify any detrimental changes. Maintenance of the institutional controls implemented would be considered minimal.

Availability

Alternative 1 would only require materials for signs and possibly barriers to implement institutional controls. These materials are readily available. Monitoring would use industry standard equipment and materials that are also readily available.

Administrative Feasibility

The implementation of Alternative 1 does not require permits or easements, and does not impact adjoining property. It will not inhibit the ability to impose institutional controls. Existing site management and access controls would be maintained until a comprehensive final plan is implemented in the future. The alternative is generally consistent with the aesthetic qualities of the facility end use as a wildlife refuge.

Alternative 1 would most likely not meet CDPHE, EPA, and community acceptance because debris is left exposed at the surface of the OLF and surface erosion would most likely continue.

Cost

Evaluation of costs should consider the capital costs to engineer, procure, and construct the required equipment and facilities, and the operating and maintenance costs associated with the alternative.

Capital Cost

The capital cost to implement Alternative 1 is between \$50,000 and \$60,000.

Operation & Maintenance Cost

The operation and maintenance costs associated with this alternative involve inspection of the OLF surface and maintenance of the groundwater and surface water monitoring stations. Sampling and analysis of groundwater and surface water is also included. Operation and maintenance costs are estimated to be approximately \$25,000 per year; however, additional costs could be incurred to address any hazards exhibited by the wastes continuing to be exposed.

Summary – Alternative 1

Alternative 1 was not retained for further consideration because the OLF debris remains exposed and potential surface erosion would continue. The OLF currently exhibits little to no impact on human health and the environment.

6.2.2 Alternative 2 – Soil Cover

Alternative 2, Soil Cover is presented in Section 6.1.2 and generally includes the removal of radiologically contaminated surface soil (completed in August 2004), limited site grading, placement of a 2-ft-thick soil cover, and revegetation of the soil cover.

Effectiveness

Effectiveness considers whether the alternative provides protection of human health and the environment, and achieves the remedial objectives.

Protectiveness

Alternative 2 would provide a higher overall level of protection than Alternative 1 because the waste would be covered, eliminating direct contact with the OLF debris. The radiologically contaminated soil has already been removed. Alternative 2 would comply with ARARs. The stabilization of the hillside would add additional long-term protection of the waste fill area by reducing the possibility of movement and erosion. Potential remediation worker exposure would be higher during implementation of Alternative 2 than during Alternative 1 because of the movement of waste during the regrading operations. However, appropriate safety measures will be employed to protect the worker during construction.

The regraded surface provides for a more stable configuration. Static factors of safety are estimated to be from 1.5 at "wet-year" groundwater levels to 2.2 during "dry-year" conditions. Also, the seismic factors of safety are estimated at 1.0 to 1.2 with a possible corresponding deformation range of 9 to 6 inches. The seismic calculations assume a 0.12 (Xg, gravity) peak acceleration coefficient, which has a 2-percent probability of occurring every 50 years (ref. for Geotech report).

Alternative 2 would have low to moderate short-term effectiveness. This alternative has a chance of impacting workers, the public, and the environment during implementation. Most of the potential health impacts would be due to potential inhalation of fugitive dust and the ingestion of dust and contaminated materials (hand to mouth). However, health and safety controls would be readily implemented to protect workers and the public. A site-specific Health and Safety Plan (HASP) would be developed for the site that addresses worker safety including dust monitoring, decontamination procedures, etc. Also, engineering controls, such as the addition of water to disturbed areas, would be implemented to control dust. During the implementation of these alternatives, there would also be the potential for short-term impacts to the environment due to spills, dust, and surface runoff from disturbed areas. These impacts would be readily controlled through appropriate transportation and engineering practices, such as covering of loads, onsite spill cleanup, dust control measures, erosion protection, silt fences, etc. In addition, construction activities would remove some jurisdictional and candidate wetlands and a portion of the PMJM protection area within the boundary of the OLF.

Alternative 2 will provide a long-term cover over the currently exposed OLF debris and eliminate the current erosional conditions. However, because the OLF (as presented in Section 4.0) currently exhibits limited to no impact on human health and the environment, Alternative 2 provides containment of the OLF materials consistent with the presumptive remedy discussed in Section 1.1. Alternative 2 would rely upon proven technologies for slope stabilization and landfill covering. Infiltration of

⁸ The factor of safety is the ratio of the force resisting movement to the force causing movement.

surface water would be reduced through installation of a soil cover with a consistent grade.

Achieve Remedial Objectives

Alternative 2 will meet all of the remedial action objectives. The Landfill will be covered with an appropriately designed soil cover to prevent contact with the waste materials. Construction activities will remove wetlands and a portion of the PMJM protection area within the boundary of the OLF; however, the PMJM habitat would return after construction of the action.

Implementability

Implementability addresses the technical and administrative feasibility of implementing an alternative using the required equipment, services, and materials.

Technical Feasibility

Alternative 2 is technically feasible using proven controls and engineering design features that have been successfully implemented at other sites with similar conditions. All controls within the alternative could be executed using readily available machinery, including earthmoving equipment, haul trucks, and other conventional construction equipment.

Alternative 2 will require maintenance of the cover through routine inspections and repair as needed. Monitoring of groundwater and surface water would be required; however, the requirements would be slightly less than for Alternative 1 because of the containment provided by Alternative 2.

Availability

For Alternative 2 mainly natural materials are required. The cover materials would either come from an on-site borrow source, or a borrow source close to the site. Monitoring would use industry standard equipment and materials that are also readily available.

Administrative Feasibility

The implementation of Alternative 2 does not require permits or easements, and does not impact adjoining property. It will not inhibit the ability to impose institutional controls. Existing site management and access controls would be maintained until a comprehensive final plan is implemented in the future. The alternative is consistent with the aesthetic qualities of the facility end use as a wildlife refuge.

Alternative 2 will remove jurisdictional wetlands and a portion of the PMJM protection area.

Alternative 2 would most likely gain CDPHE, EPA, and community acceptance.

Cost

Evaluation of costs should consider the capital costs to engineer, procure and construct the required equipment and facilities, and the operating and maintenance costs associated with the alternative.

Capital Cost

The capital cost to implement Alternative 2 is between \$4,000,000 and \$4,600,000.

Operation & Maintenance Cost

The operation and maintenance costs associated with this alternative involve inspection and maintenance of the cover. Other monitoring costs, such as groundwater and surface water monitoring would also be included. Operation and maintenance costs are estimated to be \$31,000 per year.

Summary – Alternative 2

Alternative 2 implements the presumptive remedy, meets all of the remedial action objectives and attains the ARARs.

6.2.3 Alternative 3 – Soil Cover with Buttress Fill

Alternative 3, Soil Cover with a buttress fill is presented in Section 6.1.3 and generally includes the removal of radiologically contaminated surface soil (completed in August 2004), limited site grading, placement of a 2-ft-thick soil cover, revegetation of the soil cover, and installation of a buttress fill at the toe of the regraded slope.

Effectiveness

Effectiveness considers whether the alternative provides protection of human health and the environment, and achieves the remedial objectives.

Protectiveness

Alternative 3 provides the same degree of overall protection as Alternative 2 because the waste would be covered to prevent direct contact. Alternative 3 would comply with ARARs. Construction of the buttress fill would only slightly add additional long-term protection of the waste fill area by reducing the possibility of movement (see Table 6.1). Potential worker exposure to radioactively and nonradioactively contaminated substances would be higher during implementation of Alternative 3 than during Alternative 2 because of the excavation of soil and possibly the weathered bedrock to allow construction of the buttress.

Alternative 3 would provide a slightly higher level of long-term effectiveness because the stability of the OLF coupled with the stability of an appropriately designed soil cover the buttress would increase slightly. Alternative 3 would rely upon proven technologies for slope stabilization and landfill covering. Although unlikely, plugging of the buttress drains could lower the stability of the buttress by saturating the buttress soil and increasing the water levels.

Alternative 3 would have lower short-term effectiveness than Alternative 2. This alternative has a greater chance of impacting workers, the public, and the environment during implementation. Greater potential health impacts would be due to creating more potential inhalation of fugitive dust and the ingestion of dust and contaminated materials (hand to mouth) and the risks associated with construction of the buttress (more heavy equipment and truck traffic). However, health and safety controls would be readily implemented to reduce the risk to workers and the public. In addition, construction of Alternative 3 would remove more jurisdictional and candidate wetlands and PMJM protection area than Alternative 2, and prevent the growth of PMJM habitats up the landfill slope.

Achieve Remedial Objectives

Alternative 3 would meet all of the remedial action objectives. The Landfill would be covered with an appropriately designed soil cover to prevent contact with the waste materials. However, construction activities will permanently remove wetlands and a portion of the PMJM protection area within the boundary of the OLF.

Implementability

Implementability addresses the technical and administrative feasibility of implementing an alternative using the required equipment, services, and materials.

Technical Feasibility

Alternative 3 is technically feasible using proven controls and engineering design features that have been successfully implemented at other sites with similar conditions; however, the buttress fill is more difficult to build than the components of Alternative 2. Construction of the buttress may require trench boxes or special shoring to prevent movement of soil and waste materials into the buttress excavation. All controls within the alternative could be executed using readily available machinery, including earthmoving equipment, haul trucks, and other conventional construction equipment.

Alternative 3 would require more maintenance and inspections than Alternative 2 because of the added component buttress fill. Monitoring of groundwater and surface water would be required, just like Alternative 2.

Availability

For Alternative 3 mainly natural materials are required; however, more material will be required than for Alternative 2. The materials would either come from an on-site borrow source, or a borrow source close to the site. Monitoring would use industry standard equipment and materials that are also readily available.

Administrative Feasibility

The implementation of Alternative 3 does not require permits or easements, and does not impact adjoining property. It will not inhibit the ability to impose institutional

controls. Existing site management and access controls would be maintained until a comprehensive final plan is implemented in the future. The alternative is consistent with the aesthetic qualities of the facility end use as a wildlife refuge; however, the migration of PMJM habitat north of the buttress would be seriously slowed or eliminated.

Alternative 3 would permanently remove jurisdictional wetlands and PMJM protection area.

Alternative 3 would most likely gain CDPHE, EPA, and community acceptance more readily than Alternative 2.

Cost

Evaluation of costs should consider the capital costs to engineer, procure and construct the required equipment and facilities, and the operating and maintenance costs associated with the alternative.

Capital Cost

The capital cost to implement Alternative 3 is between \$6,000,000 and \$6,900,000.

Operation & Maintenance Cost

The operation and maintenance costs associated with this alternative involve inspection and maintenance of the cover. Other monitoring costs, such as groundwater and surface water monitoring would also be included. Operation and maintenance costs are estimated to be \$31,000 per year.

Summary – Alternative 3

Alternative 3 does not significantly provide for greater protection of the public and environment than Alternative 2 and exhibits greater short-term and long-term impacts to the ecological environment. Therefore, this alternative is not considered the most cost-effective accelerated action. Alternative 3 increases the risk of worker injury over that of Alternative 2 with the additional construction materials and operation of heavy construction equipment. Alternative 3 was not retained.

6.2.4 Alternative 4 - Removal with Offsite Disposal

Alternative 4, Removal with offsite disposal is presented in 6.1.3 and generally includes the removal of radiologically contaminated surface soil (completed in August 2004), the removal and disposal of all OLF wastes and contaminated soil, and grading of the area to a stable configuration.

Effectiveness

Effectiveness considers whether the alternative provides protection of human health and the environment, and achieves the remedial objectives.

Protectiveness

Alternative 4 would provide the highest level of long-term effectiveness, because all waste materials would be removed permanently from the OLF area. Alternative 4 would rely upon proven techniques for waste excavation, classification, and disposal.

Under Alternative 4, material removed from the OLF will require characterization for disposal in an appropriately licensed facility. However, prior to disposal, the waste may need to be treated to meet Land Disposal Restriction (LDR) standards or other standards required by the disposal facility. The types of treatment required would be identified during design and implementation. Alternative 4 would comply with ARARs, although compliance with waste management requirements for treatment and disposal may prove difficult or impractical for some wastes. This could lead to the need for waste storage at RFETS pending final waste disposition.

Alternative 4 will have a high short-term effectiveness due to the exposure of the workers to waste during implementation and the potential for an off-site release due to transportation accidents. This alternative will also temporarily damage jurisdictional and candidate wetlands within the boundary of the OLF. Wetlands and PMJM habitat mitigation may be required.

Achieve Remedial Objectives

Alternative 4 will meet all of the remedial action objectives because all the waste materials would be removed from the site for disposal in off-site licensed facilities. Construction activities will damage jurisdictional wetlands and a portion of the PMJM protection area within the boundary of the OLF. However, these habitats will likely recover.

Implementability

Implementability addresses the technical and administrative feasibility of implementing an alternative using the required equipment, services, and materials.

Technical Feasibility

Alternative 4 is technically feasible using only proven controls that have been successfully implemented at other sites with similar conditions. All controls within the alternative could be executed using readily available machinery including earthmoving equipment, haul trucks, and other conventional construction equipment. However, the handling, segregation, sampling, treatment, and disposal processes for this alternative are technically challenging and will require additional operational and safety procedures for successful implementation.

Off-site disposal included in the alternative would be technically feasible, because disposal facilities have been identified by RFETS and have been used for waste disposal in the past. However, this alternative may require waste storage pending disposition of some wastes at off-site disposal facilities.

Alternative 4 is the only alternative that does not require post action maintenance or monitoring by RFETS or the USFWS. The commercial disposal facility chosen would be responsible for all monitoring and maintenance of the disposed waste.

Availability

Required goods and services for implementation of the alternative are reasonably available, although treatment may be costly and impractical for some wastes. It is anticipated that the contractors, labor, equipment, and most of the materials would come from the Denver/Front Range area, which surrounds the site.

Off-site disposal facilities are established for hazardous and radioactive waste generated at RFETS. Solid waste would be disposed of in a nearby State-permitted solid waste facility. Off-site RCRA hazardous waste and low-level hazardous waste would be disposed at appropriate facilities (for example, NTS and/or Envirocare of Utah).

Administrative Feasibility

The implementation of Alternative 4 does not require permits or easements, and does not impact adjoining property. It will not inhibit the ability to impose institutional controls. Existing site management and access controls would be maintained until a comprehensive final plan is implemented in the future. The alternative is generally consistent with the aesthetic qualities of the facility end use as a wildlife refuge.

This alternative will temporarily damage jurisdictional wetlands and a portion of the PMJM protection area. Therefore, formal consultation with the USFWS would be required for potential PMJM impacts.

Alternative 4 is administratively feasible; however, is the most complex alternative because all waste will be removed from the OLF area and disposed of off site. Typical safety concerns with the transportation of radioactive and nonradioactive contamination from the site would be expected. However, transportation of similar waste from RFETS is routine and is unlikely to cause public concern. Appropriate safety measures would be implemented to protect the public during waste transportation.

Cost

Evaluation of costs should consider the capital costs to engineer, procure and construct the required equipment and facilities, and the operating and maintenance costs associated with the alternative.

Capital Cost

The capital cost to implement Alternative 4 is between \$100,000,000 and \$260,000,000 depending on the actual composition of the waste materials and the need for treatment prior to disposal.

Operation & Maintenance Cost

No operation and maintenance costs would be incurred with this alternative.

Summary - Alternative 4

Alternative 4 was not retained for further consideration because the high costs of removal, treatment and disposal make this alternative impractical. Alternative 2 will meet the remedial action objectives at a lower cost.

6.2.5 Summary

This section discusses the results of the comparative evaluation for each remedial alternative for the OLF at RFETS. The results are also summarized in Table 6-1.

Alternative 1 would not prevent direct contact with the OLF debris or control the current erosional processes. However, it could be easily implemented and would be cost effective, relying wholly on active controls to limit risks. This alternative was not selected as the proposed accelerated action for the OLF.

Alternative 2 will prevent direct contact with the OLF debris and control erosional processes, with a short disruption of the PMJM habitat. The alternative is implementable. This alternative includes post-accelerated action institutional controls to maintain remedy effectiveness, but the controls are not difficult to implement. The primary drawback to Alternative 2 is that it exposes some waste during the slope stabilization process, and creates potential worker safety and environmental issues. This alternative was selected as the proposed accelerated action for the OLF because it is the most cost-effective and it implements the presumptive remedy.

Alternative 3 would prevent direct contact with the OLF debris and control erosional processes, but with permanent disruption of the PMJM habitat and additional wetland removal. The alternative is implementable; however, construction is more difficult and requires more materials and use of heavy construction equipment. This alternative includes post-accelerated action institutional controls to maintain remedy effectiveness, but the controls are not difficult to implement. Alternative 3, like Alternative 2, also exposes some waste during the slope stabilization process.

Alternative 3 does not significantly provide for greater protection of the public and environment than Alternative 2 and exhibits greater short- and long-term impacts to the ecological environment. Therefore, it is not considered the most cost-effective accelerated action. Alternative 3 would increase the risk of worker injury over that of Alternative 2 with the additional construction materials and heavy construction equipment. Alternative 3 was not selected as the proposed accelerated action for the OLF.

Alternative 4 provides the highest level of protection for public health and the environment with a short disruption of the PMJM habitat. However, it presents the highest risk to workers implementing the action. It is also extremely expensive due to the high cost of off-site disposal in licensed facilities. Because of the high cost and long construction duration, this alternative was not selected as the proposed accelerated action for the OLF.

6-20

7.0 PROPOSED REMEDIAL ACTION PLAN

The remedial action plan for the OLF will consist of the following major activities to meet the RAOs:

- Removal of surface soil "hot spots" (removal completed, see Appendix C);
- Limited grading of landfill to slope of 18 percent;
- Placement of a 2-ft-thick soil cover over the entire fill area;
- Engineering controls;
- Site monitoring (groundwater and surface water); and
- Institutional controls.

The objectives of this action are principally met through the removal of surface soils that are contaminated above the soil action level and installation of the landfill soil cover. However, additional continuing actions are required to maintain and assess the protectiveness and effectiveness of the cover. Further discussion of the actions in relation to attaining to the extent practicable, ARARs is contained in Section 8.0. Further discussion of Long-Term Stewardship activities is contained in Section 10.0.

These actions will be taken until final remedy requirements are selected and incorporated (along with post-closure requirements for remedial actions conducted at other IHSSs at Rocky Flats) in post-closure regulatory documents, which may include the final CAD/ROD for Rocky Flats or a post-closure RFCA-type agreement.

7.1 Removal of Surface Soil Hot Spots

Surface soil with concentrations above the WRW and Ecological Receptor action levels were removed as shown on Figure 4-2. A description of the removal and confirmation sampling results are presented in Appendix C.

7.2 Area Grading & Soil Cover

The waste fill area will be graded to generally an approximately 18-percent (5.5:1) slope using a cut-and-fill approach that will be as balanced as possible (See Figures 6-1 and 6-2). Standard earth-moving equipment, such as dozers, hoes or scrapers, will be used to cut the areas where the slope exceeds the desired 18 percent and to fill the areas where the slope is less than the desired 18 percent slope. It is estimated that approximately 55,000 cubic yards of waste fill material will be moved during the process and 105,000 cy of fill will be required to reach the 18-percent grade before placing the 2-ft cover.. The grading plan will be optimized in the design to add stormwater drainage swales, and run-on and runoff controls, as well as balance the overall cut/fill earthmoving yardages and include anticipated groundwater elevations and bedrock topography.

Control measures will be implemented during the grading process to control the spread and release of waste materials in the OLF. The control measures will include establishment of work zones, decontamination procedures, dust suppression methods, traction mats, visual inspections, and radiological surveys. Work will be suspended when environmental conditions could greatly increase the possibility of the spread of contaminated materials. Monitoring will be performed, as necessary, to verify that there has been no release of contaminated materials. Generally, the work will be conducted as if at a radiologically contaminated site using proper personal protective equipment (PPE), respiratory protection, and worker monitoring.

After grading of the landfill surface is complete, a soil cover will be placed over the landfill to a minimum thickness of 2 ft. Approximately 65,000 cubic yards of local or onsite soil will be used to construct the cover. The soil cover will be sufficiently compacted to provide a stable cover system to promote surface water runoff, reduce surface water ponding, increase overall slope stability, and provide a suitable soil surface for revegetation.

Revegetation of the soil cover with native species will reduce infiltration and control erosion. This approach is in keeping with the current strategy to restore RFETS with the native prairie grasslands as closely as possible. The seeding will be conducted, along with using erosion control matting or mulch, to prevent erosion of the cover while allowing the vegetation to establish a strong stand.

The following plant properties will ensure healthy, productive, and long-term vegetative growth on the landfill cover:

- Locally-adapted, noninvasive or native species able to withstand Front Range drought and temperature extremes will be used as vegetative cover.
- Long-term fertilization and nutrient supplements are not planned at this time; therefore, it is critical that the vegetation be able to survive under existing soil conditions. Native grasses and forbs will thrive with little maintenance. Soil amendments may be provided to supplement borrow material to establish initial vegetation on the cover.
- Both cool and warm season species will be planted to provide transpiration throughout as much of the year as possible. Locally-adapted species of grasses and forbs normally transpire all available water in semiarid climates, such as that at RFETS.
- A strong stand of vegetation will limit cover erosion from both wind and water.

A draft seed mix will be developed during the design in consultation with the RFCA Parties, the RFETS Ecology Group, and other interested parties.

7.3 Engineering Controls

Engineering controls may be used to provide a physical barrier to protect the public and wildlife refuge workers from potential risks at the site. The engineering controls may include

signage to limit public access. Signs to inform the public of limited access would be posted at 200-ft intervals.

7.4 Site Monitoring

Site monitoring will include a program to ensure that current conditions at the site do not change in an adverse manner. Surface water and groundwater monitoring will be instituted to identify impacts after the action has been implemented. An annual walkdown of the area will be conducted to identify areas of erosion of the soil cover for repair. A ground survey will also be completed to monitor slope stability. More details regarding site monitoring is presented in Section 10.0. Monitoring locations will be determined during the design of the accelerated action.

7.5 Institutional Controls

General and specific post-accelerated action institutional controls for RFETS as a whole are currently being evaluated by DOE and the regulatory agencies, and in consultation with the USFWS and the community.

The controls that will be implemented at the OLF for this proposed action are as follows:

- Current Site-wide security and access controls will be maintained until completion of the RFETS Closure Project, currently scheduled for December 2006, but will be replaced by equivalent controls for the OLF and other specific areas for which security and access controls are required.
- 2. In accordance with the Rocky Flats Wildlife Refuge Act of 2001 (Pub.L. 107-107, Sec. 3171-3182 [December 28, 2001]), DOE will retain jurisdiction over the engineered controls associated with the proposed action.
- 3. Drilling and pumping of groundwater wells for uses other than the remedy.
- 4. Use and excavation of the cover and the area in the immediate vicinity of the cover will be prohibited
- 5. Drilling on and in the immediate vicinity of the cover will be prohibited.
- 6. Disruption of surface water sampling stations until such stations are no longer needed will be prohibited.
- 7. To avoid adverse impacts, roads and trails will not be allowed on the cover or the immediate vicinity of the cover. Signs may be erected that indicate vehicles are prohibited from specific areas and that direct vehicle traffic appropriately. A determination will be made during project construction as to whether signs or barriers will be used as the preferred means of restricting access.



8. Upon construction completion, fencing at specific locations on or around the cover, will also be considered to limit the potential for damage or tampering with the Site. Signs and markers may be used as controls to delineate the landfill boundary; outline digging, fishing, swimming, groundwater, and surface use restrictions; and/or describe access restrictions to the landfill cover and monitoring locations for the cover.

Final institutional and physical controls for the accelerated action will also be documented in the Closeout Report. Inspection of these institutional controls will be performed quarterly to determine their continuing effectiveness. Results of these inspections will be reported annually.

7.6 Worker Health and Safety

All work under this proposed action will be controlled using the Site Integrated Safety Management System (ISMS) and the Integrated Work Control Program (IWCP). A project-specific HASP will be developed to address the safety and health hazards of project execution and specify the requirements and procedures for employee protection. The Occupational Safety and Health Administration (OSHA) construction standard for Hazardous Waste Operations and Emergency Response, 29 Code of Federal Regulations (CFR) 1926.65, will be used as the basis for the HASP. In addition, DOE Order 5480.9A, Construction Project Safety and Health Management, applies to this project. This Order requires preparation of an Activity Hazard Analyses (AHA) for each task, which includes identifying the task, hazards associated with the task, and controls necessary to eliminate or mitigate the hazards. The AHAs will be included in the HASP.

Data and controls will be continually evaluated. If field conditions vary from the planned approach (for example, when unanticipated hazards are encountered, such as contaminated debris and airborne contamination), an AHA will be prepared for the new conditions, and work will proceed according to the appropriate control measures.

8.0 APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS

As required by Part 4 of RFCA, the proposed action will be performed to the extent practicable in compliance with applicable or relevant and appropriate requirements (ARARs) under CERCLA. ARARs have been identified for the proposed action consistent with the NCP, the preambles to the proposed and final NCP, and CERCLA Compliance with Other Laws Manuals Part I and Part II (EPA 1988, 1989).

The ARARs are presented in Appendix A. This section provides additional detail for the ARARs related to the cover for the OLF, post-closure care, air, surface water, wetlands, wildlife and mineral resources.

As discussed in Section 4.0, the OLF has not impacted the environmental media outside the landfill boundary (surface water and groundwater) since its closure 36 years ago in 1968. The actions outlined in this IM/IRA will be designed to increase the protectiveness of the OLF. Specifically, the soil cover will be designed and built to perform the following functions:

- Prevent direct contact with the fill materials and commingled soil;
- Reduce and control the erosion of surface soil;
- Provide a separation layer between surface water runoff and the fill materials and contaminated soils;
- Reduce the infiltration of groundwater through the fill material by providing a continuous soil cover and positive drainage of stormwater flow off the cover;
- Provide for minimal impact to PMJM habitats; and
- Maintain or enhance stability characteristics of the OLF to minimize adverse impacts from potential future landsliding.

8.1 Landfill Cover Requirements

The proposed containment accelerated action for the OLF includes a cover that will be designed and constructed to meet any Relevant and Appropriate requirements (ARARs) of the cover performance standards in 40 CFR Part 265.310(a). This section focuses only on those 265.310(a) requirements that have been determined to be both relevant and appropriate to the OLF.

Specifically, the cover performance standards determined to be relevant and appropriate are 40 CFR 265.310(a)(2) and (a)(4), which require DOE to close the landfill with a final cover designed and constructed to:

• Function with minimum maintenance; and

• Accommodate settling and subsidence so that the cover's integrity is maintained.

To demonstrate compliance with these cover performance standards, the following sections discuss each of these requirements.

Ancillary activities performed concurrently with construction of a stable soil cover will include PMJM habitat protection, wetlands protection, surface water management, and site security. Compensatory mitigation for unavoidable impacts to wetlands will be provided in accordance with ARARs. Grading the surface of the landfill will control surface water runoff. Surface water will drain south and into Woman Creek.

Site security will be maintained during and after construction activities. Signs will be posted warning of potential danger at the landfill.

8.1.1 Function With Minimum Maintenance

Based on the evaluation of all the environmental and geotechnical data, the current soil cover and contour of the placed waste and commingled soil at the OLF do not present a significant hazard after over 36 years in this configuration. Implementation of the proposed accelerated action will further minimize landfill maintenance in the following areas:

- The regraded surface and 2-ft-thick cover will reduce cover maintenance by providing several ft of separation between the waste and surface of the landfill (prevent direct contact with the waste), by eliminating the erosion and sloughing of soils that have resulted from poor waste placement practices, and providing a more geotechnically stable landfill.
- Stormwater runon controls will divert surface water away from the OLF to reduce stormwater erosion.
- Stormwater runoff will be controlled by the grading/contouring of the landfill surface to eliminate ponding water and promote positive drainage from the landfill.
- The soil cover of the landfill will be vegetated to reduce surface erosion. This will also increase landfill stability by reducing groundwater levels through plant evapotranspiration.

8.1.2 Accommodate Settling and Subsidence to Maintain Cover's Integrity

Because the OLF has been inactive for 36 years, settling and subsidence are considered complete. However, to prevent any further movement, the following observations are noted:

- The waste is currently commingled with soil (over 50 percent), which reduces the extent of settling and subsidence.
- The proposed accelerated action will reposition and recompact some of the waste and commingled soil to further reduce settling and subsidence.

- Appropriate method compaction specifications will be developed to provide the appropriate levels of compaction to reduce settling and subsidence.
- Furthermore, a soil cover is very flexible with regard to settling and subsidence and also extremely easy to repair should the need arise.

8.2 Air

The proposed action has the potential to generate fugitive particulate emissions, but very little potential for hazardous air pollutant emissions. Subpart H of 40 CFR Part 61 contains the requirements for monitoring and reporting activities within DOE facilities that have the potential to emit radionuclides other than radon. Potential emissions from the proposed action that may affect 40 CFR 61 compliance have not been identified; however, normal perimeter National Emission Standards for Hazardous Air Pollutants (NESHAPs) compliance air monitoring will be conducted during the cover installation.

Colorado Regulation No. 1 (5 CCR 1001-3) governs opacity and particulate emissions. Section II of Regulation No. 1 addresses opacity and prohibits stack-emissions from fuel-fired equipment exceeding 20 percent opacity. Section III addresses the control of particulate emissions. Fugitive particulate emissions will be generated from construction and transportation activities. During construction activities, dust minimization techniques, such as water sprays, will be used to minimize suspension of particulates. In addition, construction activities will not be conducted during periods of high wind. The substantive requirements of Regulation No. 1 will be incorporated into a Dust Control Plan, which will define the level of particulate control for the project.

Colorado Regulation No. 3 (5 CCR 1001-5) provides CDPHE with the authority to inventory emissions, and Part A describes Air Pollutant Emission Notice (APEN) requirements. Air quality management subject matter experts will evaluate the project emissions and, if applicable, an APEN will be prepared to facilitate CDPHE's inventory process.

The final surface of the landfill cover will appropriately reduce the potential post-accelerated action wind erosion of soil and subsequent particulate emissions. Significant air emissions are not anticipated after the closure construction is complete.

8.3 Surface Water

The proposed action has the potential to impact surface water during construction. As described in the following paragraphs, impacts will be minimized by meeting the substantive requirements of the Clean Water Act and associated implementing regulations.

8.3.1 Stormwater

Given the expected conditions at the OLF site, no significant surface water impacts are anticipated as a result of stormwater events. However, because the total area of the project is greater than 1 acre and the location is outside the IA, which has an effective National Pollutant Discharge Elimination System (NPDES) Permit for Storm Water, the proposed action would require an NPDES Storm Water Permit for Construction Activities, except for

the fact that it is a CERCLA action, Paragraphs 16 and 17 of RFCA, establish the requirements under which a CERCLA permit waiver applies. For any action that would require a permit except for CERCLA, Paragraph 17 requires that certain information be included in the submittal.

Permit Required

Because the landfill cover construction project is greater than 1 acres in size and lies outside of the Site's IA, an NPDES General Storm Water Permit for Construction Activities would be required. The permit is found at 40 CFR Part 122, and is obtained by filing a Notification of Intent (NOI) with EPA. This IM/IRA serves as the NOI for the OLF.

Requirements to Obtain a Permit

Because the stormwater permit for construction activities is a general permit, it has been through public comment and promulgated by EPA. Obtaining the permit was done through the NOI (that is, a letter submittal to the agency containing basic information about the project). The permit requires installation of best management practices (BMPs) and structural stormwater controls, such as silt fences, to protect downstream waters from potential surface water contaminants (for example, sediment-laden runoff). These requirements will be part of the cover design.

How Stormwater Control Measures Meet the Requirements

The total area of disturbed soil is approximately 22 acres, including the area of the landfill to be resurfaced (20 acres) and miscellaneous construction activities (2 acres). Surface water control measures will be used to minimize surface water contact with potentially contaminated soil or groundwater and minimize erosional effects during the construction activities. Precipitation falling on areas where construction is in progress will be diverted to existing surface water drainage ditches. Other shallow ditches will be temporarily constructed as needed to prevent sediment-laden stormwater from flowing directly into Woman Creek. Newly-constructed soil surfaces will be stabilized using soil terracing, revegetation hydromulch, straw-mulch, silt fencing, straw waddles, and other stormwater BMPs to minimize soil erosion, sediment transport, and surface water quality degradation until the required vegetation is established. The use of straw-mulch, straw waddles, adequately spaced silt fences, and other appropriate measures minimizes soil loss and allows the vegetation to become established.

8.3.2 Remediation Wastewater

Remediation wastewater generated during construction activities is not expected; however, if produced, it will be managed consistent with provisions of the RFCA Implementation Guidance Document (IGD) (DOE et al. 1999). Remediation wastewater, if produced, will be collected, characterized, and treated on or off site if required, directly discharged in accordance with requirements of the Site's Incidental Waters Program (K-H 2003a).

8.4 Wetlands

As described in Section 3.8, the U.S. Army Corps of Engineers has designated wetlands within the construction area. DOE will mitigate the permanent loss of wetlands resulting

from the remediation construction in accordance with a Wetland Mitigation Plan to be prepared as part of the remedial action design (see Appendix E).

8.5 Wildlife

Construction activities will remove jurisdictional wetlands and a portion of the PMJM protection area within the boundary of the OLF. Formal consultation with USFWS will be required. Wetland and PMJM habitat mitigation may be required. However, disruption of the PMJM habitat is temporary. Mitigation plans will be developed during design of the action, as required.

Construction activities may impact migratory birds protected by the Migratory Bird Treaty Act. Due to the variations in potential impacts depending upon the season and nesting schedules for migratory birds, the substantive requirements of these federal statutes will be evaluated by the Site Ecology Group prior to conducting activities associated with the proposed action. The substantive requirements identified during the evaluation will be implemented throughout the construction process.

9.0 ENVIRONMENTAL IMPACTS

Paragraph 95 of RFCA mandates incorporation of National Environmental Policy Act (NEPA) values into RFETS decision documents. This section of the IM/IRA satisfies the RFCA requirement for a "NEPA equivalency" assessment of environmental consequences by addressing the environmental consequences of the proposed accelerated action.

The remediation impact analysis relies heavily on conclusions reached in the Cumulative Impact Document (CID) (DOE 1997) and the 2000 CID Update Report (DOE 2001), both of which focus on cumulative impacts resulting from on-site closure activities. In general, the proposed action will have very few adverse short-term impacts on a variety of resource areas, including air quality, water quality, traffic congestion, and ecological resources. In some instances, the impacts could be intense for a short period of time. However, the impacts will not notably affect human health and safety, or the environment, and they will be temporary and controlled through mitigation actions (for example, dust will be controlled with water sprays during placement of the cover).

The proposed action will have both positive and adverse effects, each identified in this section. Certain mitigation measures are required by law and are also identified for each resource area.

9.1 Impacts to Air Quality

The purpose of this section is to assess the potential impacts to air quality associated with implementation of the proposed accelerated action (regraded surface with soil cover), including fugitive dust emissions and methane emissions.

9.1.1 Potential Fugitive Dust Emissions

The primary pollutant generated as a result of the proposed action will be fugitive dust, which includes total suspended particulates (TSP) and particulate matter 10 micron (PM₁₀), and particulate matter 2.5 microns (PM_{2.5}) in size. Dust emissions from the regrading and cover construction activities will be controlled with practical, economically reasonable, and technologically feasible work practices, as required by the CAQCC Regulation No. 1. Specifically, on-site dust will be controlled through dust minimization techniques, such as the use of water sprays to minimize suspension of particulates, and terminating earthmoving operations during periods of high wind. In addition, PM10 will be monitored consistent with the Site IMP (RFETS 2000). Particulate emissions will be short-term and controllable, and emissions are not expected to be above enforceable National Ambient Air Quality Standards (NAAQSs) at the RFETS perimeter. Therefore, potential impacts to workers and the public from proposed action will not be significant.

9.1.2 Potential Equipment Emissions

The regrading and cover construction activities will also include operation of vehicles, heavy machinery, and other equipment that generate other criteria pollutants. Estimated concentrations of other criteria and Hazardous Air Pollutants provided in the CID (DOE 1997)

were well below the most restrictive occupational exposure limit, with the exceptions of sulfur dioxide, nitrogen dioxide, and carbon monoxide, which approached 50 percent of the most restrictive occupational exposure limit. The CID (DOE 1997) identified the primary sources of these pollutants as diesel-powered emergency generators used to supply backup power at RFETS. According to the 2000 CID Update Report (DOE 2001), maximum daily emissions will remain about the same as forecast in the CID (DOE 1997). Equipment emissions from construction activities at the OLF are expected to be substantially less than the CID (DOE 1997) and 2000 CID Update Report (DOE 2001) estimates; therefore, impacts to workers and the public are not a concern.

9.2 Impacts to Surface Water

Construction activities at the OLF will result in surface disturbance from the clearing of vegetation, excavation and salvage of topsoil material, blading and leveling of the land, the potential for accidental uncovering of contaminated media, and the construction of the soil cover. Potential impacts to surface water during the construction phase include increased erosion, and subsequent sediment loading to drainage ditches and Woman Creek during storm events. The absence of vegetative cover results in increased potential for both sheet and channelized runoff, as well as wind and water erosion, resulting in increased sedimentation of ditches and Woman Creek.

The soil cover construction will require soil obtained from off-site commercial operations or on-site sources. Excavation of these borrow materials has impacts similar to those identified above. Off-site facilities address these issues through permits issued to the facility.

The construction activities are expected to result in limited physical contact with contaminated soils or waste materials. In the event equipment and personnel come in contact with potentially contaminated materials during construction, decontamination will be performed at the RFETS main decontamination facility or a temporary decontamination facility at the OLF to reduce potential impacts to surface water.

Long-term impacts will remain minimal because the regrading, soil cover, and revegetation will minimize infiltration of precipitation and subsequent contact with contaminants. The proposed accelerated action will also incorporate surface drainage features to control runon/runoff and provide surface erosion control. The proposed action will result in a decrease in the risk of contaminants reaching surface water by:

- Preventing direct contact of precipitation with the waste materials and commingled soil;
- · Providing Stormwater runon and runoff controls; and
- Preventing soil erosion by providing temporary, engineered erosion controls and cover revegetation.

Precipitation falling within the boundary of the landfill will be drained from the cover and diverted away from the landfill. Surface water drainage from areas outside the OLF boundary

will be prevented from flowing onto the landfill and diverted around the boundary. Using appropriate surface-reclamation measures, adequate vegetative cover will be established on the final surface of the landfill. The establishment of vegetative cover on the new slopes and contours of the landfill, and the surrounding disturbed surfaces, will greatly reduce erosional hazards to levels similar to surrounding areas.

Post-accelerated action monitoring activities will include inspections of the landfill surface and associated drainage ditch conditions. Observations of the vegetative cover and evidence of soil erosion and loss will be included in the routine inspection and maintenance activities. Further erosion control measures, regrading, and revegetation will be implemented if maintenance inspections indicate the landfill surface erosion controls are not as effective as planned.

The SID in the area of the OLF will be eliminated by implementing the proposed action. The SID will be effectively replaced with installation of the soil cover. Removal of the SID will enhance the overall stability of the landfill by eliminating the existing ponding of stormwater on the OLF.

9.3 Impacts to Groundwater

Groundwater quality in the area of the OLF is not significantly impacted. The intended purpose of the cover is to prevent contact with potentially contaminated landfill material. The regraded cover will also reduce surface water from percolating through the landfill to groundwater. These measures will prevent localized contamination of groundwater. The regraded soil cover will provide an overall positive impact to groundwater and will continue to protect groundwater quality at the site. No significant negative impact to groundwater quality is expected from implementation of the accelerated action.

9.4 Impacts to Wildlife and Vegetation

The OLF construction activities will have varying impacts on ecological resources within the project area. Impacts to ecological resources are unavoidable; however, adverse impacts will be minimized through mitigative measures. The Proposed Action will principally affect wetlands, migratory bird habitat, and habitat for the PMJM (*Zapus hudsonius preble*), a federally-listed threatened species under the Endangered Species Act. Impacts to the PMJM and wetlands may require mitigation (that is, a replacement of habitat of equal value either on or offsite). Habitat for native animals will change slightly, as the hillside is regraded and revegetated during construction of the proposed accelerated action. However, the changes will improve the quality of the vegetation by replacing exotic species with native species. The changes will adversely affect some species for a short time, but will likely have a long-term benefit for most endemic species.

Because the PMJM is a federally-listed threatened species, its habitat is a primary concern at RFETS. Several acres of PMJM habitat are located on RFETS. The PMJM is found in the riparian woodland/shrubland habitat along Woman Creek, and designated PMJM habitat extends into the southern portion of the OLF area as shown on Figure 3-4. Some designated PMJM habitat will be lost permanently within the project area because of soil cover (landfill

cap) constraints. However, some of PMJM habitat will be only temporarily impacted by the project. Both temporary and permanent impacts will be mitigated through consultation with the USFWS.

Other animal species will lose existing habitat when the construction of accelerated action is completed. The regraded soil cover may limit the types of animals that eventually occupy the area. The changes, however, will benefit yet other species. Many endemic species are adapted to prairie environments and would readily inhabit the reconfigured OLF.

Migratory birds are protected under the Migratory Bird Treaty Act. Both the birds and their nests are protected under this law. Songbirds occasionally nest in the trees and shrubs or on the ground in the OLF area. Active nests will be protected; inactive nests will be removed prior to construction activities, through the use of special permits from the USFWS. While long-term habitat changes that result from the proposed action will adversely affect some bird species (for example, loss of a nesting site for owls), other species (for example, grassland species) will benefit from the changes.

Much of the OLF project area is currently dominated by noxious weed species, such as diffuse knapweed and scotch thistle. These weeds have invaded the disturbed ground within the project area over the past decade. Additionally, non-native species of grasses, such as smooth brome and intermediate wheatgrass, were planted along the SID after it was constructed. These non-native species will be replaced with native species that provide better wildlife forage and habitat, and increase the natural resource values of the area.

There are several small wetland areas within the boundary of the OLF project area that will be destroyed. The impacted areas are subdivided as follows:

- SID Wetlands: The entire SID wetland area is 3.06 acres; the portion of the SID that will be affected by the proposed action is 0.34 acres.
- Woman Creek Wetlands: The proposed accelerated action is not expected to impact the wetlands in Woman Creek.
- Candidate Wetlands: Eight small isolated areas identified as potential wetlands, totaling approximately 0.91 acres, are located north of the SID. Designation of these areas as "jurisdictional" is currently in discussion.

A conceptual approach to mitigating wetland damage at the OLF is being developed. The approach to offset wetland losses is based on a worst-case scenario, wherein all wetlands on the hillsides and along Woman Creek are impacted. A Wetlands Mitigation Plan will be prepared that describes the actions that will be taken to replace wetlands that are destroyed. Both in-situ wetland creation/restoration and the use of wetland bank credits have been proposed for mitigation of wetland impacts. The use of either technique or a combination of the techniques is subject to review and approval by the USFWS. The mitigative measures are therefore considered sufficient to offset losses and other adverse impacts to wetlands.

The OLF project may temporarily affect water quality from eroded soil during construction. Erosion controls will be used to minimize water quality effects. Surface water flow volumes may change due to the design of the new landfill cover. Such changes would be minimal and would occur sporadically (for example, after heavy rains). The minor potential changes in surface water flow volumes will not change or affect lower Platte River species that depend on instream flows.

Soil materials will be obtained from off-site commercial operations for fill and cover operations, and the excavation of borrow materials will impact wildlife and vegetation at those locations. Commercial facilities must comply with the Endangered Species Act, and threatened and endangered species are therefore protected. The impact to other species will vary but will depend on the facility and extent of the operations. However, these indirect impacts are considered in operational permits issued for the facilities by state and local county governments.

9.5 Impacts to Nearby Populations

In accordance with Executive Order 12898, the potential impact of the proposed action on minority and low-income populations is considered. The proposed action will occur on site away from inhabited areas, and will not lead to off-site indirect effects on nearby populations. Disproportionately high and adverse human health or environmental effects will not be imposed on these populations. The proposed action will provide short-term employment for a limited number of people, and socioeconomic effects of the action will be minimal.

9.6 Impacts to Transportation

The proposed accelerated action will only slightly impact both on-site and off-site transportation systems. Increased on-site truck traffic will be an inconvenience; however, safety risks will be low, and impacts will be mitigated by very low and closely observed speed limits. In comparison analyses in the CID (DOE 1997; 2001), off-site traffic impacts will not increase substantially.

9.7 Impacts to Cultural and Historic Resources

RFETS was placed on the National Register of Historic Places as a Historic District (5JF1227) on May 19, 1997. Historic District designation mandates compliance with the Historic Preservation Act of 1966, and the Programmatic Agreement among DOE, the Colorado State Historic Preservation Officer, and the Advisory Council on Historic Preservation Regarding Historic Properties at RFETS. Although the action will be conducted within the Historic District boundaries, no impact is expected to occur to protected structures.

9.8 Impacts to Visual Resources

During installation of the cover, bulldozers and other equipment may be visible from off-site locations. Dust generated during earthmoving operations may be temporarily visible, but will dissipate before leaving the Site as a visible cloud or plume of dust. Control measures, such as watering, will be used if needed to control dust.

9.9 Noise Impacts

Noise levels may be elevated during construction of the accelerated action. Noise levels will not exceed those commonly encountered at a highway construction site. Appropriate hearing protection will be supplied to project personnel as identified in the project-specific HASP.

9.10 Cumulative Impacts

The proposed action supports the overall mission to clean up RFETS and make it safe for future uses. The cumulative effects of this broad, Sitewide effort are presented in the CID (DOE 1997) and 2000 CID Update Report (DOE 2001), which describe the short- and long-term effects from the overall cleanup mission.

The primary focus of the CID (DOE 1997) is cumulative impacts resulting from on-site activities conducted during Site closure. Cumulative impacts result from the effects of Site closure activities and other actions taken during the same time in the same geographic area, including off-site activities, regardless of what agency or person undertakes such other actions. The analysis contained in the 2000 CID Update Report (DQE 2001) included updated on-site and off-site transportation activities, as well as several new off-site activities, although the future non-DOE projects are relatively uncertain. Increased traffic congestion will be the most noticeable impact according to the 2000 CID Update Report (DOE 2001), resulting from increased RFETS traffic and other planned or proposed construction projects near RFETS. Air pollutants and noise will also have adverse impacts; however, the impacts are expected to be short-term in nature, with staggered project start and completion dates. Most people will perceive a positive, long-term visual and "quality of life" benefit, as RFETS infrastructure and equipment are removed, returning RFETS to a more natural appearance.

The cumulative impacts of the proposed action are expected to be similar to those analyzed in the CID (DOE 1997) and 2000 CID Update Report (DOE 2001). Over the short term, additional construction personnel will have an additive effect on the existing workload for Site operations, and there will be increased air emissions, visual impacts, noise, and traffic impacts resulting from construction activities. These short-term impacts will be minimal. Long-term impacts (that is, OLF cover construction activities in conjunction with other environmental restoration work and facility decommissioning activities) facilitate future use of the Site and fulfill the mandated cleanup objectives.

9.11 Irreversible & Irretrievable Commitment of Resources

The proposed action will result in a variety of permanent commitments of resources; however, it is not expected to result in a substantial loss of valuable resources. Most of the resources used for construction of the accelerated action will be permanently committed to the implementation. Irreversible and irretrievable resources are defined as resources that are either consumed, committed, or lost. At the OLF, irreversible and irretrievable resources include the following:

• Consumptive use of geological resources (for example, quarried rock, clay, sand, and gravel for road construction) will be required for construction activities. Supplies of

these materials will be provided either by on-site or off-site commercial borrow source. The proposed action requires a permanent commitment of fill, soil, and vegetative cover to construct the OLF cover. Adequate supplies are available without affecting local demand for these products.

- Fuel consumed by construction equipment and vehicles used for the construction of the OLF cover will not be recovered.
- Soil in the vicinity of the OLF will be disturbed by construction activities. Many impacts are temporary, pending completion of accelerated action activities and associated revegetation.
- The commitment of up to 25 acres of land as a landfill permanently commits and constrains the area to limited land-use options.
- Wetlands and associated natural resources will be reduced at the OLF. Long-term direct impacts to the floodplain resulting in changes of flood elevations will not occur.
- A long-term commitment of personnel and funds will be required to perform post-accelerated action inspection, maintenance, and monitoring activities.
- Commercial, industrial, and residential land uses are permanently prohibited within boundaries of the OLF due to construction of the cover and the network of monitoring wells.
- Incidental resources that are consumed, committed, or lost on a temporary and/or partial basis during construction include construction personnel and equipment, the construction water source, and construction materials for staging and access.
- Appropriate landfill surface revegetation will result in an acceptable appearance of the site, and the ecological succession of the closed landfill and adjacent land will be improved by surface revegetation. Vegetation and habitat will eventually become similar to surrounding areas.
- Monitoring and maintenance activities will be performed, as necessary, to ensure long-term protection of human health and the environment.

10.0 ADDITIONAL LONG-TERM STEWARDSHIP CONSIDERATIONS

The objective of this section is to identify additional accelerated action care (that is, long-term stewardship) requirements of the proposed accelerated action for the OLF. These requirements are necessary for the long-term effectiveness of this action and include the following components: information management, periodic review, and maintenance of a responsible controlling authority. Other requirements necessary for the short- and long-term effectiveness of the remedy are identified in this IM/IRA, including institutional controls, inspection and maintenance, and environmental monitoring. These requirements are specific to the accelerated actions described in this IM/IRA and are summarized in Table 10-1. Additionally, these requirements will ultimately be captured (along with post-closure care requirements from other accelerated actions at Rocky Flats) in post-closure regulatory documents, which may include the Final CAD/ROD for Rocky Flats or a post-closure RFCA-type agreement.

10.1 Information Management


A successful stewardship program is dependent on retaining the necessary records about the history and residual contamination of the site. Retained information should include the history of the site, environmental data, selected remedies, use of controls and their associated monitoring and maintenance records, and any other information judged necessary for succeeding generations to understand the nature and extent of the residual contamination. At a minimum, the following records will be retained, stored, and retrievable for this accelerated action:

- This IM/IRA and any future modifications;
- The final design for the regraded surface and soil cover and field change requests;
- The as-built drawings of the accelerated action;
- The monitoring and maintenance manual and subsequent revisions;
- Inspection records and logbooks;
- Maintenance records and logbooks;
- Annual performance assessment reports;
- Analytical Data;
- CERCLA 5-year review reports;
- Correspondence involving the regulatory agencies associated with modifications to the post-accelerated action care regime;

- The Memorandum of Understanding (MOU) between DOE and the U.S. Department of Interior (DOI) (identifying the controlling authority;
- The CAD/ROD; and
- The RFETS HRR and other relevant historical documentation.

This information will be maintained in the Administrative Record (AR) File. Currently, the AR File is maintained onsite. DOE is currently looking at options for retention of permanent records following Site closure.





Area	Action	Frequency of Action	Criteria	Possible Follow-on Action
Cover	Visual Inspection	Quarterly for five years	Differential Settling/Subsidence	Repair, as necessary.
			Erosion	Repair erosion areas with soil and rock, as necessary.
· · · · · · · · · · · · · · · · · · ·			Unwanted Vegetation	Remove deep rooting trees or employ weed control measures, as necessary.
 			Burrowing animals	Remove and repair damage, as necessary.
Perimeter Drainage Ditches	Visual Inspection	Quarterly for five years	Erosion	Repair erosion areas with soil, erosion blankets and reseeding, as necessary.
			Unwanted Vegetation	Remove deep rooting trees or employ weed control measures, as necessary.
Surface Water Sampling Stations	Sampling	Quarterly for five years	Analyze for VOCs and metals (including uranium). Effluent limitations are the surface water standards. (RFCA Attachment 5, Table 1)	If a surface water standard is exceeded, sampling will increase to monthly for three consecutive months. If exceedances continue, the RFCA Parties will consult to determine whether a change in the remedy is required; additional parameters need to be analyzed; or if a different sampling frequency is required.
Groundwater	Sampling	Quarterly for five years	Increasing trend in VOCs and metals (including uranium) in downgradient versus upgradient groundwater monitoring wells.	Statistically significant changes in downgradient versus upgradient groundwater quality will require consultation between the RFCA parties to determine if changes to the remedy are required.
Institutional and Physical Controls	Visual Inspection	Quarterly for five years	Security and Access Controls; and overall site conditions	Check signs, fences (if required), markers, and overall condition of the OLF site to determine continuing effectiveness of institutional and physical controls.

10.2 Periodic Assessments

Periodic assessments are performed to determine whether the selected remedies and stewardship controls continue to operate as designed, and ascertain whether new technologies might exist to eliminate remaining residual contamination in a safe and cost-effective manner. The CERCLA 5-year review process is required for all Superfund sites that leave residual contamination behind after closure, and establishes the minimum requirements for post-closure periodic assessments. The EPA Comprehensive Five-Year Review Guidance (2001) describes the format of the review and suggests mechanisms that can be implemented through the 5-year review process to ensure the protectiveness of the remedy.

DOE is responsible for conducting the five-year reviews. EPA then issues a finding of concurrence or nonconcurrence. The public has indicated an interest in performing reviews more frequently than the 5-year interval specified in CERCLA. DOE intends to work with its stakeholders to arrive at a review regimen that meets community needs.

The periodic assessment will include actions such as evaluating monitoring and maintenance records, verifying regulatory compliance, and determining whether land use assumptions are still valid. Specific topics for the periodic assessment for the OLF are likely to include cover performance, landfill stability, surface water quality, and groundwater quality; as well as the need to continue monitoring.

10.3 Controlling Authority

Long-term protection of human health and the environment necessitates that a controlling authority be established with responsibility for post-closure management. CERCLA mandates that DOE, as a responsible party, will retain responsibility for the contamination at RFETS resulting from its activities there, as well as responsibility for long-term maintenance of any remedies. The Rocky Flats National Wildlife Refuge Act of 2001 requires that, following certification by EPA, certain lands of the current Site will be transferred from the Secretary of Energy to the Secretary of the Interior. These lands will be under administrative jurisdiction of the USFWS. The Act also requires the Secretary of Energy to retain administrative jurisdiction over Site lands required to carry out response actions required for the cleanup and closure of the Site. The MOU currently being negotiated between DOE and DOI will outline this process, although it is unlikely the final boundaries of the land to be transferred will be determined until the final cleanup and closure plans are approved. However, the OLF will remain under the administrative jurisdiction of the Secretary of Energy.

10.4 Reporting Requirements

Annual reporting of data results, inspection results, repairs, and routine maintenance will be performed. These requirements may be combined into one report and/or with future Sitewide maintenance and monitoring reports.

11.0 IMPLEMENTATION SCHEDULE

It is anticipated that the remedial action will take just over 6 months to complete and be implemented during Fiscal Year 2005. The approximate schedule for work follows.

- Mobilization 20 days
- Pregrade Cut 30 days
- Pregrade Fill 70 days
- Fine Grading 20 days
- Soil Cover 40 days
- Vegetation and Erosion Control 10 days
- Demobilization 10 days

Most of these activities will be performed with some concurrent overlap. A detailed schedule for the construction will be developed during the design.

12.0 CLOSEOUT REPORT

Upon completion of the accelerated action at the OLF, a Closeout Report will be prepared in accordance with RFCA. The Closeout Report will document the work completed within the scope of this IM/IRA. The expected outline/content for the Closeout Report is as follows:

- Introduction;
- Remedial action description;
- Dates and duration of specific activities;
- Deviations from the decision document, if any;
- Final disposition of any wastes generated;
- Demarcation of wastes left in place (that is survey benchmarks and measurements);
- Demarcation of areas requiring access controls;
- A copy of the Vegetation Plan; and
- A copy of the Monitoring and Maintenance Plan.

Upon completion, the Closeout Report will be submitted for review and approval by CDPHE and EPA, and placed in the Administrative Record File.



13.0 ADMINISTRATIVE RECORD

The Administrative Record (AR) File for the proposed accelerated action to be conducted pursuant to this IM/IRA is available in the Rocky Flats Reading Room, located at:

Front Range Community College 3705 112th Avenue Westminster, Colorado 80030

(303) 469-4435.

The AR File contains the references listed in Section 15.0, References.

Upon approval of the Final IM/IRA, the AR will consist of the approval letter, Final IM/IRA (which will include a Comment Responsiveness Summary), references listed in Section 15.0, References, and any additional documents identified in the Final IM/IRA for inclusion in the AR.

An AR File for the implementation phase of the Final IM/IRA will be maintained as governed by Site AR policies and procedures, pursuant to the RFCA Community Relation Plan. The Final Closeout Report for the project will be included in the AR File. In addition, project-specific information, such as project correspondence, work control documents, and other information generated as a direct result of this project, will be filed in the Project Record. The Project Record files will be transferred to Site Records Management upon completion of the Final Closeout Report.

14.0 COMMENT RESPONSIVENESS SUMMARY

Responses to comments on this IM/IRA received during the formal public comment period, including comments from the regulatory agencies, will be documented in the Appendix F.

15.0 REFERENCES

Bryce, L.R. et al. 1988, Health Physics Manual of Good Practices for Uranium Facilities, EGG-2530; UC-41, U.S. Department of Energy, June.

CDPHE, 1992, Letter, G. Baughman, CDPHE, to M. Hestmark, EPA, dated March 27, 1992, subject: Final Phase I RFI/RI Workplan for 08 5 – Woman Creek: Resubmitted Portions, February 28.

CDPHE, 1999, Quality Assurance Project Plan for the Determination of Isotopic Uranium in Groundwater at RFETS using HR-ICP/MS (High Resolution Inductively Coupled Plasma Mass Spectroscopy), July.

DBS, 2001, Feasibility Study for the Solar Evaporation Ponds at RFETS, Rocky Flats Environmental Technology Site, Golden, Colorado, Daniel B. Stephens & Associates, Inc., December.

DOE, 1986a, Resource Conservation and Recovery Act, Part B – Operating Permit Application for USDOE Rocky Flats Plant, Hazardous and Radioactive Mixed Wastes, U.S. Department of Energy, Rocky Flats Area Office, Golden, Colorado, November.

DOE, 1986b, Comprehensive Environmental Assessment and Response Program, Phase I: Installation Assessment, Rocky Flats Plant, U.S. Department of Energy, April.

DOE, 1990, Memorandum from D. P. Simonson, DOE, to J. M. Kersh, EG&G Rocky Flats, Subject: Erosion of Soil Around Barrel Containing Radioactive Materials at the Old Landfill, June 7.

DOE, 1992, Final No Further Action Justification Document for Operable Unit 16, Low Priority Sites, Manual 2100-WP-OU16.01, 2.0, Rev. 1, Section 2.3.6 IHSS 196, Water Treatment Plant Backwash Pond, October.

DOE, 1997, Rocky Flats Environmental Technology Site Cumulative Impacts Document, Rocky Flats Environmental Technology Site, Golden, Colorado, June.

DOE, 1999, Vegetation Management Environmental Assessment, Rocky Flats Environmental Technology Site, Golden, Colorado, April.

DOE, 2001, Rocky Flats Environmental Technology Site Cumulative Impacts Document, 2000 Update, Rocky Flats Environmental Technology Site, Golden, Colorado, June.

DOE, 2003, Environmental Restoration RFCA Standard Operating Protocol for Routine Soil Remediation FY 03 Notification #IA-03-04, IHSS Group SW-2, Rocky Flats Environmental Technology Site, Golden, Colorado, February.

DOE, 2003, Quarterly Ground Water Monitoring Report for Third Quarter 2003, Rocky Flats Environmental Technology Site, Golden, Colorado, May.

DOE, CDPHE, and EPA, 1996, Final Rocky Flats Cleanup Agreement, as modified, U.S. Department of Energy, Colorado Department of Public Health and Environment, and U.S. Environmental Protection Agency, Rocky Flats Environmental Technology Site, Golden, Colorado, July.

DOE, CDPHE, and EPA 1997, RFCA Integrated Monitoring Plan and subsequent approved annual updates, Rocky Flats Environmental Technology Site, Golden, Colorado,.

DOE, CDPHE, and EPA, 1999, *Implementation Guidance Document*, Rocky Flats Cleanup Agreement, Appendix 3, U.S. Department of Energy, Colorado Department of Public Health and Environment, and U.S. Environmental Protection Agency, Rocky Flats Environmental Technology Site, Golden, Colorado, July.

DOE, 2004, Final Comprehensive Risk Assessment Work Plan and Methodology, Rocky Flats Environmental Technology Site, Golden, Colorado, September.

Earth Tech, Inc., 2004, Accelerated Action Design for the Original Landfill, Geotechnical Investigation Phase 3 Stability Analysis Technical Support Memorandum, Rocky Flats Environmental Technology Site, Golden, Colorado, November.

EG&G, 1990a, Letter from J. M. Kersh, EG&G Rocky Flats, to R.M. Nelson, DOE, June 22, 1990, subject: Erosion of Soil Around Barrel Containing Radioactive Materials at the Old Landfill.

EG&G, 1990b, Letter from J.M. Kersh, EG&G Rocky Flats, to R.M. Nelson, DOE, Subject: Update of Actions Concerning Erosion of Soil Around Barrel at the Old Landfill (SWMU 115), August 8.

EG&G, 1991, Letter, J.M. Kersh, EG&G Rocky Flats, to R.M. Nelson, DOE, Subject: EPA Concerns, Operable Unit No. 5 (OU 5), Old Landfill – JMK-0016-91, July 29.

EG&G, 1992a, Historical Release Report for Rocky Flats Plant, Manual No. 21100-TR-12501.01, Volume I – Text, Rocky Flats Environmental Technology Site, Golden, Colorado, June.

EG&G, 1992b, Final Phase I RFI/RI Work Plan, Revision 1, Woman Creek Priority Drainage (Operable Unit No. 5), Rocky Flats Plant, Golden, Colorado, February.

EG&G, 1993, Background Geochemical Characterization Report, Rocky Flats Plant, September.

EG&G, 1994, Technical Memorandum No. 15, Addendum to Final Phase I RFI/RI Work Plan, Amended Field Sampling Plan, Volume 2, Woman Creek Priority Drainage, Rocky Flats Plant, Golden, Colorado, May.

EG&G, 1995, Geologic Characterization Report for the Rocky Flats Environmental Technology Site, Volume I of the Sitewide Geoscience Characterization Study, Golden, Colorado, March.

EPA, 1988, CERCLA Compliance with Other Laws Manual: Interim Final, August.

EPA, 1989, CERCLA Compliance with Other Laws Manual: Part II, Clean Air Act and Other Environmental Statutes and State Requirements, EPA, August.

EPA, 1990, Letter from L.W. Johnson, EPA, to R.M. Nelson, DOE, Subject: Radioactive Contamination at SWMU 115 Old Landfill, July 10.

EPA, 1991a, Conducting Remedial Investigations/Feasibility Studies for CERCLA Municipal Landfill Sites, EPA/540/P-91/001, February.

EPA, 1991b, Letter, M. Hestmark, EPA, to F. Lockhart, DOE, dated March 21, 1991, subject: OU-5 – Old Landfill.

EPA, 1992a, Letter from M. Hestmark, EPA, to F. Lockhart, DOE, Subject: Technical Memorandum 1, Revisions to the Final Phase 1 RFI/RI Workplan for Operable Unit 5, February 19.

EPA, 1992b, Letter, M. Hestmark, EPA to F. Lockhart, DOE, dated June 19, 1992, subject: Schedules to implement approved RFI/RI Workplans for Operable Units 4, 5, 6, 9, and OU 2 Bedrock.

EPA, 1993, Guidance on Conducting Non-Time-Critical Removal Actions Under CERCLA.

EPA, 1993a, Presumptive Remedy for CERCLA Municipal Landfill Sites, OSWER Directive 9355.0-49FS, September.

EPA, 1994, Feasibility Study Analysis for CERCLA Municipal Landfill Sites, OSWER Directive 9356.0-03, EPA/540/R-94/081, August.

Geomatrix, 1995, Evaluation of the Capability of Inferred Faults in the Vicinity of Building 371, Geomatrix Consultants, Inc. Rocky Flats Environmental Technology Site, Golden, Colorado, January.

Integrated Hydro Systems, 2004, Integrated Flow and VOC Fate and Transport for the Original Landfill, Rocky Flats Environmental Technology Site, Golden, Colorado, October.

Kaiser, 2001, Personal Communication with Linda Kaiser, Rocky Flats Environmental Technology Site, Golden, Colorado, July.

Kaiser-Hill, 1996, Final Phase I RFI/RI Report, Woman Creek Priority Drainage, Operable Unit, April.

Kaiser-Hill, 2002, Draft Site Characterization Report, Original Landfill, Rocky Flats Environmental Technology Site, Golden, Colorado, March.

Kaiser-Hill, 2003, Control and Disposition of Incidental Waters, 1-C91-EPR-SW.01, Revision 3, Rocky Flats Environmental Technology Site, Golden, Colorado.

Kaiser-Hill, 2004, Uranium in Surface Soil, Surface Water, and Groundwater at the Rocky Flats Environmental Technology Site, Golden, Colorado, June.

Metcalf & Eddy, 1995, Draft Geotechnical Investigation Report for Operable Unit No. 5, ME-EEG-T-0009, Rocky Flats Environmental Technology Site, Golden, Colorado, September.

NCRP, 1987, Recommendations on Limits for Exposure to Ionizing Radiation Report.

RFETS, 2000, Integrated Monitoring Plan Background Document, Section 5.0 Ecological Monitoring, Rocky Flats Environmental Technology Site, Golden, Colorado, November.

Rockwell, 1988, Remedial Investigation and Feasibility Study Plans for Low Priority Sites, Volume I – Site Descriptions, Groupings and Prioritization, June.

R.S. Means Company Inc., 2001, Means 2002 Cost Works.

Scott, G.R., 1963, Quaternary Geology and Geomorphic History of the Kassler Quadrangle, Colorado, USGS Professional Paper 421, pp. 1-70.

Singer, Steve, 2002, Personal communication with Manager of Water Programs, Kaiser-Hill Team, Rocky Flats Environmental Technology Site, Golden, Colorado February.


Appendix A

ARARs

> APEN Requirements

Requirement	Citation	Туре	Comment
ATOMIC ENERGY ACT (AEA) [42 USC 2200 et. s	eq.]		Establishes a program to reduce the number of workers currently exposed to
CHRONIC BERYLLIUM DISEASE PREVENTION PROGRAM	10 CFR 850	A	beryllium in the course of their work at DOE facilities. The cited sections are followed in relation to determinations of beryllium contamination and release
Definitions Release Criteria Waste Disposal	.3 .31 .32		to the public.
Warning Labels	.38 (b-c)		
Walling Labers	•		
	·		
CLEAN AIR ACT (CAA), 42 USC 7401 et seq.			
·	5 CCR 1001		
COLORADO AIR QUALITY CONTROL COMMISSION (CAQCC) REGULATIONS	(40 CFR 52, SUBPART		
COMMISSION (CAQCE) REGULATIONS	G)		
 Emission Control Regulations for Particulates, Smokes, Carbon Monoxide, and Sulfur Oxides 	5 CCR 1001-3 (CAQCC Reg. No. 1)		
> Smoke and Opacity	Section II.A.1	C	Air pollutant emissions from stationary sources (e.g., fuel-fired pumps, generators, a compressors, process vents/stacks) shall not exceed 20% opacity.
> Fugitive Particulate Emissions	Section III.D	A	Technologically feasible and economically reasonable control measures and operating procedures will be employed to reduce, prevent, and control particulate emissions.
Construction Activities	III.D.2(b)		
 Storage and Handling of Material 	III.D.2(c)		
 Haul Roads 	III.D.2(e)		
 Haul Trucks 	III.D.2(f)		
 Air Pollutant Emission Notices (APEN), Construction Permits and Fees, Operating Permits, and Including the Prevention of Significant 	5 CCR 1001-5 (CAQCC Reg. No. 3)		
Deterioration	· :		
		.]	An APEN shall be filed with CDPHE prior to construction, modification, or alteration

Requirement	Citation	Type	Comment
EAN AIR ACT (CAA), 42 USC 7401 et seq.			
 Construction Permits, Including Regulations for the Prevention of Significant Deterioration (PDS) 	Part B		of, or allowing emissions of air pollutants from, any activity. Certain activities are exempted from APEN requirements per specific exemptions listed in the regulation. Construction permits are not required for CERCLA activities; however, substantive requirements that would normally be associated with construction permits will apply
	; .	j	
Construction Permits	Section III	С	Construction permits are not required for CERCLA activities; however, substantive requirements that would normally be associated with construction permits will apply Also, fuel-fired equipment (e.g., generators, compressors) associated with these activities may require permitting.
Non-Attainment Area Requirements	Section IV.D.2	A/C/L	Even though CERCLA activities are exempt from construction permit requirements non-attainment area requirements may apply if emissions of certain pollutants exce certain threshold limits. The requirements include emissions reductions or offsets, a strict emission control requirements. Although RFETS is no longer a non-attainment area, this requirement is retained in the event the non-attainment designation change
 Prevention of Significant Deterioration Requirements 	Section IV.D.3	A/C/L	Even though CERCLA activities are exempt from construction permit requirements PSD requirements may apply if emissions of certain pollutants exceed certain threshold limits. The requirements include strict emission control requirements, source impact modeling, and pre-construction and post-construction monitoring.
 Emissions of Volatile Organic Compounds (VOCs) General Requirements for Storage and Transfer of VOCs 	5 CCR 1001-9 (CAQCC Reg. No. 7) Section III.B	A	Applies to the transfer of VOCs to a tank larger than 56 gallons. In such cases, submerged-fill or bottom-fill techniques must be used.
 Disposal of VOCs Storage and Transfer of Petroleum Liquid Control of Hazardous Air Pollutants 	Section V Section VI 5 CCR 1001-10 (CAQCC Reg. No. 8), 40 CFR 61, Subpart A	A	Prohibits the disposal of VOCs by evaporation or spillage. Regulated storage and transfer of petroleum liquids. This subpart details the general provisions that apply to sources subject to National Emission Standards for Hazardous Air Pollutants (NESHAPs).
National Emission Standards for Emissions of Radionuclides Other Than Radon From Department of Energy Facilities	5 CCR 1001-10 (CAQCC Reg. No. 8) 40 CFR 61, Subpart H		



1	Requirement	Citation	Туре	Comment
CLEAN A	AIR ACT (CAA), 42 USC 7401 et seq.			
>	Standard	61.92	C/L	This section establishes a radionuclide emission standard equal to those emissions that yield an effective does equivalent (EDE) of 10 mrem/year to any member of the public. The perimeter samplers in the Radioactive Ambient Air Monitoring Program (RAAMP) sampler network are used to verify compliance with the standard.
	Emission Monitoring and Test Procedures	61.93	C/A	This section establishes emission monitoring and testing protocols required to measure radionuclide emissions and calculated EDEs. This section also requires that radionuclide emissions measurements (i.e., stack monitoring) be made at all release points that have a potential to discharge radionuclides into the air which could cause an EDE to the most impacted member of the public in excess of 1% of the standard (i.e., 0.1 mrem/year).
>	Compliance and Reporting	61.96	C/L	This section requires the Site to perform radionuclide air emission assessments of all new and modified sources. For sources that exceed the 0.1 mrem/year EDE threshold (controlled), the appropriate applications for approval must be submitted to EPA and CDPHE. Additional substantive requirements may apply if the activity requires agency approval.

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM REGULATION		· .		.		,		
Storm Water Permit for Construction ActivitiesGeneral Permits	40 CFR 122.26 40 CFR 122.28		A/L A/L					· · · · · · · · · · · · · · · · · · ·
DISCHARGES OF DREDGED OR FILL MATERIAL INTO WATERS OF THE UNITED STATES	33 USC 1344 33 CFR 323.3		A/L					
Discharges Requiring Permits	J				:		 	
DOE COMPLIANCE WITH FLOODPLAIN/WETLANDS ENVIRONMENTAL REVIEW REQUIREMENTS COMPLIANCE WITH FLOODPLAIN/WETLANDS ENVIRONMENTAL REVIEW REQUIREMENTS	10 CFR 1022	. ;	A/L					

Permit Requirement Completion Time

Submission of Biological Assessment

Requirement	Citation	Туре	Comment
FEDERAL WATER POLLUTION CONTROL A	CT (aka Clean Water A	ct [CWA]).	33 USC 1251 et seq.
 Floodplain/Wetlands Determination Floodplain/Wetlands Assessment Applicant Responsibilities 	.11 .12 .13		
MIGRATORY BIRD TREATY ACT, 16 USC 701	et seq.		
TAKING, POSSESSION, TRANSPORTATION, SALE, PURCHASE, BARTER, EXPORTATION, AND IMPORTATION OF WILDLIFE AND PLANTS	50 CFR 10	A/L	Principally focuses on the taking and possession of birds protected under this regulation. Enforcement is predicated on location of the project and time of the year Current list of protected birds is maintained by the Site Ecology group.
NATURAL RESOURCE AND WILDLIFE PROT	ECTION LAWS		
EARLY CONSULTATION	50 CFR 402.11	A/L	Identify and minimize early in the planning stage of action, any potential conflicts between the action and federally listed species.
Purpose Preparation Requirements Request for Information Director's Response	50 CFR 402.12	A/L	This is the process DOE needs to follow to evaluate the potential effects of the action on listed and proposed species and designated and proposed critical habitat and determine whether any such species or habitat are likely to be adversely affected by the action and is used in determining whether formal consultation or a conference is necessary.
 No Listed Species or Critical Habitat Present Listed Species or Critical Habitat Present Verification of Current Accuracy or Species List 			
ContentsIdentical/Similar to Previous Action			



Appendix A – Applicable or Relevant and Appropriate Requirements

Requirement	Citation	Type	Comment
Use of Biological Assessment	<i>'</i>	<u> </u>	
NTERAGENCY COOPERATION Informal Consultation	50 CFR 402	A/L	This is an optional process that includes all discussions, correspondence, etc., between the USFWS and the DOE. IT is designed to assist in determining whether formal consultation or a conference is required. If during it is determined by the DOE with concurrence of the USFWS that the action is not likely to adversely affect listed species or critical habitat, the consultation process is terminated and no further action is necessary. DOE shall review its actions at the earliest possible time to determine whether any action may affect listed species or critical habitat.

SOLID WASTE DISPOSAL ACT (aka: Resource Conservation and Recovery Act [RCRA]), 42 USC 6901 et seq.; SUBTITLE C: HAZARDOUS WASTE MANAGEMENT (Colorado Hazardous Waste Act [CHWA]), CRS 25-15-101 to -217

Although the Colorado hazardous waste management regulations are similar to the federal requirements, both the federal and state regulatory citations are provided for reference purposes and to denote that both federal and state requirements were considered in establishing the identifying the ARAR requirement adopted for the remediation of the RFETS. Only substantive portions of the regulations are required under CERCLA actions for onsite activities.

CLOSURE	6 CCR 1007-3, Part 265, Subpart N (40CFR 265, Subpart N)		
Cover requirements (Landfills) Function with minimum maintenance; and	.310(a)(2)	A/C	Relevant and Appropriate
Accommodate settling and Subsidence so that the cover's integrity is maintained.	.310(a)(4)	A/C	Relevant and Appropriate

FEDERAL NOXIOUS WEED ACT (Pub. L. 93-629; 7	USC 2814 et seq.)		· · · · · · · · · · · · · · · · · · ·	<u> </u>	·		· · · · · · · · · · · · · · · · · · ·	
MANAGEMENT OF UNDESIRABLE PLANTS ON FEDERAL LANDS	7 USC 2814					•		





Requirement	Citation	Туре	Comment
FEDERAL NOXIOUS WEED ACT (Pub. L. 93-629;	7 USC 2814 et seq.)		
Duties of Federal Agencies	(a)(3), (a)(4), (c)(1), (c)(2)	A	Federal agencies must complete and implement cooperative agreements with State agencies regarding the management of undesirable plant species on Federal lands under the agency's jurisdiction and establish integrated management systems to control or contain undesirable plant species targeted under cooperative agreements.
COLORADO NOXIOUS WEED ACT (CRS 35-	5.5-101 et seq.)		
DUTY TO MANAGE NOXIOUS WEEDS	Section 104	A	It is the duty of all persons to use integrated methods to manage noxious weeds if the same are likely to be materially damaging to the land of neighboring landowners, and it is the duty of local governing bodies to assure that these plants are, in fact, managed.
COOPERATION WITH FEDERAL AND STATE AGENCIES	Section 111	A	The local governing bodies in Colorado are authorized to enter into cooperative agreements with federal and state agencies for the integrated management of noxious weeds within their respective territorial jurisdictions. The Jefferson County Noxious Weed Management Plan establishes the countywide strategy for the management, control, and eradication of noxious weeds in the County.
NATIONAL WILDLIFE REFUGE ACT			

NATIONAL WILDLIFE REFUGE ACT			
NATIONAL WILDLIFE REFUGE SYSTEM ADMINISTRATION ACT	16 USC 668 et seq.	L	Relevant and Appropriate. Prohibits interference with natural growth or wildlife, on National Wildlife Refuges administered by the USFWS,
			unless permitted.

Appendix B

Environmental Data Tables

Table 1
Sampling and Analytical Summary for OLF Soil

MED AND REPORT & STORY OF STREET	Surface Soil 2		Committee of the second	Sübsi	urface Solli	2,842,95,475	KARK SEE BESTERN
	Callaction Date	Analyte:Group	Location Code	ollection Date: 5	stant Deput	End Depth	Analyte Group
20Cation reories	8/8/1990	Metal	50592	12/15/1992			
INT. DITCH	8/8/1990		50592	12/15/1992	3.75		VOC
INT. DITCH		Pesticide	50592	12/15/1992	0		Metal
INT. DITCH	8/8/1990		50592	12/15/1992	0		PCB
INT. DITCH	8/8/1990		50592	12/15/1992	0		Pesticide
INT. DITCH		Radionuclide	50592	12/15/1992	0		Radionuclide
SS505093		Radionuclide	50592	12/15/1992	0		SVOC
SS505293	6/24/1993	Radionuclide	50592	12/15/1992	0		VOC
SS505393		Radionuclide	50592	12/15/1992	4		VOC
SS505493		Radionuclide	50592	12/15/1992	6		VOC
SS505593		Radionuclide	50592	12/15/1992	- 8		VOC
SS505693			50592	12/15/1992	6		Metal
SS505893		Radionuclide	50592	12/15/1992	6	12	PCB
SS506293	1/8/1993		50592	12/15/1992	6	12	Pesticide
SS506293	1/8/1993		50592	12/15/1992	.6		Radionuclide
SS506293		Pesticide	50592	12/15/1992	6	. 12	SVOC
SS506293		Radionuclide	50592	12/15/1992	6	. 12	VOC
SS506293	1/8/1993		50592	12/15/1992	10	12	VOC
SS506293	1/8/1993		50592	12/15/1992	. 12	14	VOC
SS506493	1/8/1993		50592	12/15/1992	14		VOC
SS506493	1/8/1993		50592	12/15/1992	12		Metal
SS506493		Pesticide	50592	12/15/1992	12		PCB
SS506493		Radionuclide		12/15/1992	12		Pesticide
SS506493	1/8/199:		50592	12/15/1992	12		Radionuclide
SS506493	1/8/199		50592	12/15/1992			SVOC
SS506593	1/25/199		50592			1	VOC
SS506593	1/25/199		50592				VOC
SS506593	1/25/199	3 Pesticide	50592				voc
SS506593	1/25/199	3 Radionuclide	50592				voc
SS506593	1/25/199		50592				4 Metal
SS506593	1/25/199		50592				4 PCB
SS506693	1/25/199		50592				4 Pesticide
SS506693	1/25/199		50592				4 Radionuclide
SS506693	1/25/199	3 Pesticide	50592			<u> </u>	4 SVOC
SS506693	1/25/199	3 Radionuclide	50592				4 VOC
SS506693	1/25/199	3 SVOC	50592			<u> </u>	4 VOC
SS506693	1/25/199	3 VOC	50592				6 VOC
SS506793	1/15/199	3 Metal	50592			<u> </u>	8 VOC
SS506793	1/15/199		50592				2 Metal
SS506793	1/15/199	3 Pesticide	50592				2 PCB
SS506793	1/15/199	3 Radionuclide	50592				2 Pesticide
SS506793		3 SVOC	5059			_	2 Radionuclide
SS506793	1/15/19	93 VOC	5059			<u> </u>	2 SVOC
SS506893	1/15/19	93 Metal	5059				32 VOC
SS506893	1/15/19	93 PCB	5059				21/00
SS506893		93 Pesticide	5069			0	2 VOC 4 VOC
SS506893	1/15/19	93 Radionuclide	5069			0	
SS506893	1/15/19	93 SVOC	5069			0	6 Metal
	1/15/19	93 VOC	5069			0	6 PCB
SS506893		93 Metal	5069			0	6 Pesticide
SS507093	1/25/19	93 PCB	5069		2	<u> </u>	6 Radionuclide
SS507093	1/25/15	93 Pesticide	5069		2	0	6 SVOC
SS507093		93 Radionuclide			2	. 0	6 VOC
SS507093		93 SVOC	5069		2	4	6 VOC
SS507093		93 VOC	5069			6	8 VOC

Table 1
Sampling and Analytical Summary for OLF Soil

S507193	1/25/1993	Metal	50692	12/8/1992	8	10 \	
	1/25/1993		50692	12/9/1992	6	12 N	
SS507193	1/25/1993		50692	12/9/1992	6	12 F	
SS507193		Radionuclide	50692	12/9/1992	6		Pesticide
SS507193	1/25/1993		50692	12/9/1992	6	12 F	Radionuclide
SS507193	1/25/1993		50692	12/9/1992	6	12 8	SVOC
SS507193	1/25/1993		50692	12/9/1992	6	12\	/OC
SS507293			50692	12/9/1992	10	12\	/OC
S507293	1/25/1993		50692	12/9/1992	12	14\	/OC
SS507293	1/25/1993		50692	12/9/1992	14	16	/OC
SS507293		Radionuclide	50692	12/10/1992	0	14	Metal
SS507293	1/25/1993		50692	12/10/1992	- 0	14 1	PCB
SS507293	1/25/1993		50692	12/10/1992	0		Pesticide
SS507393	1/20/1993			12/10/1992		14	Radionuclide
SS507393	1/20/1993		50692	12/10/1992	0		SVOC
SS507393	1/20/1993		50692	12/10/1992	0		VOC
SS507393		Radionuclide	50692		- 0		VOC
SS507393	1/20/1993		50792	12/11/1992			VOC
SS507393	1/20/1993	VOC	50792	12/11/1992	- 0		Metal
SS507493	1/25/1993	Metal	50792	12/11/1992			PCB
SS507493	1/25/1993		50792	12/11/1992	0		Pesticide
SS507493	1/25/1993	Pesticide	50792	12/11/1992	0		Radionuclide
SS507493	1/25/1993	Radionuclide	50792	12/11/1992	0		SVOC
SS507493	1/25/1993	SVOC	50792	12/11/1992	0		
SS507493	1/25/1993	VOC	50792	12/11/1992	0		VOC
SS507593	1/25/1993		50792	12/11/1992	4		VOC
SS507593	1/25/1993		50792	12/11/1992	6		VOC
SS507593		Pesticide	50792	12/11/1992	0		Metal
SS507593		Radionuclide	50792	12/11/1992	0		PCB
SS507593	1/25/1993		50792	12/11/1992	0		Pesticide
SS507593	1/25/1993		50792	12/11/1992	0		Radionuclide
	1/20/1993		50792	12/11/1992	0		SVOC
SS507693	1/20/199		50792	12/11/1992	0		VOC
SS507693		Pesticide	50792	12/11/1992	8		VOC
SS507693		Radionuclide	50892	12/14/1992	0		VOC
SS507693	1/20/199		50892	12/14/1992	2	4	VOC
SS507693			50892	12/14/1992	0	6	Metal
SS507693	1/20/199		50892	12/14/1992	o	6	PCB
SS507793	1/26/199		50892	12/14/1992	0	6	Pesticide
SS507793	1/26/199		50892	12/14/1992	0	6	Radionuclide
SS507793		3 Pesticide	50892	12/14/1992	0	6	SVOC
SS507793		3 Radionuclide	50892	12/14/1992	- 0		VOC
SS507793	1/26/199			12/14/1992	4		voc
SS507793	1/26/199		50892	12/14/1992	6		voc
SS507893	1/26/199		50892		- 8		voc
SS507893	1/26/199	3 PCB	50892	12/14/1992	6		Metal
SS507893		3 Pesticide	50892	12/14/1992	6		PCB
SS507893		3 Radionuclide	50892	12/14/1992			Pesticide
SS507893	1/26/199	3 SVOC	50892	12/14/1992	6		Radionuclide
SS507893	1/26/199	3 VOC	50892	12/14/1992	6		SVOC
SS507993		3 Metal	50892	12/14/1992	6		
SS507993	1/26/199	3 PCB	50892	12/14/1992	6		VOC
SS507993		93 Pesticide	50892	12/14/1992	10		VOC
		3 Radionuclide	50892	12/14/1992	8		Metal
SS507993		3 SVOC	50892	12/14/1992	8		PCB
SS507993	1/26/19	31/00	50892	12/14/1992	8		Pesticide
SS507993 SS508093		93 Metal	50892	12/14/1992	.8		Radionuclide
ICCENDADA	1/2//19	SO IIVICIAI	J J J J J J J J J J J J J J J J J J J	12/14/1992		4.0	SVOC

Table 1
Sampling and Analytical Summary for OLF Soil

SS508093	1/27/1993	Pesticide	50892	12/14/1992	8		VOC
SS508093		Radionuclide	50992	12/18/1992	0		VOC
SS508093	1/27/1993		50992	12/18/1992	0		Metal
SS508093 SS508093	1/27/1993		50992	12/18/1992	0		PCB
SS508093 SS508193	1/20/1993		50992	12/18/1992	0		Pesticide
	1/20/1993		50992	12/18/1992	0		Radionuclide
SS508193	1/20/1993		50992	12/18/1992	0		SVOC
SS508193		Radionuclide	50992	12/18/1992	0		VOC
SS508193	1/20/1993		50992	12/18/1992	4		VOC
SS508193	1/20/1993		50992	12/18/1992	6		VOC
SS508193			50992	12/18/1992	8	10	VOC
SS508293	1/26/1993		50992	12/18/1992	6	12	Metal
SS508293	1/26/1993		50992	12/18/1992	6	12	PCB
SS508293	1/26/1993		50992	12/18/1992	6	12	Pesticide
SS508293		Radionuclide	50992	12/18/1992	6	12	Radionuclide
SS508293	1/26/1993		50992	12/18/1992	6	12	SVOC
SS508293	1/26/1993		50992	12/18/1992	6	12	VOC
SS508393	1/26/1993		50992	12/18/1992	12		VOC
SS508393	1/26/1993		50992	12/18/1992	0		Metal
SS508393	1/26/1993			12/18/1992	- 6		PCB
SS508393		Radionuclide	50992	12/18/1992	0		Pesticide
SS508393	1/26/1993		50992	12/18/1992	- 0		Radionuclide
SS508393	1/26/1993		50992		- 0		SVOC
SS508493	1/26/1993		50992	12/18/1992	- 0		voc .
SS508493	1/26/1993		50992	12/18/1992	14		voc
SS508493		Pesticide	50992	12/18/1992			voc
SS508493	1/26/1993	Radionuclide	51092	12/21/1992	0		VOC
SS508493	1/26/1993	SVOC	51092	12/21/1992	2		
SS508493	1/26/1993	VOC	51092	12/21/1992	0		Metal
SS508593	1/27/1993	Metal	51092	12/21/1992	0		PCB
SS508593	1/27/1993	PCB	51092	12/21/1992	0		Pesticide
SS508593		Pesticide	51092	12/21/1992	0		Radionuclide
SS508593	1/27/1993	Radionuclide	51092	12/21/1992	0		SVOC
SS508593	1/27/1993	SVOC	51092	12/21/1992	0		VOC
SS508593	1/27/1993		51092	12/21/1992	4		VOC
SS508693	1/21/1993		51092	12/21/1992	6		VOC
SS508693	1/21/1993		51092	12/21/1992	0		Metal
SS508693		Pesticide	51092	12/21/1992	0		PCB
SS508693		Radionuclide	51092	12/21/1992	0		Pesticide
	1/21/199		51092	12/21/1992	0		Radionuclide
SS508693	1/21/199		51092	12/21/1992	0		SVOC
SS508693	2/1/199		51092	12/21/1992	0		VOC
SS508793	2/1/199		57594	10/31/1994	1.7		VOC
SS508793		3 Pesticide	57594	10/31/1994	3.7		VOC
SS508793		3 Radionuclide	57594	10/31/1994	0	. (Metal
SS508793			57594	10/31/1994	0		PCB
SS508793		3 SVOC	57594	10/31/1994	. 0		Pesticide
SS508793	2/1/199	3 VOC	57594	10/31/1994	0	(Radionuclide
SS508893	1/26/199	SINICIAI	57594	10/31/1994	0	,	SVOC
SS508893	1/26/199	3 PUD	57594	10/31/1994	0		6 VOC
SS508893	1/26/199	3 Pesticide	57594	10/31/1994	5.7		6 VOC
SS508893		3 Radionuclide	57594	10/31/1994			8 VOC
SS508893		3 SVOC		10/31/1994			2 Metal
SS508893	1/26/199		57594				2 PCB
SS508993	1/27/199		57594	10/31/1994			2 Pesticide
SS508993	1/27/199		57594	10/31/1994			2 Radionuclide
SS508993	1/27/199	3 Pesticide	57594	10/31/1994			2 SVOC
SS508993	1/27/199	3 Radionuclide	57594	10/31/1994	6	<u></u>	2 3000

Table 1
Sampling and Analytical Summary for OLF Soil

				1000111001	C.	42	VOC
SS508993	1/27/1993	SVOC	57594	10/31/1994	6		VOC
SS508993	1/27/1993	VOC	57594	10/31/1994	15.7		
SS509093	2/2/1993	Metal	57594	11/4/1994	18		Metal
SS509093	2/2/1993	PCB	57594	11/4/1994	18		PCB
SS509093	2/2/1993		57594	11/4/1994	18		Pesticide
SS509093	2/2/1993	Radionuclide	57594	11/4/1994	18		Radionuclide
SS509093	2/2/1993		57594	11/4/1994	18		SVOC
SS509093	2/2/1993	VOC	57594	11/4/1994	18		voc
SS509093	1/21/1993		57594	11/7/1994	18		Metal
SS509193	1/21/1993		57594	11/7/1994	18		PCB
	1/21/1993		57594	11/7/1994	18	23	Pesticide
SS509193		Radionuclide	57594	11/7/1994	18	23	Radionuclide
SS509193	1/21/1993		57594	11/7/1994	18	23	SVOC
SS509193	1/21/1993	VOC	57594	11/7/1994	18	23	VOC
SS509193	1/21/1993		57594	11/8/1994	84.9	90.4	Metal
ŞS509293	2/1/1993		57594	11/8/1994	84.9	90.4	
SS509293	2/1/1993		57594	11/8/1994	84.9		Pesticide
SS509293		Pesticide		11/8/1994	84.9		Radionuclide
SS509293		Radionudide	57594	11/8/1994	84.9		SVOC
SS509293	2/1/1993		57594		84.9	90.4	
SS509293	2/1/1993		57594	11/8/1994	24		Metal
SS509393	2/1/1993		57594	11/29/1994			PCB
SS509393	2/1/1993		57594	11/29/1994	24		Pesticide
SS509393		Pesticide	57594	11/29/1994	24		
SS509393	2/1/1993	Radionuclide	57594	11/29/1994	24		Radionuclide
SS509393	2/1/1993	SVOC	57594	11/29/1994	24		SVOC
SS509393	2/1/1993		57594	11/29/1994	24		VOC
SS509493	1/27/1993		58393	5/12/1993	3.25		VOC
SS509493	1/27/1993		58393	5/12/1993	0		Metal
SS509493		Pesticide	58393	5/12/1993	0		PCB
SS509493		Radionuclide	58393	5/12/1993	0		Pesticide
SS509493	1/27/1993		58393	5/12/1993	0		Radionuclide
SS509493	1/27/1993		58393	5/12/1993	0		SVOC
	1/28/1993		58393	5/12/1993	0		VOC
SS509593	1/28/1993		58393	5/12/1993	6.45		VOC
SS509593		Pesticide	58393	5/12/1993	10.4	10.7	VOC.
SS509593		Radionuclide	58393	5/12/1993	6	12.7	Metal
SS509593			58393	5/12/1993	6	12.7	PCB
SS509593	1/28/1993		58393	5/12/1993	6	12.7	Pesticide
SS509593	1/28/1993		58393	5/12/1993	6		Radionuclide
SS509693	6/21/1993			5/12/1993	- 6		SVOC
SS509693	6/21/1993		58393	5/12/1993	6		VOC
SS509693		Pesticide	58393	5/12/1993	19.5		Metal
SS509693		Radionuclide	58393		19.5		Radionuclide
SS509693	6/21/199		58393	5/12/1993	19.5		VOC
SS509693	6/21/199		58393	5/12/1993			VOC
SS509793	1/21/199		58493	5/13/1993	3.15		VOC
SS509793	1/21/199		58493	5/13/1993	2		
SS509793		3 Pesticide	58493	5/13/1993	0		Metal
SS509793		3 Radionuclide	58493	5/13/1993	0		PCB
SS509793	1/21/199		58493	5/13/1993	0		Pesticide
SS509793	1/21/199		58493	5/13/1993	0		Radionuclide
SS509793 SS509893		3 Metal	58493	5/13/1993	0		SVOC
	2/1/199		58493	5/13/1993			VOC
SS509893		3 Pesticide	58493	5/13/1993			VOC
SS509893			58493	5/13/1993			VOC
SS509893		3 Radionuclide	58493				2 Metal
SS509893	2/1/199	3 SVOC	58493				2 PCB
SS509893	2/1/199	3 VOC	50493	3/13/1333		I	

Table 1
Sampling and Analytical Summary for OLF Soil

		Т	58493	5/13/1993	6	12	Pesticide
SS509993	2/1/1993		58493	5/13/1993	6		Radionuclide
SS509993	2/1/1993			5/13/1993	6		SVOC
SS509993	2/1/1993		58493	5/13/1993	6		VOC
S509993	2/1/1993	Radionuclide	58493	10/13/1994	2		voc
S509993	2/1/1993		58494	10/13/1994	4		voc
SS509993	2/1/1993		58494		0		Metal
SS510093	1/27/1993		58494	10/13/1994			PCB
SS510093	1/27/1993		58494	10/13/1994	- 0		Pesticide
SS510093	1/27/1993		58494	10/13/1994			Radionuclide
SS510093	1/27/1993	Radionuclide	58494	10/13/1994	0		SVOC
SS510093	1/27/1993		58494	10/13/1994			VOC
SS510093	1/27/1993	VOC	58494	10/13/1994	0		VOC
SS510193	1/28/1993	Metal	58494	10/13/1994	6		VOC
SS510193	1/28/1993	PCB	58494	10/13/1994	8		
SS510193	1/28/1993	Pesticide	58494	10/13/1994	. 6		Metal PCB
SS510193	1/28/1993	Radionuclide	58494	10/13/1994	6		
SS510293	6/21/1993		58494	10/13/1994	6		Pesticide
SS510293	6/21/1993		58494	10/13/1994	6		Radionuclide
SS510293	6/21/1993		58494	10/13/1994	6		svoc
SS510293		Radionuclide	58494	10/13/1994	6		VOC
SS510293	6/21/1993		58494	10/13/1994	9.5		VOC
SS510293 SS510293	6/21/1993		58593	5/14/1993	0		Metal
	1/21/1993		58593	5/14/1993	0		Radionuclide
SS510393	1/21/1993		58593	5/14/1993	0		VOC
SS510393		Pesticide	58593	5/14/1993	2	4	VOC
SS510393		Radionudide	58593	5/14/1993	0	6	Metal
SS510393			58593	5/14/1993	0	6	PCB
SS510393	1/21/1993		58593	5/14/1993	0	- 6	Pesticide
SS510393	1/21/1993		58593	5/14/1993	0	6	Radionuclide
SS510493	2/1/1993		58593	5/14/1993	0	6	SVOC
SS510493	2/1/1993		58593	5/14/1993	. 0	6	VOC
SS510493		Pesticide	58593	5/14/1993	4		VOC
SS510493		Radionuclide	58593	5/14/1993	6	8	
SS510493	2/1/1993			5/14/1993	8		voc
SS510493	2/1/1993		58593	5/14/1993	6		Metal
SS510593	1/28/1993		58593		6		PCB
SS510593	1/28/1993		58593	5/14/1993	6		Pesticide
SS510593		Pesticide	58593	5/14/1993			Radionuclide
SS510593		Radionuclide	58593	5/14/1993	6		SVOC
SS510593	1/28/1993	SVOC	58593	5/14/1993			VOC
SS510593	1/28/1993	VOC	58593	5/14/1993	6		
SS510693	1/28/1993	3 Metal	58593	5/14/1993	10.5		VOC
SS510693	1/28/199		58593	5/14/1993			1 VOC
SS510693		3 Pesticide	58593	5/14/1993			1 VOC
SS510693	1/28/199	3 Radionuclide	58593	5/14/1993			1 Metal
SS510693	1/28/199		58593	5/14/1993			1 PCB
SS510693	1/28/199		58593				1 Pesticide
	1/28/199	3 Metal	58593	5/14/1993	12.5		1 Radionuclide
SS510793	1/28/199		58593		12.5		1 SVOC
SS510793		3 Pesticide	58593				1 VOC
SS510793	1/20/199	3 Radionuclide	58593			18.	1 VOC
SS510793			58693				2 Metal
SS510893	1/28/199		58693				2 Radionuclide
SS510893	1/28/199	S PUB	58693	1			4 VOC
SS510893		3 Pesticide					6 Metal
SS510893		3 Radionuclide	58693				6 PCB
SS510893		3 SVOC	58693				6 Pesticide
SS510893	1/28/199	3VOC	58693	5/1//1993		1	

Table 1 Sampling and Analytical Summary for OLF Soil

00540000	2/2/1993	Motal	58693	5/17/1993	ol	6	Radionuclide
SS510993	2/2/1993		58693	5/17/1993	- 0		SVOC
SS510993			58693	5/17/1993	0	6	VOC
SS510993	2/2/1993		58693	5/17/1993	6.2		VOC
SS510993		Radionuclide	58693	5/17/1993	6		Metal
SS510993	2/2/1993			5/17/1993	6		PCB
SS510993	2/2/1993		58693		6		Pesticide
SS511093	2/2/1993		58693	5/17/1993			Radionuclide
SS511093	2/2/1993	PCB	58693	5/17/1993	6		
SS511093		Pesticide	58693	5/17/1993	6		SVOC
SS511093	2/2/1993	Radionuclide	58693	5/17/1993	6		VOC
SS511093	2/2/1993	SVOC	58693	5/17/1993	10.3		VOC
SS511093	2/2/1993	VOC	58693	5/18/1993	15.5	17.5	
SS511193	2/2/1993		58693	5/18/1993	12		Metal
SS511193	2/2/1993		58693	5/18/1993	12	19.5	
SS511193		Pesticide	58693	5/18/1993	12	19.5	Pesticide
		Radionuclide	58693	5/18/1993	12	19.5	Radionuclide
SS511193			58693	5/18/1993	12	19.5	SVOC
SS511193	2/2/1993		58693	5/18/1993	12		VOC
SS511193	2/2/1993			5/18/1993	19.8	20.1	
SS511293	2/2/1993		58693	5/18/1993	21.5		VOC
SS511293	2/2/1993		58693		19.5		Metal
SS511293		Pesticide	58693	5/18/1993			PCB
SS511293		Radionuclide	58693	5/18/1993	19.5		Pesticide
SS511293	2/2/1993		58693	5/18/1993	19.5		
SS511293	2/2/1993	VOC	58693	5/18/1993	19.5		Radionuclide
SS511493	2/2/1993	Metal	58693	5/18/1993	19.5		SVOC
SS511493	2/2/1993	PCB	58693	5/18/1993	19.5		VOC
SS511493		Pesticide	58693	5/18/1993	23.5		VOC
SS511493		Radionuclide	58693	5/18/1993	25.5		VOC
SS511493	2/2/1993		58693	5/18/1993	25.5		Metal
SS511493	2/2/1993		58693	5/18/1993	25.5	29.5	PCB
SS515593		Radionuclide	58693	5/18/1993	25.5	29.5	Pesticide
		Radionuclide	58693	5/18/1993	25.5		Radionuclide
SS515693	1/1/1990	Tradionadiae	58693	5/18/1993	25.5	29.5	SVOC
			58693	5/18/1993	25.5	29.5	VOC
			58693	5/18/1993	27.5	29.5	VOC
	•		59293	6/4/1993	0		Metal
,	,	• • •			0		Radionuclide
			59293	6/4/1993	- 0		VOC
. [59293		2		voc
	. •		59293		0		Metal
			59293		0		PCB
			59293				Pesticide
		•	59293		0		Radionuclide
1			59293		0		
1.	•		59293		0		SVOC
			59293		0		VOC
1			59293		4		VOC
1.		•	59293		6		VOC
	.•		59293	6/4/1993	8		VOC
			59293	6/4/1993	6		Metal
	•		59293		6		PCB
1.		•	59293				Pesticide
Ţ,	,		59293			1	Radionuclide
,							SVOC
			59293				VOC
		•	59293				
1				VI 01414000			/IV/()(.
			59293 59293				VOC VOC

Table 1
Sampling and Analytical Summary for OLF Soil

				
59293	6/4/1993	12		Metal
59293	6/4/1993	12	18.9	
59293	6/4/1993	12		Pesticide
59293	6/4/1993	12	18.9	Radionuclide
59293	6/4/1993	12	18.9	SVOC
59293	6/4/1993	12	18.9	VOC
59493	6/14/1993	0.4	2	Metal
59493	6/14/1993	0.4	2	Radionuclide
59493	6/14/1993	0.4	2	voc
59493	6/14/1993	0	6.3	Metal
59493 59493	6/14/1993	0		PCB
	6/14/1993			Pesticide
59493	6/14/1993			Radionuclide
59493		0		SVOC
59493	6/14/1993	0		voc
59493	6/14/1993	4.9		voc
59493	6/14/1993			Metal
59493	6/14/1993	6.9		PCB
59493	6/14/1993	6.9		
59493	6/14/1993	6.9		Pesticide
59493	6/14/1993	6.9		Radionuclide
59493	6/14/1993	6.9		SVOC
59493	6/14/1993	6.9		VOC
59493	6/14/1993	10.9		VOC
59493	6/14/1993	14.9		VOC
59493	6/14/1993	12.9		Metal
59493	6/14/1993	12.9	17.8	PCB
59493	6/14/1993	12.9	17.8	Pesticide
59493	6/14/1993	12.9		Radionuclide
59493	6/14/1993	12.9	17.8	SVOC
59493	6/14/1993	12.9		VOC
59593	6/15/1993	0		Metal
59593	6/15/1993	. 0		Radionuclide
59593		0		VOC
59593		0		Metal
		<u>_</u>		PCB
59593		- 0	1	6 Pesticide
59593		0		Radionuclide
59593				SVOC
59593				6 VOC
59593				6 VOC
59593		. 4		B VOC
59593				
59593				0 VOC
59593		. 6		2 Metal
59593				2 PCB
59593	6/15/1993			2 Pesticide
59593	6/15/1993			2 Radionuclide
59593		- (2 SVOC
59593		(6 1	2 VOC
59593		10		2 VOC
59593		14.4		4 Metal
5959				4 PCB
5959				4 Pesticide
5959				4 Radionuclide
				.4 SVOC
5959				4 VOC
5959			0	2 Metal
5979	6/11/1993		<u> </u>	Livictor

Table 1
Sampling and Analytical Summary for OLF Soil

59793	6/11/1993	0		Radionuclide
59793	6/11/1993	0		voc
59793	6/11/1993	2		VOC
59793	6/11/1993	0		Metal
59793	6/11/1993	0	5.3	PCB
59793	6/11/1993	0	5.3	Pesticide
59793	6/11/1993	0	5.3	Radionuclide
59793	6/11/1993	0	5.3	SVOC
59793	6/11/1993	o		VOC
59793	6/11/1993	5.3		voc
	6/11/1993	7.3		VOC
59793	6/11/1993	5.3		Metal
59793	6/11/1993	5.3	11.3	
59793		5.3		Pesticide
59793	6/11/1993			Radionuclide
59793	6/11/1993	5.3		
59793	6/11/1993	5.3		SVOC
59793	6/11/1993	5.3		VOC
59793	6/11/1993	9.3		voc
59793	6/11/1993	13.3		Metal
59793	6/11/1993	13.3		PCB
59793	6/11/1993	13.3		Pesticide
59793	6/11/1993	13.3		Radionuclide
59793	6/11/1993	13.3		SVOC
59793	6/11/1993	13.3	15.3	VOC
60993	6/23/1993	0	2	VOC
60993	6/23/1993	2	4	VOC
60993	6/23/1993	0		Metal
60993	6/23/1993	0		РСВ
60993	6/23/1993	0		Pesticide
60993	6/23/1993	0		Radionuclide
	6/23/1993	0		SVOC
60993	6/23/1993			VOC
60993	6/23/1993	4		VOC
60993	6/23/1993	6		voc
60993	6/23/1993	2		voc
61093	6/23/1993	- 4		VOC
61093		6		VOC
61093	6/23/1993	8		VOC
61093	6/23/1993	6		Metal
61093	6/23/1993			PCB
61093	6/23/1993	6		Pesticide
61093	6/23/1993	6		
61093	6/23/1993	6		Radionuclide
61093	6/23/1993	6		SVOC
61093	6/23/1993	6		VOC
61093	6/23/1993	12		VOC
63193	6/22/1993	0		VOC
63193	6/22/1993	2		VOC
63193	6/22/1993	0		Metal
63193	6/22/1993	0		Radionuclide
63193		4		VOC
63193		6		VOC
63193		8	10	VOC
63193		<u>6</u>		2 Metal
63193		6		2 PCB
63193		6		2 Pesticide
63193		6		2 Radionuclide
03193	OIZZI 1000	<u>_</u>	<u> </u>	

Table 1
Sampling and Analytical Summary for OLF Soil

63193	6/22/1993	6	12	SVOC
63193	6/22/1993	6	12	VOC
63193	6/22/1993	10	12	VOC
63193	6/22/1993	12	14	VOC
63193	6/22/1993	14	16	VOC
63193	6/22/1993	16	18	VOC
63193	6/22/1993	12	20	Metal
63193	6/22/1993	12	20	PCB
63193	6/22/1993	12	20	Pesticide
63193	6/22/1993	12	20	Radionuclide
63193	6/22/1993	12	20	SVOC
63193	6/22/1993	12		voc
		18		VOC
63193	6/22/1993	18		JVUC

Table 2
Sampling and Analytical Summary for OLF Groundwater

JEMES!	sion positiones	ล่อสเปลเดิ		તાંમીક્ષ્યાનાં લેવા	Parificalitans (%)
Library Carlo	Collegion Data	Manifest Change	la perifera de la contesta de la con	Icalesias Cale	Manya Grand
581	2/6/1992		581	2/6/1992	Metal
581		Radionuclide	581		Radionuclide
581	2/6/1992		10994		
581	2/6/1992		10994	9/2/1994	
10994	6/21/1994		10994	11/30/1994	
10994	6/21/1994		10994	2/8/1995	
10994			10994		Radionuclide
10994			10994	5/24/1995	
10994	6/21/1994		10994		Radionuclide
10994			10994	11/1/1995	
10994			10994		Radionuclide
10994		Pesticide	10994	3/14/1996	
10994			10994		Radionuclide
10994	9/2/1994		10994	6/7/1996	
10994			10994		Radionuclide
10994			10994	9/5/1996	
10994	11/30/1994		10994	11/20/1996	
10994			10994		Radionuclide
10994			10994	6/25/1997	
10994			10994	12/16/1997	
10994		Radionuclide	10994		Radionuclide
10994			10994		Radionuclide
10994			10994		
10994			10994		Radionuclide
10994			10994		
10994			10994		Radionuclide
10994		Radionuclide	10994		
10994			10994		Radionuclide
10994			10994		
			10994		Radionuclide
10994		Radionuclide	10994		
10994			10994		Radionuclide
10994		Radionuclide	10994	2/8/2002	
10994 10994			10994		Radionuclide
			10994		
10994			10994		Radionuclide
10994		Radionuclide	10994		
10994			10994		Radionuclide
10994					
10994		Radionuclide	10994		
10994		Radionuclide	10994		Radionuclide
10994			10994		
10994			11094		
10994		Radionuclide	11094		Radionuclide
10994			11094		
10994			11094		Radionuclide
10994		Radionuclide	11094		
10994			11094		Radionuclide
10994			20697		
10994			20697		Radionuclide
10994	7/14/1998	VOC	20797	8/11/2004	Metal

Table 2
Sampling and Analytical Summary for OLF Groundwater

	7/4/4000 NA/OD	20797	8/31/2004 Radionuclide
10994	7/14/1998 WQP	43392	9/22/1993 Radionuclide
10994	9/24/1998 VOC	43392	11/30/1993 Metal
10994	1/28/1999 Metal	43392	11/30/1993 Radionuclide
10994	1/28/1999 VOC	43392	3/4/1994 Radionuclide
10994	1/28/1999 WQP 7/19/1999 VOC	43392	5/18/1994 Metal
10994	7/19/1999 WQP	43392	5/18/1994 Radionuclide
10994	1/24/2000 VOC	43392	8/18/1994 Metal
10994	1/24/2000 WQP	43392	8/18/1994 Radionuclide
10994	8/14/2000 VOC	43392	3/1/1995 Metal
10994	8/14/2000 WQP	43392	3/1/1995 Radionuclide
10994	1/11/2001 VOC	43392	5/18/1995 Metal
10994	1/11/2001 WQP	43392	5/18/1995 Radionuclide
10994		43392	10/18/1995 Radionuclide
10994	8/14/2001 VOC	43392	1/17/1996 Radionuclide
10994	1/31/2002 VOC	43392	5/22/1996 Radionuclide
10994	2/8/2002 WQP	43392	8/29/1996 Metal
10994	7/15/2002 VOC	43392	11/12/1996 Metal
10994	7/23/2002 WQP	43392	11/12/1996 Radionuclide
10994	1/14/2003 VOC	43392	6/3/1997 Metal
10994	1/14/2003 WQP	43392	11/20/1997 Metal
10994	9/23/2003 VOC	43392	7/22/1998 Metal
10994	9/23/2003 WQP	43392	2/2/1999 Metal
11094	12/20/1994 Metal	43392	2/2/1999 Radionuclide
11094	12/20/1994 PCB	43392	7/20/1999 Metal
11094	12/20/1994 Pesticide	43392	7/20/1999 Radionuclide
11094	12/20/1994 Radionuclide	43392	1/25/2000 Metal
11094	12/20/1994 SVOC	43392	1/25/2000 Radionuclide
11094	12/20/1994 VOC	43392	9/7/2000 Metal
11094	12/20/1994 WQP	43392	9/7/2000 Radionuclide
11094	2/10/1995 Metal	43392	3/13/2001 Metal
11094	2/10/1995 PCB	43392	3/13/2001 Radionuclide
11094	2/10/1995 Pesticide	43392	7/18/2001 Metal
11094	2/10/1995 Radionuclide	43392	7/18/2001 Radionuclide
11094	2/10/1995 SVOC	43392	2/28/2002 Metal
11094	2/10/1995 VOC	43392	3/6/2002 Radionuclide
11094	2/10/1995 WQP	43392	8/21/2002 Radionuclide
11094	5/22/1995 Metal	43392	9/6/2002 Metal
11094	5/22/1995 Radionuclide	43392	9/11/2003 Metal
11094	5/22/1995 VOC	43392	9/11/2003 Radionuclide
11094	5/22/1995 WQP	56594	12/22/1994 Metal
11094	5/27/2003 VOC	56594	12/22/1994 Radionuclide
20197	5/22/2001 VOC	56594	4/25/1995 Metal
20397	5/17/2001 VOC	56594	4/25/1995 Radionuclide
20597	5/22/2001 VOC	56594	4/28/2003 Metal
20697	9/26/1997 VOC	56994	2/3/1995 Metal
20697	5/18/2001 VOC	56994	2/3/1995 Radionuclide
20697	7/15/2004 VOC	56994	5/16/1995 Metal
20797	7/30/1997 VOC	56994	5/16/1995 Radionuclide
20797	5/17/2001 VOC	56994	8/9/2004 Metal
20797	7/15/2004 VOC	56994	8/9/2004 Radionuclide
21097	5/18/2001 VOC	57094	
21097	7/15/2004 VOC	57094	0/11/2001/11/000

Table 2
Sampling and Analytical Summary for OLF Groundwater

	4044400015	Padianualida	57094	8/11/2004	Radionuclide
43392	12/14/1992 F		57594	4/12/1995	
43392	12/14/1992 V		57594		Radionuclide
43392	12/14/1992 V		5786	4/8/1987	
43392	9/22/1993 F		5786	2/22/1990	
43392	9/22/1993 \		5786		Radionuclide
43392	9/22/1993 V		5786	5/11/1990	
43392	11/30/1993 F		5786	7/26/1990	
43392	11/30/1993		5786		Radionuclide
43392	11/30/1993		5786		Radionuclide
43392	3/4/1994		5786	3/29/1991	
43392	3/4/1994 \		5786		Radionuclide
43392		Radionuclide	5786	5/22/1991	
43392	5/18/1994		5786		Radionuclide
43392	5/18/1994 \				Radionuclide
43392		Radionuclide	5786 5786	2/18/1992	
43392	8/18/1994		5786 5786		Radionuclide
43392	8/18/1994	WQP	5786	4/29/1992	
43392		Radionuclide	5786		Radionuclide
43392	12/6/1994		5786	3/17/1993	
43392	12/6/1994		5786		Radionuclide
43392		Radionuclide	5786		
43392	3/1/1995		5786	6/22/1993	
43392	3/1/1995		5786		Radionuclide
43392	5/18/1995	Radionuclide	5786	5/19/1994	
43392	5/18/1995		5786		Radionuclide
43392	5/18/1995		5786	2/28/1995	
43392		Radionuclide	5786		Radionuclide
43392	10/18/1995	VOC	5786	5/22/1995	
43392	1/17/1996	Radionuclide	5786		Radionuclide
43392	1/17/1996	VOC	57894	1/22/1995	
43392	5/22/1996	Radionuclide	57894		Radionuclide
43392	5/22/1996		57894	4/25/1995	
43392	8/29/1996	Radionuclide	57894	***	Radionuclide
43392	8/29/1996		57994	5/11/199	
43392	8/29/1996		58094	12/21/199	
43392		Radionuclide	58094		Radionuclide
43392	11/12/1996		58094		
43392	11/12/1996		58094		Radionuclide
43392	6/3/1997		58194	5/2/199	
43392	11/20/1997		58194		5 Radionuclide
43392	7/22/1998		58494		5 Metal
43392		Radionuclide	58494		5 Radionuclide
43392	2/2/1999		58494		
43392		Radionuclide	58594	12/21/199	
43392	7/20/1999		58594	12/21/199	4 Radionuclide
43392		Radionuclide	58594		
	1/25/2000		58594		5 Radionuclide
43392		Radionuclide	59194		
43392	9/7/2000		59194		5 Radionuclide
43392	3/1/2001		59194		4 Metal
43392		Radionuclide	59194		4 Radionuclide
43392			59294		4 Metal
43392	//18/2001	Radionuclide		1. 0.200	

Table 2 Sampling and Analytical Summary for OLF Groundwater

Metal	3661/6/8	£6969	VOC	0661/11/9	9849
Radionuclide		26263		2/22/1990	9849
	9661/11/1	£6969		2/22/1990	9878
Radionuclide		£6969 _.	Radionuclide	2/22/1990	9878
	10/24/1994	£6969		12/15/1989	9878
Radionuclide		66969		7861/8/4	9849
	1 661/61/8	£6969		7861/8/4	9878
Radionuclide		£6969	Radionuclide		9878
	1661/6/9	£6969		4/12/1995	7 6978
Radionuclide		£6969		4/12/1995	76949
	3/14/1994	£6969		4/12/1995	1 6949
		£6969	Radionuclide		76978
Radionudide		£6969 £6969		3001/21/1	7697 8
	£661/01/11			4/12/1995	76978
Radionuclide		86969		8/11/2004	76078
	£661/£1/8	<u> 26969</u>			16023
Radionudide		<u>86969</u>		2/8/2003	16073
	£661/9Z/9	£6969		1002/11/9	
Radionudide		£6 1 69		9661/1/9	76076
	9661/6/9	<u> 59493</u>		9661/1/9	76073
Radionudide		£6 1 69		₩00Z/6/8	76699
Metal	3/6/1862	£6 1 69		1002/9/9	≯6699
Radionuclide		<u> 26163</u>		2661/91/9	₹6699
Metal	3661/4/1	£6769		3661/91/9	⊅669 9
Radionuclide	10/21/1994	£6169		9661/91/9	⊅669 9
lsteM	10/21/1994	£6463	Radionuclide		1 6699
Radionuclide	t-661/61/8	29493		2/3/1995	Þ669 <u>9</u>
Metal	1661/61/8	£6 7 69		2/3/1995	1 6699
Radionudide	1 661/6/9	£6 1 69	SVOC	2/3/1995	1 6699
Metal	7661/6/9	£6 1 69	Radionuclide	2/3/1662	1 6699
Radionuclide	3/14/1994	£6 1 69	Pesticide	2/3/1995	1 6699
	3/14/1994	£6 1 69	PCB	2/3/1885	1 6699
Radionuclide		£6 1 69	70C	4/28/2003	1 6999
	11/9/1993	£6769	Radionuclide	4/28/2003	1 6999
Radionuclide		£6 7 69	WQP	9661/97/7	1 6999
	E661/11/8	£6 † 69	70C	9661/97/7	76999
Radionuclide		26463	SAOC	4\25\1895	1 6999
	6/25/1993	£6 1 69	Radionuclide		76999
Radionuclide		£6£69	Metal	4/25/1995	1 6999
Radionuclide		£6£69		12/22/1994	76999
	9661/05/4	£6£6 9		12/22/1994	76999
Radionuclide		£6£6 9		12/22/1994	76999
	9661/91/11	£6593	2adionuclide		76999
Radionuclide		£6563		12/22/1994	76999
	9661/92/7	£6869		12/22/1994	76999
Radionuclide		£6869 E6869	Sadionuclide		Z62£Þ
	3661/8/E	26363		8/27/2003	43392
				3/27/2003	Z625A
Radionuclide		£6869	Sadionuclide		43392
Radionuclide		26363		7/9/2002	43392
	\$651/0Z/9	£6269 26066	Sadionuclide		43392
Radionuclide		26269			43392
	3/29/1994	<u> 26869</u>		Z\Z8\Z00Z	43392
Radionuclide	8/3/2004	29294		1/18/2001	V3303

Table 2
Sampling and Analytical Summary for OLF Groundwater

			3/9/1995 Radionuclide
5786	5/11/1990 WQP	59593	
5786	7/26/1990 Radionuclide	59593	6/14/1995 Metal
5786	7/26/1990 VOC	59593	6/14/1995 Radionuclide
5786	7/26/1990 WQP	59594	1/25/1995 Metal
5786	10/12/1990 VOC	59594	1/25/1995 Radionuclide
5786	3/29/1991 Radionuclide	59594	5/15/1995 Metal
5786	3/29/1991 VOC	59594	5/15/1995 Radionuclide
5786	3/29/1991 WQP	59594	7/28/2004 Metal
5786	5/22/1991 Radionuclide	59594	7/28/2004 Radionuclide
5786	5/22/1991 VOC	59694	3/8/1995 Metal
5786	5/22/1991 WQP	59694	3/8/1995 Radionuclide
5786	9/16/1991 Radionuclide	59694	5/23/1995 Metal
5786	9/16/1991 VOC	59694	5/23/1995 Radionuclide
5786	9/16/1991 WQP	59793	1/15/1995 Radionuclide
5786	12/14/1991 Radionuclide	59793	5/12/1995 Metal
5786	12/14/1991 VOC	59793	5/12/1995 Radionuclide
5786	12/14/1991 WQP	59894	3/8/1995 Metal
5786	2/18/1992 Metal	59894	3/8/1995 Radionuclide
5786	2/18/1992 Radionuclide	59894	5/16/1995 Metal
5786	2/18/1992 VOC	59894	5/16/1995 Radionuclide
5786	2/18/1992 WQP	59993	1/23/1995 Radionuclide
5786	4/29/1992 Metal	59993	5/11/1995 Metal
5786	4/29/1992 Radionuclide	60093	5/9/1995 Metal
5786	4/29/1992 VOC	60093	5/9/1995 Radionuclide
5786	4/29/1992 WQP	60293	1/22/1995 Metal
5786	3/17/1993 Radionuclide	60293	1/22/1995 Radionuclide
5786	3/17/1993 VOC	60293	4/20/1995 Metal
	3/17/1993 WQP	60293	4/20/1995 Radionuclide
5786	6/22/1993 Radionuclide	60393	5/10/1995 Metal
5786	6/22/1993 VOC	60393	5/10/1995 Radionuclide
5786	6/22/1993 WQP	60593	5/4/1995 Metal
5786	2/25/1994 Radionuclide	60593	5/4/1995 Radionuclide
5786	2/25/1994 VOC	60693	5/4/1995 Metal
5786	2/25/1994 WQP	60693	
5786	5/19/1994 Radionuclide	60893	
5786	5/19/1994 VOC	60893	
5786	5/19/1994 WQP	60893	
5786			
5786	2/28/1995 Radionuclide	60893	
5786	2/28/1995 VOC	60993	
5786	2/28/1995 WQP		
5786	5/22/1995 Radionuclide	61093	
5786	5/22/1995 VOC	61093	
5786	5/22/1995 WQP	61093	
57894	1/22/1995 Metal	61093	
57894	1/22/1995 PCB	61293	
57894	1/22/1995 Pesticide		
57894	1/22/1995 Radionuclide		
57894	1/22/1995 SVOC	61293	
57894	1/22/1995 VOC	62793	
57894	1/22/1995 WQP	62793	
57894	4/25/1995 Metal	62793	
57894	4/25/1995 Radionuclide	62893	7/13/1993 Radionuclide

Table 2
Sampling and Analytical Summary for OLF Groundwater

55004	4DEMODE CVOC	· · · · · · · · · · · · · · · · · · ·	62893	1/18/1995	Metal
57894	4/25/1995 SVOC 4/25/1995 VOC	<u>, </u>	62893		Radionuclide
57894			62893	4/18/1995	
57894	4/25/1995 WQP		62893		Radionuclide
57994	5/11/1995 VOC		63193		Radionuclide
57994	5/29/2001 VOC		63193	1/10/1995	
57994	8/10/2004 VOC		63193		Radionuclide
58094	12/21/1994 PCB		63193	4/17/1995	
58094	12/21/1994 Pestic		63193		Radionuclide
58094	12/21/1994 Radio		63893	1/5/1995	
58094	12/21/1994 SVOC		63893		Radionuclide
58094			63893	4/18/1995	
58094	12/21/1994 WQP		63893		Radionuclide
58094	4/26/1995 Metal		63993	1/5/1995	
58094	4/26/1995 Radio		63993		Radionuclide
58094	4/26/1995 SVO	 +	63993	4/18/1995	
58094	4/26/1995 VOC		63993		Radionuclide
58094	4/26/1995 WQP		64093	1/5/1995	
58094	5/24/2001 VOC		64093		Radionuclide
58194	5/2/1995 Meta		64093	4/18/1995	
58194	5/2/1995 Radio		64093		Radionuclide
58194	5/2/1995 SVO		7086	10/2/1986	
58194	5/2/1995 VOC		7086	5/18/1987	
58194	5/2/1995 WQP		7086	5/27/1987	
58194	5/23/2001 VOC		7086	7/6/1987	
58494	5/3/1995 Meta		7086		Radionuclide
58494	5/3/1995 Radio			12/8/1987	
58494	5/3/1995 SVO		7086		Radionuclide
58494	5/3/1995 VOC		7086 7086	2/15/1988	
58494	5/3/1995 WQF				Radionuclide
58494	8/21/1997 VOC		7086 7086	4/7/1988	
58494	6/6/2001 VOC				Radionuclide
58494	7/10/2003 VOC		7086		
58594	12/21/1994 PCB		7086		Radionuclide
58594	12/21/1994 Pest		7086 7086	10/18/1988	
58594	12/21/1994 Radi				
58594	12/21/1994 SVO	<u>C</u>	7086		Radionuclide
58594	12/21/1994 VOC		7086 7086		
58594	12/21/1994 WQI		7086 7086		
58594	4/25/1995 Meta				Radionuclide
58594	4/25/1995 Rad		7086		
58594	4/25/1995 SVC		7086		
58594	4/25/1995 VOC		7086		
58594	4/25/1995 WQ		7086	<u> </u>	
58594	8/21/1997 VOC		7086		Radionuclide
58594	5/21/2001 VOC		7086		
58693	5/18/1993 Met		7086		
58693	5/18/1993 Rad		7086		Radionuclide
58693	5/18/1993 VO		7086		
59194	6/27/1995 Rad		7086		1 Radionuclide
59194	6/27/1995 SVC		7086		
59194	6/27/1995 VO		7086		1 Radionuclide
59194	.6/27/1995 WQ	P	7086	12/6/199	Tivietai



Table 2
Sampling and Analytical Summary for OLF Groundwater

504041	7/31/2003 VOC	7086	12/6/1991 Radionuclide
59194	8/9/2004 VOC	7086	2/17/1992 Metal
59194	5/28/2003 VOC	7086	2/17/1992 Radionuclide
59294	8/3/2004 VOC	7086	4/28/1992 Metal
59294	3/29/1994 Metal	7086	4/28/1992 Radionuclide
59393	3/29/1994 Radionuclide	7086	8/14/1992 Metal
59393	3/29/1994 SVOC	7086	8/14/1992 Radionuclide
59393	3/29/1994 VOC	7086	11/6/1992 Metal
59393	3/29/1994 WQP	7086	11/6/1992 Radionuclide
59393	5/20/1994 Metal	7086	3/8/1993 Metal
59393	5/20/1994 Radionuclide	7086	3/8/1993 Radionuclide
59393	5/20/1994 VOC	7086	6/3/1993 Metal
59393	6/8/1994 Radionuclide	7086	6/3/1993 Radionuclide
59393		7086	9/20/1993 Metal
59393	6/8/1994 SVOC	7086	9/20/1993 Radionuclide
59393	6/8/1994 VOC	7086	12/10/1993 Metal
59393	6/8/1994 WQP	7086	12/10/1993 Radionuclide
59393	8/19/1994 SVOC	7086	2/23/1994 Metal
59393	8/19/1994 VOC	7086	2/23/1994 Radionuclide
59393	8/19/1994 WQP	7086	5/16/1994 Metal
59393	10/26/1994 VOC	7086	5/16/1994 Radionuclide
59393	10/26/1994 WQP	7086	8/25/1994 Metal
59393	1/7/1995 Metal	7086	8/25/1994 Radionuclide
59393	1/7/1995 Radionuclide	7086	11/21/1994 Metal
59393	1/7/1995 VOC	7086	11/21/1994 Radionuclide
59393	3/8/1995 Metal	7086	3/10/1995 Metal
59393	3/8/1995 SVOC	7086	3/10/1995 Radionuclide
59393	3/8/1995 VOC	7086	11/9/1995 Metal
59393	3/8/1995 WQP	7086	11/9/1995 Radionuclide
59393	4/26/1995 Metal	7086	4/26/1996 Metal
59393	4/26/1995 Radionuclide	7086	4/26/1996 Radionuclide
59393	4/26/1995 SVOC	7086	7/18/1996 Metal
59393	4/26/1995 VOC	7086	7/18/1996 Radionuclide
59393	4/26/1995 WQP	7086	11/25/1996 Metal
59393	11/16/1995 Radionuclide	7086	11/25/1996 Radionuclide
59393	11/16/1995 VOC	7086	7/31/1997 Metal
59393	11/16/1995 WQP	7086	2/27/1998 Metal
59393	4/30/1996 Radionuclide	7086	7/28/1998 Metal
59393	4/30/1996 VOC	7086	7/28/1998 Radionuclide
59393	4/30/1996 WQP	7086	2/8/1999 Radionuclide
59393	11/8/1996 Radionuclide	7086	8/18/1999 Radionuclide
59393	11/8/1996 VOC	7086	2/7/2000 Metal
59393	11/8/1996 WQP	7086	2/7/2000 Radionuclide
59393	5/29/2003 VOC	7086	7/31/2000 Radionuclide
59394	8/21/1997 VOC	7086	2/23/2001 Metal
59493	6/25/1993 Metal	7086	2/23/2001 Radionuclide
59493	6/25/1993 Radionuclide	7086	9/10/2001 Metal
59493	6/25/1993 SVOC		9/10/2001 Radionuclide
59493	6/25/1993 VOC	7086	3/14/1995 Metal
59493	6/25/1993 WQP	71494	3/14/1995 Radionuclide
59493	8/11/1993 Metal	71494	5/16/1995 Metal
59493	8/11/1993 Radionuclide	71494	5/16/1995 Radionuclide
59493	8/11/1993 SVOC	71494	Ji Toi 1995 Radionabildo

Table 2
Sampling and Analytical Summary for OLF Groundwater

	•				0/40/4004	Matal
	59493	8/11/1993		P416689	2/16/1994	
	59493	8/11/1993	WQP	P416689	4/29/1994	
	59493	11/9/1993	Metal	P416689	8/19/1994	
	59493	11/9/1993	Radionuclide	P416689	4/25/1995	
	59493	11/9/1993	SVOC	P416689		Radionuclide
<u> </u>	59493	11/9/1993	VOC	P416689		Radionuclide
-	59493	11/9/1993		P416689		Radionuclide
 	59493	3/14/1994		P416689	7/17/1996	Radionuclide
-	59493		Radionuclide	P416689	1/28/1997	
	59493	3/14/1994		P416689	6/3/1997	Metal
	59493	3/14/1994		P416689	12/3/1997	
\vdash	59493	3/14/1994		P416689	4/29/1998	Metal
├	59493	5/9/1994		P416689	10/19/1998	Metal
 	59493		Radionuclide	P416689	4/26/1999	Metal
-	59493	5/9/1994		P416689	10/19/1999	Metal
<u> </u>	59493	5/9/1994		P416689	5/8/2000	Metal :
		5/9/1994		P416689	5/8/2000	Radionuclide
<u></u>	59493	8/19/1994		P416689	12/12/2000	Metal
	59493		Radionuclide	P416689		Radionuclide
.	59493	8/19/1994 8/19/1994		P416689	4/9/2001	
<u> </u>	59493	8/19/1994 8/19/1994		P416689		Radionuclide
<u> </u>	59493			P416689	12/12/2001	
<u> </u>	59493	8/19/1994		P416689		Radionuclide
 	59493	10/21/1994		P416689		Radionuclide
<u> </u>	59493		Radionuclide	P416689	5/16/2002	
<u> </u>	59493	10/21/1994		P416689	10/22/2002	
<u> </u>	59493	10/21/1994		P416689		Radionuclide
<u> </u>	59493	10/21/1994		P416689		Metal
<u> </u>	59493	1/4/1995	Pesticide	P416689		Radionuclide
<u> </u>	59493		Radionuclide	P416689	6/10/2003	
<u> </u>	59493			P416689	7/9/2003	
<u> </u>	59493	1/4/1995		P416689	3/16/2004	
<u> </u>	59493	1/4/199		P416689	4/19/2004	
<u> </u>	59493	1/4/199		P416689	5/25/2004	
· L	59493	3/9/199		P410009	3/20/200-	TILLOCO.
<u> </u>	59493		Radionuclide	-	• • •	
L	59493		SVOC	-{		
	59493	3/9/199		4		
	59493	3/9/199		_		
<u> </u>	59493	6/9/199		4		
Ŀ	59493		5 Radionuclide	4		
	59493		5 SVOC			
	59493	6/9/199		.		
	59493		5 WQP			
	59493	7/31/200		≟	·:	
.	59593	6/25/199		_		· .
.	59593		3 Radionuclide		•	
	59593	6/25/199	3 SVOC		•	
	59593	6/25/199	3 VOC	∐ .		
· · ·	59593	6/25/199	3 WQP			•
	59593	8/13/199				
· -	59593		3 Radionuclide			
 	59593		3 SVOC			
						

Table 2
Sampling and Analytical Summary for OLF Groundwater

59593	8/13/1993 VOC
59593	8/13/1993 WQP
59593	11/10/1993 Metal
59593	11/10/1993 Radionuclide
59593	11/10/1993 SVOC
59593	11/10/1993 VOC
59593	11/10/1993 WQP
59593	3/14/1994 Metal
59593	3/14/1994 Radionuclide
59593	3/14/1994 SVOC
59593	3/14/1994 VOC
59593	3/14/1994 WQP
59593	5/9/1994 Metal
. 59593	5/9/1994 Radionuclide
59593	5/9/1994 SVOC
59593	5/9/1994 VOC
59593	5/9/1994 WQP
59593	8/19/1994 Metal
59593	8/19/1994 Radionuclide
59593	8/19/1994 SVOC
59593	8/19/1994 VOC
59593	8/19/1994 WQP
59593	10/24/1994 Metal
59593	10/24/1994 Radionuclide
59593	10/24/1994 SVOC
59593	10/24/1994 VOC
59593	10/24/1994 WQP
59593	1/11/1995 Radionuclide
59593	1/11/1995 WQP
59593	3/9/1995 Metal
59593	3/9/1995 Radionuclide
59593	3/9/1995 SVOC
59593	3/9/1995 VOC
59593	3/9/1995 WQP
59593	6/14/1995 Metal
59593	6/14/1995 Radionuclide
59593	6/14/1995 SVOC
59593	6/14/1995 VOC
59593	6/14/1995 WQP
59593	5/29/2003 VOC
59594	1/25/1995 PCB
59594	1/25/1995 Pesticide
59594	1/25/1995 Radionuclide
59594	1/25/1995 SVOC
59594	
59594	
59594	
59594	5/15/1995 SVOC
59594	
59594	5/15/1995 WQP
59594	
59694	3/8/1995 PCB

Table 2
Sampling and Analytical Summary for OLF Groundwater

59694	3/8/1995 Pesticide
59694	3/8/1995 Radionuclide
59694	3/8/1995 SVOC
59694	3/8/1995 VOC
59694	5/23/1995 PCB
59694	5/23/1995 Pesticide
59694	5/23/1995 Radionuclide
59694	5/23/1995 SVOC
59694	5/23/1995 VOC
59694	5/23/1995 WQP
59694	7/31/2003 VOC
59793	1/15/1995 Radionuclide
59793	1/15/1995 VOC
59793	5/12/1995 Metal
59793	5/12/1995 Radionuclide
59793	5/12/1995 SVOC
59793	5/12/1995 VOC
59793	5/12/1995 WQP
59793	5/17/2001 VOC
59794	7/10/2003 VOC
59894	3/8/1995 PCB
59894	3/8/1995 Pesticide
59894	3/8/1995 Radionuclide
59894	3/8/1995 SVOC
59894	3/8/1995 VOC
59894	3/8/1995 WQP
59894	5/16/1995 Radionuclide
59894	5/16/1995 SVOC
59894	5/16/1995 VOC
59894	5/16/1995 WQP
59993	7/6/1993 Radionuclide
59993	7/6/1993 VOC
59993	1/23/1995 Radionuclide
59993	1/23/1995 VOC
59993	6/7/2001 VOC
60093	7/6/1993 VOC
60093	5/9/1995 Metal
60093	5/9/1995 Radionuclide
60093	5/9/1995 SVOC
60093	5/9/1995 VOC
60093	5/9/1995 WQP
60293	7/6/1993 Metal
60293	7/6/1993 PCB
60293	7/6/1993 Pesticide
60293	7/6/1993 Radionuclide
60293	7/6/1993 SVOC
60293	7/6/1993 VOC
60293	7/6/1993 WQP
60293	1/22/1995 Metal
60293	1/22/1995 PCB
	1/22/1995 Pesticide
60293	1/22/1995 Radionuclide
60293	11221 1330 I Nationalide



Table 2
Sampling and Analytical Summary for OLF Groundwater

· ·	
60293	1/22/1995 SVOC
60293	1/22/1995 VOC
60293	1/22/1995 WQP
60293	4/20/1995 Metal
60293	4/20/1995 Radionuclide
60293	4/20/1995 SVOC
60293	4/20/1995 VOC
60293	4/20/1995 WQP
60393	5/10/1995 Radionuclide
60393	5/10/1995 VOC
60493	7/13/1993 VOC
60493	7/29/2003 VOC
60593	7/7/1993 VOC
60593	5/4/1995 Metal
60593	5/4/1995 Radionuclide
60593	5/4/1995 SVOC
60593	5/4/1995 VOC
60593	5/4/1995 WQP
60693	7/7/1993 VOC
60693	5/4/1995 Metal
60693	5/4/1995 Radionuclide
60693	5/4/1995 SVOC
60693	5/4/1995 VOC
60693	5/4/1995 WQP
60893	7/7/1993 VOC
60893	1/26/1995 Metal
60893	1/26/1995 Radionuclide
60893	1/26/1995 SVOC
60893	1/26/1995 VOC
60893	4/20/1995 Metal
60893	4/20/1995 Radionuclide
60893	4/20/1995 SVOC
60893	4/20/1995 VOC
60893	4/20/1995 WQP
60993	5/10/1995 VOC
61093	7/13/1993 Metal
61093	7/13/1993 PCB
61093	7/13/1993 Pesticide
61093	7/13/1993 Radionuclide
61093	7/13/1993 SVOC
61093	7/13/1993 VOC
61093	7/13/1993 WQP
61093	1/25/1995 Metal
61093	1/25/1995 PCB
61093	1/25/1995 Pesticide
61093	1/25/1995 Radionuclide
61093	1/25/1995 SVOC
61093	1/25/1995 VOC
61093	1/25/1995 WQP
61093	4/24/1995 Metal
61093	4/24/1995 Radionuclide
61093	4/24/1995 SVOC
0 1035	

Table 2
Sampling and Analytical Summary for OLF Groundwater

	40 44005h 400
61093	4/24/1995 VOC
61093	4/24/1995 WQP
61093	6/23/2004 VOC
61293	1/7/1995 Radionuclide
61293	1/7/1995 VOC
61293	5/22/1995 SVOC
61293	5/22/1995 VOC
61293	5/22/1995 WQP
61293	5/2/2003 VOC
61293	8/2/2004 Radionuclide
61293	8/2/2004 VOC
62793	7/13/1993 VOC
62793	1/23/1995 Radionuclide
62793	1/23/1995 VOC
62793	5/11/1995 VOC
62793	5/29/2001 VOC
62893	7/13/1993 VOC
62893	1/18/1995 Metal
62893	1/18/1995 Radionuclide
62893	2/1/1995 VOC
62893	4/18/1995 Metal
62893	4/18/1995 Radionuclide
62893	4/18/1995 SVOC
62893	4/18/1995 VOC
62893	4/18/1995 WQP
62893	8/21/1997 VOC
62893	5/29/2001 Radionuclide
62893	5/29/2001 VOC
62893	5/27/2003 VOC
63193	7/12/1993 Metal
63193	7/12/1993 PCB
63193	7/12/1993 Pesticide
63193	7/12/1993 SVOC
63193	7/12/1993 VOC
63193	
63193	7/12/1993 WQP 1/10/1995 Radionuclide
63193	
63193	1/10/1995 SVOC
63193	1/10/1995 VOC
63193	1/10/1995 WQP
63193	4/17/1995 Metal
63193	4/17/1995 Radionuclide
63193	4/17/1995 SVOC
63193	4/17/1995 VOC
63193	4/17/1995 WQP
63193	8/21/1997 VOC
63193	5/21/2001 VOC
63193	5/28/2003 VOC
63893	1/5/1995 PCB
63893	1/5/1995 Pesticide
63893	1/5/1995 Radionuclide
63893	1/5/1995 SVOC

Table 2
Sampling and Analytical Summary for OLF Groundwater

63893	1/5/1995 VOC
63893	1/5/1995 WQP
63893	4/18/1995 Metal
63893	4/18/1995 Radionuclide
63893	4/18/1995 SVOC
63893	4/18/1995 VOC
63893	4/18/1995 WQP
63993	1/5/1995 PCB
63993	1/5/1995 Pesticide
63993	1/5/1995 Radionuclide
63993	1/5/1995 SVOC
63993	1/5/1995 VOC
63993	1/5/1995 WQP
. 63993	4/18/1995 Metal
63993	4/18/1995 Radionuclide
63993	4/18/1995 SVOC
63993	4/18/1995 VOC
63993	4/18/1995 WQP
64093	1/5/1995 PCB
64093	1/5/1995 Pesticide
64093	1/5/1995 Radionuclide
64093	1/5/1995 SVOC
64093	1/5/1995 VOC
64093	1/5/1995 WQP
64093	4/18/1995 Metal
64093	4/18/1995 Radionuclide
64093	4/18/1995 SVOC
64093	4/18/1995 VOC
64093	4/18/1995 WQP
7086	10/2/1986 Metal
7086	10/2/1986 PCB
7086	10/2/1986 Pesticide
7086	10/2/1986 Radionuclide
7086	10/2/1986 VOC
7086	10/2/1986 WQP
7086	5/18/1987 Radionuclide
7086	5/18/1987 VOC
7086	5/18/1987 WQP
7086	5/27/1987 Radionuclide
7086	5/27/1987 VOC
7086	5/27/1987 WQP
7086	7/6/1987 VOC
7086	7/6/1987 WQP
7086	12/8/1987 VOC
7086	12/8/1987 WQP
7086	2/15/1988 VOC
7086	2/15/1988 WQP
7086	4/7/1988 VOC
7086	4/7/1988 WQP
7086	7/13/1988 WQP
7086	
7086	
7000	10/10/1000 1744

Table 2
Sampling and Analytical Summary for OLF Groundwater

7086	1/16/1989 VOC
7086	1/16/1989 WQP
7086	4/12/1989 VOC
7086	4/12/1989 WQP
7086	7/25/1989 VOC
7086	7/25/1989 WQP
7086	11/30/1989 Radionuclide
7086	11/30/1989 VOC
7086	11/30/1989 WQP
7086	2/22/1990 Radionuclide
7086	2/22/1990 VOC
7086	2/22/1990 WQP
7086	5/24/1990 Radionuclide
7086	5/24/1990 VOC
7086	5/24/1990 WQP
	7/20/1990 Radionuclide
7086	7/20/1990 VOC
7086	
7086	7/20/1990 WQP
7086	10/19/1990 Radionuclide
7086	10/19/1990 VOC
7086	10/19/1990 WQP
· 7086	5/14/1991 Radionuclide
7086	5/14/1991 VOC
7086	5/14/1991 WQP
. 7086	9/6/1991 Metal
7086	9/6/1991 Radionuclide
7086	9/6/1991 VOC
7086	9/6/1991 WQP
7086	12/6/1991 Metal
7086	12/6/1991 Radionuclide
7086	12/6/1991 VOC
7086	12/6/1991 WQP
7086	2/17/1992 Metal
7086	2/17/1992 Radionuclide
7086	2/17/1992 VOC
7086	2/17/1992 WQP
	4/28/1992 Metal
7086	4/28/1992 Radionuclide
7086	4/28/1992 VOC
7086	4/28/1992 WQP
7086	
7086	8/14/1992 Metal
7086	8/14/1992 Radionuclide
7086	8/14/1992 VOC
7086	8/14/1992 WQP
7086	11/6/1992 Metal
7086	11/6/1992 Radionuclide
7086	11/6/1992 VOC
7086	11/6/1992 WQP
7086	3/8/1993 Radionuclide
7086	3/8/1993 VOC
7086	3/8/1993 WQP
7086	6/3/1993 Radionuclide
7,000	

Table 2
Sampling and Analytical Summary for OLF Groundwater

7086	6/3/1993 VOC
7086	6/3/1993 WQP
7086	9/20/1993 Radionuclide
7086	9/20/1993 VOC
7086	9/20/1993 WQP
7086	12/10/1993 Radionuclide
7086	12/10/1993 VOC
7086	12/10/1993 WQP
7086	2/23/1994 Radionuclide
7086	2/23/1994 VOC
7086	2/23/1994 WQP
7086	5/16/1994 Radionuclide
7086	5/16/1994 VOC
7086	5/16/1994 WQP
	8/25/1994 Radionuclide
7086	0/25/1994 RadioHucide
7086	8/25/1994 VOC
7086	8/25/1994 WQP
7086	11/21/1994 Radionuclide
7086	11/21/1994 VOC
7086	11/21/1994 WQP
7086	3/10/1995 Radionuclide
7086	3/10/1995 VOC
7086	3/10/1995 WQP
7086	11/9/1995 Radionuclide
7086	11/9/1995 VOC
7086	11/9/1995 WQP
7086	4/26/1996 Radionuclide
7086	4/26/1996 VOC
7086	4/26/1996 WQP
7086	7/18/1996 Radionuclide
7086	7/18/1996 VOC
	7/18/1996 WQP
7086	11/25/1996 Radionuclide
7086	
7086	11/25/1996 VOC
7086	7/31/1997 Radionuclide
7086	7/31/1997 VOC
7086	7/31/1997 WQP
7086	2/27/1998 Radionuclide
7086	2/27/1998 VOC
7086	2/27/1998 WQP
7086	7/28/1998 VOC
7086	7/28/1998 WQP
7086	2/8/1999 Metal
7086	2/8/1999 VOC
7086	2/8/1999 WQP
7086	8/18/1999 Metal
7086	8/19/1999 VOC
7086	
7086	
7086	
7086	
7086	7/31/2000 Radionuclide

Table 2
Sampling and Analytical Summary for OLF Groundwater

7086	7/31/2000 VOC
7086	7/31/2000 WQP
7086	2/23/2001 VOC
7086	2/23/2001 WQP
7086	9/10/2001 VOC
7086	9/10/2001 WQP
7086	2/7/2002 Metal
7086	2/7/2002 Radionuclide
7086	2/7/2002 VOC
7086	2/7/2002 WQP
7086	3/11/2002 Metal
7086	4/15/2002 Metal
7086	5/16/2002 Metal
7086	9/4/2002 Metal
	9/4/2002 Radionuclide
7086	9/4/2002 VOC
7086	9/4/2002 WQP
7086	
7086	2/11/2003 Metal
7086	2/11/2003 Radionuclide
7086	2/11/2003 VOC
7086	2/11/2003 WQP
7086	8/26/2003 Metal
7086	8/26/2003 Radionuclide
7086	8/26/2003 VOC
7086	8/26/2003 WQP
7086	9/30/2003 Metal
7086	10/23/2003 Metal
7086	10/23/2003 Radionuclide
7086	10/23/2003 VOC
7086	5/12/2004 Metal
7086	5/12/2004 Radionuclide
7086	5/12/2004 VOC
71494	3/14/1995 PCB
71494	3/14/1995 Pesticide
71494	3/14/1995 Radionuclide
71494	3/14/1995 SVOC
71494	3/14/1995 VOC
71494	3/14/1995 WQP
	5/16/1995 PCB
71494	5/16/1995 Pesticide
71494	5/16/1995 Radionuclide
71494	5/16/1995 SVOC
71494	
71494	5/16/1995 VOC
71494	5/16/1995 WQP
71494	8/12/2003 VOC
P416689	11/22/1993 Radionuclide
P416689	11/22/1993 SVOC
P416689	11/22/1993 VOC
P416689	11/22/1993 WQP
P416689	2/16/1994 VOC
P416689	4/29/1994 Metal
P416689	4/29/1994 Radionuclide

Table 2
Sampling and Analytical Summary for OLF Groundwater

D440000	4/29/1994 VOC
P416689	8/19/1994 Radionuclide
P416689	8/19/1994 VOC
P416689	11/8/1994 Radionuclide
P416689	11/8/1994 VOC
P416689	
P416689	11/8/1994 WQP
P416689	1/31/1995 Radionuclide
P416689	1/31/1995 VOC
P416689	1/31/1995 WQP
P416689	4/25/1995 Metal
P416689	4/25/1995 Radionuclide
P416689	4/25/1995 VOC
P416689	8/16/1995 Radionuclide
P416689	8/16/1995 VOC
P416689	8/16/1995 WQP
P416689	10/17/1995 Radionuclide
P416689	10/17/1995 VOC
P416689	2/19/1996 Radionuclide
P416689	2/19/1996 VOC
P416689	4/30/1996 Radionuclide
P416689	4/30/1996 VOC
P416689	7/17/1996 Radionuclide
P416689	7/17/1996 VOC
P416689	7/17/1996 WQP
P416689	1/28/1997 VOC
P416689	6/3/1997 VOC
P416689	12/3/1997 VOC
P416689	3/12/1998 VOC
P416689	4/29/1998 VOC
P416689	10/19/1998 VOC
P416689	4/26/1999 Radionuclide
P416689	4/26/1999 VOC
P416689	10/19/1999 Radionuclide
	10/19/1999 VOC
P416689	5/8/2000 Radionuclide
P416689	5/8/2000 VOC
P416689	12/6/2000 VOC
P416689	12/29/2000 Radionuclide
P416689	12/29/2000 Nadio Idade
P416689	4/9/2001 VOC
P416689	4/30/2001 Radionuclide
P416689	12/4/2001 VOC
P416689	4/29/2002 VOC
P416689	6/12/2002 Radionuclide
P416689	10/14/2002 VOC
P416689	11/21/2002 Radionuclide
P416689	4/28/2003 VOC
P416689	5/6/2003 Radionuclide
P416689	10/22/2003 VOC
P416689	4/13/2004 VOC
P416689	6/22/2004 VOC
P416689	7/20/2004 VOC
P416689	8/17/2004 VOC

				imainti anono	EEOMS	G5/10/90 MQP	ZEOWSI	05/03/91 Redionucide	HOMS	IsteM 06/80/11	6E0MS
6/26/1991 Redionuctide	SM158	11/20/1880 AOC	960WS	IstoM P24-04-0	20003	OOA 06/01/90	zcows	lateM 19/50/20	HOMS	10/02/90 WQP	6COMS
6/26/1991 Metat		11/20/1890 Redionuciide	800VS	INIOM 19/80/CO	8M022	• 05/10/90 Redionucide		12/04/90 Redionuciide	HOMS	10/05/30 AOC	6COMS
ebibunolbaR 1991/81/8	EM159	11/20/1990 Metal		13/04/50 Redionicide	EM033	Material 00/01/20	80003	12/04/90 Metal	INOMS	10/05/80 SAOC	6COMS
S/16/1991 Metal	SW129	QDW 0691/8/8	9COM8	12/04/90 Metal	2003	4DW/08/11/40	20003	10/03/90 Metal	INOMS	10/02/90 Pesticide	SM038
4/9/1991 Redionucide	SM159	9/8/1880 /AOC		ebilounolba A 08/10/11	20003	OU/11/90 VOC	80003	1896W 06/50/60	HOMS	IsteM 06\20\01	SM039
haleM 1991/6/A	6ZIMS	ebibunoiba R 099 l \8\8	80008	lateM 06/70/11		20/8 06/11/10	260/03	ebilounolbs R 09/80/80	HOMS	90V13/90 VVQP	680008
3/28/1991 Radionucide	SM129	(a)+M 0661/8/8	900008	1920-M 08/10/01	20003	04/11/90 Pesticide	20003	hteM 09/80/80	HOMS	69/13/90 Radionuciide	SW039
3/28/1991 Metal	SW129	90W 0681/7\alpha	9COMS	hazeM 06VE1VE0	2003	(#19M 08/11/90	20003	07/05/90 Redionucide	HOMS	(#19M 06\£1\60	8E0MS
13/6/1990 Redionuciide	SW129	OOV 0881/778	9COVV8	ebilbunoibe R edionuciide	SW033	06/11/10	EM035	(#19W 08/S0/L0	HOMS	09/15/90 Redionucide	600AS
13/6/1890 Metal	6ZIMS 6	ebilbunolba R 0991/1/8		ebilounolba A 06/81/70	20003	03/23/80 AOC	20003	Intel® 06/4-0/80	HOMS	9DW 06\81\10	6EOAAS
11/2/1890 Redionucide	6ZIMS	IsteM 0661/7/8	SWOOR	ladeM 06/T0/80	2M033	epijanoipa R adionucijde	20003	1876M 06/20/50	HOMS	03/16/90 VOC	6EDMS
11/5/1880 Metal	SM139	90W 0681/k1/2	9COMS	IndeM 06/01/80	SW033	03/23/80 Wetst	20003	Intel® 06/20/40	HOMS	ebitounolba R 06/81/70	2M038
8/10/1882 Metal	8E0WS	20A 0681/91/9	900008	ebilounolbe Redionuciide	. EEOWS	05/50/80 AOC	SW032	1879M (08/15/E0	. HOMS	9DW 08\70\80	6COMS
#IPW Z661/L/P	8E0WS	S/14/1990 Radionuciide	9COMS	IntelM 08\f F\H0		02/20/90 Redionalide	20003	02/06/90 Redionucide	HOMS	OOV 08/10/80	2AA038
1/20/1882 Metal	8E0WS	Mater 0681/41/2	9COMS	(IE)-PM (OS/S2/60	SW033	90W 08/81/10	20003	02/06/90 Metail	INOMS	ebilounolbe 9 06/10/80	6E0MS
INDIA 1981/7/11	8EOWS	4/12/1990 Radionucide	9C0MS	Intel® 09/81/10	20003	01/16/90 VOC	20003	(#10M 06/1-0/10	HOMS	AraM 08\70\80	6EDMS
10/23/1881 [Metal	BEOMS	4/12/1990 Pesticide	80008	12/15/89 Metal	SW033	ebilounolbasi 08/81/10	20003	15/02/28 Wetel	INOMS	90W 08/60/20	600MS
E39M 1981/81/8	SCOWS	3/14/1880 AOC	80008	18/13/89 Metal	CCOMS	COLIGORA Metal	20003	11/20/89 Metal	LINOMS	09/08/80/AOC	EDMS
1236/1991 Metal	850WS	3/14/1990 Redionucibde	80008	IRIOM 98/91/90	££0WS	12/18/89 WQP	80003	IsleM 68/81/80	HOMS	05/09/90 Redionucide	6E0MS
7/25/1991 Redionucide	8C0W2	3/14/1880 Wetal	80008	Into M 98/15/80	SEOWS		20003	05/26/89 Metal	SWOAT	Into M 06/60/50	60003
7/25/1991 Metal	SEOMS	2/9/1990 WQP		ebilbunolba9 Radionuciide	SW033	12/15/89 Redionuciide	20003	ebilounoibe 9 95/10/50	HOMS	90W 06/21/10	6C0W2
epibunolbe/i Redionucide	SEOWS	5/8/1880 AGC	260448	INDIA GRACARO	80003	12/15/89 Metal	80033	INDEM 68/10/CO	LIMAS	04/15/80 AOC	\$M038
Metall 1997/05/8	SEOMS	5/8/1880 Kadionuciide		ebilbunolba Я 88/10/10	\$50W8	10/13/88 VOC	80033	1806M 78/82/TO	HOMS	O4/15/80 ZAOC	SW039
S/16/1991 Redonatide	SCOWS	1/13/1890 WQP	90048	IEDOM 88/FO/TO	200MS	10/13/88 8/00	SW033	03/24/93 Redionucide	OHOMS	04/12/90 Redionucible	6E0MS
Mahii (991/01/6	SCOVAS	1/15/1880 AOC	900MS	04/02/92 Metal	20003	10/13/89 Redionuciide	SW033	03/24/83 Metal	OHOMS	04/12/90 Pesticide	60MS
4/8/1881 Radionucide	SCOMS	1/15/1990 Radionuciide	900/48	ebilounoibe/Redionuciide	SE0448	10/13/89 Pesticide	80033	11/04/85 Redionucide	CHOMS	04/12/90 Metal	620MS
MIN 1991/8/A	8COMS	Intel® [0881\21\r	9C0W8	Made Selatio	SW032	10/13/89 Metal	20023	11/04/92 Metal .	SWD40	04/15/80	6EOMS
3/28/1881 Kedonoge	8E0MS	12/14/1989 WOP	9000	1/13/81 Metal		dpW 68/61/60	\$20003	ImpM T8/05/T0	SWOID	92W 09/15/60	8COMS
3/29/1881 Metal	80008	12/14/1989 Redionuciide	900008	hateld 19/01/01	8M035	OON 68/61/60	8W033	04/15/92 Metal	80008	03\\$1\30 \AOC	80008
13/11/1880 Hadionolida	80008	(3/14/1989 Metal	960\\\8	9bilounolba/i 1/6\70\80 lateM 1/6\8\80	80003		20000	IsteM 19/81/11	884038	ebilounolba A 06/15/00	80003
12/11/1880 Metal	860448	11/8/1888 AOC		ebilounolba8 16/10/60	SW032	FROM 69/61/60	20003	1846M 16/20/01	6EOAAS	1834NI 08/15/50	8AA038
11/2/1880 Redionacide	SVAD38	1219M (8881/8/1)	80008	Intel® 16/70/80	20043	40W 68/10/80	SW033	1879/W 1 6/20/60	620MS	02/08/30 MQP	\$AA038
Material 0881/2/11	SV4038	10/18/1989 VOC	80008	67/10/91 Redionucide	20003		S0003	MateM 16/80/80	. 650MS	05/08/80 AOC	6E0AAS
6/25/1992 Metal	9COAS	10/18/1989 SAOC	9C0MS	Intel® 19/01/70	20003	MH-M 68/1-0/80	2M035	, ebilounoibaR F9\80\70	600MS	02/08/90 Redionuclide	6EOMS
#IPPN Z661/8/F	SVV038	10/19/1989 Radionucide	800V8	ebilounoibes 19/51/80	SWOOS		20003	heteM 19\80\TO	2M039	1839M 06/80/20	6EOMS
Mahii 1991/7/11	9EOAAS	INDM 6881/81/01	900VS	IEDOM 16/21/90	20003		20003	ebilounotbast 19/10/80	SW039	9DW 08/11/10	650MS
8/13/1881 Redonucide	900MS	9/22/1989 WGP	80008	ebibunolbasi (19/90/80	ZEOWS		SAN032	JateM FQ/F0/80	6£0MS	. 01/17/90 VOC	650WS
Male 1991/E1/8	9E0MS	8/55/1888 AOC	8K0X8		250W3	MJ-M 68/61/TO	800033	ebilounoiba F Redionuolide	800MS	ebilounoibes 08/71/10	600MS
5/16/1991 Radionucide	9C0MS	9/22/1989 Redionucide	900008	04/04/91 Redionuciide	SWO32	06/21/69 WQP	20003	hateM 19/50/20	2M038	Material ORNTINO	\$M039
FION 1881/91/9	9C0MS	9/22/1969 Metal	9COMS	120M 16/10/10	20003	06/21/89 VOC	20003	ebilounoiba R 19/10/10	2AA038	12/20/89 WQP	20003
4/8/1991 Radionucide	9E0MS	4DW 6891/82/9	9COMS	ebitounothe R 19/13/10	ZCOMS		20003	- Mater F6/10/10	600MS	15/50/88 AOC	650AAS
MINN 1991/8/A	80008	9/28/1989 AOC	960WS	Metall Metal	250003		20003	O3/26/91 Redonucide	600MS	15/50/89 Redionucide	620MS
3/12/1881 Redonicade	20003	6/28/1989 Redionucible	OCCAAS	15/04/90 Redionuciide	20003		200MS	Metall 18/85/60	6£0MS	12/20/89 Metal	6£0MS
112/181 1861/91/C	9E0MS	6/28/1989 Metal	SW036	12/04/90 Metal	SCOVIS		SM035	12/04/90 Redionuciide	600MS	11/17/89 VOC	2M028
11/S0/1880 Kadionucide	9COMS	5/24/1989 WQP	900009	ebilibunolbe/ii (04/10/) }	SCOVE		20003	12/04/90 Metal	6\$0MS		850WS
11/20/1990 Metal	80MS	ebilounoiba Radionuciide	80008	intell 08/70/1	250445		80003		680MS	MateM (85/71/11	8E0MS
ebitounoibe. 9 0991/8/8	BEOMS	5/24/1989 Pesticide	800MS	hateM 08/h0/01	20003		8M033	MateM 06/80/11	80000	90W 68/81/80	2AA038 8AA038
Material 0991/8/8	9COW8	4/3/1989 WQP	90008	HENRY 06/\$1/60	20003		\$50448	1819M 06/20/01	SWOOD	06/16/89 VOC	
hatelM 0001/7/8	80008	00V 689 VV	900448	95/30/90 Me/eti	20003		SWOOS	M16M 08/51/60	SWOOD		8M038
#10(N) 0661/1/1/9	9604/8	7/3/1888 RAOC	200036	hateM 06\01\80	20003		80008	ebilounolba R 06/81/80	6C0M8	1219M 68/91/90	820003
4/12/1990 Redionucide	8W038	ebitounoibes Redionucide	800A8		20001		\$6000	ebilbunolba R 08/8/1/10	600MS	02/48/89 WQP	820/43
4/12/1990 Metal	9£0\\\8	4/3/1889 Pesticide	960W8	Mate M 06/17/40	M035		20003	IsteM 08\70\80	600MS	09/59/88 AOC	650WS
\$14/1880 Metal	SEOVAS	INTO 00011170	SCOV(8)		2000		SW033	MeM 08/80/80	680WS		6E0MS
2/9/1990 Metal	90MS	90W 8881/75/a	90008	Material Octobro	20003		SW033		60MS		6E0MS
1/12/1890 Metal	9£0MS	6/27/1988 VOC	SAA039	12/12/89 Metal	2000		SW032	04/12/90 Metal	600AS	05/26/89 Retail	6COMS
12/14/1989 Metal	9E0MS	ebilounoibes Radionuciide	90008	10/13/89 Metal	25000		SW032	03/21/90 Metal	8E0WS		620/45
MINM 6891/6/11	2M036	MateM 8861/75/8		Istolii (85/90/80	ZEDAN		20003	02/08/90 Metal	6£0MS	40W 68/90/M	62045
10/19/1989 Metal	9COMS	8/20/1986 WQP	90000	MoM 88/81/70	W032		ZE0MS	1206M 08/71/10	6E0MS	OCV 68/80/10	6000
9/22/1989 Metal	9£0MS	9/50/1986 VOC -	960W8	Hatel 68/15/90	M035		SWOOS		6504/3	04/06/89 SVOC	650MS
6/28/1989 Metal	9E0MS	9/50/1889 EAOC	900MS		W032		20003		60000		620745
4/3/1969 Redionucible	9£0MS	8/20/1986 Redionuciide	9604/8		M035		20003		6504/8	ebiolise9 Pesticide	65045
HOW 6961/C/F	9E0MS	ebio8se9 8861\05\8	900AS		W032		200003	(B)-M (88/92/S0	600MS		65045
6/27/1988 Redionuciide	960WS	8/54/1885 AOC	HOTIO, THI	Material 88/15/80	W032		SW032		6EOMS		650445
MoM 6881/72/8	960WS	9/8/1890 WGP	ноти ти		W032		SW032:	mi=M 68/90/10	6£0MS		82000
8/20/1996 Metal	900MS	8/8/1890 VOC	ит, рітсн		M035		SEOMS	ebilounoiba R 88/15/80	60MS		20003
	INT, DITCH	ebilounoiba9 0ee1/8/8	INT, DITCH	Intelligence of the second	70044				620MS	lateM 88/75/80	STANCE OF THE ST
M-MI 0661/8/8	INT, DITCH	hateM 0991\8\8	INT. DITCH	HALL MENCAN	A LEGGE LICENS	CASTA STATE OF STREET HORSE		THE REPORT OF THE PERSON OF TH	Oleboo notego.	WindbargqU = cre. (cr	I ahan antigan
POSICIO SEASON MAINT NOSCOSO	G (Shoc) notego.)	CUOSO SYNENA! Shed noticello:			2000	TOTAL COLORUMNIA COLOR		Service Concentrations & Service Concentrations	Otal Classification	Winsbargott - (17	MT SUCKE AND DE
SECURIOR SECURIOR PROPERTY OF THE	OFFICE STREET,	Section of the sectio			Alle I Alle III Alle	WHICH SUNOT SPECTORS AND ADDRESS.	Real Property lies	THE RESERVE OF THE PARTY OF THE	WATERWAY	With Denocul Personal Communication	C. THEREST CO.
the second of th	THE REPORT WOODS		30 D. M.	1 march 1 marc	white the second of the second of the	project, Microsoft Wild to Library and the State of Association of the Control of					•

							_	in a dinamenta	20003		" Г "	02/26/89 Metal	I POMS
		- T	03 Redionuciide	nzintic T	900MS		L	04/02/92 WQP	ceuvis		·	90W 88/10/co	INOMS
		— ⊢			200AS			04/05/85 AOC	ECOMS ECOMS		. +	epitonuoiba / 88/10/00	I HOMS
			tateM co					O4/O2/92 Metal	200VB		· -		EMMS
		L.	03 Redionucibe		9C0/A8		🗀	01/15/92 WQP	844033		: ∟	hateM: 98\f0\co	
		Г	Intelli	4/28/20	SK0348		- ⊢	01/12/85 AOC	SM023			20V [1/11/1]	HOMS
			03 Redionuclide	4/22/20	SWOOS		.		ZEOMS	•		90W T8/62/T0	INOMS
		_	O3 Metal		800MS	•	· · · L	ebilbunoibaR S@&1/10				01/29/87 VOC	1 POWS
		<u>⊢</u>	03 Radionuciide		9COMS			hateM S8/21/10	SW035		· · · -	4DM 68/72/60	OHOMS
		<u>⊢</u> `			SCOMS			90W 19/21/11	2M035		· -	03/24/83 AQC	OHOMS
•		<u> </u>	O3 Metal					11/13/81 AOC	SW033				0+0MS
			63 Redionucide	02/11/19	860W8		ing regis 🛏	11/13/81 Redonucide	200035	•	L	20/24/83 SVOC	
			O3 Metal	07/11/70	8K0M8	the state of the s	· · · ·	ISJOM 10/C1/11	200025		. L	03/24/83 Kediohuciide	OHOMS
			03 Redionucide	OZ/L/V	9COAAS	. ?	-		20002			ebiotise9 Pesticide	010MS
		 	D3 Metal		80M8	•		90W (16/01/01			Г	C3/24/93 [Metal	OHOMS
		<u> </u>	03 Redionucide		80008		L.	10/10/91 VOC	800033			11/04/92 WQP	OHOMS
		L-			9COMS	•		10/10/31 SAOC	200MS	•	· · ·	11/04/85 AOC	010MS
		<u>'</u>	lateM 60				<u> </u>	10/10/91 Redionuciide	20002		. 1		OHOMS
		. [33 Redionucide		SCOV/S	5 - 15 - 15 - 15 - 15 - 15 - 15 - 15 -		ebio8se9 16/01/01	20003		L	11/04/85 SAOC	ONOMS
			HateM EC	V/1/20	9COAAS	### 1 g	· · · · · · · · · · · · · · · · · · ·	10/10/91 Metal	200025		L.	11/04/92 Radionucide	
			33 Redionacide	3/27/20	9C0MS		- ⊢		20003			11/04/92 Pesticide	CHOAAS .
		├ ~	D3 Metal		9COMS		<u> </u>	99/26/91 WQP		•		1 1/04/92 Metal	01-0AAS
		⊢	Spilonnoipe H CC		90000	· · · · · · · · · · · · · · · · · · ·	L	08/36/81 VOC	\$60W8		- F	9DW 78/05/10	010MS
		<u></u>	IsheM EC		SEOWS	•	1	09/26/91 Redionuciide	200035		<u> </u>	07/3067TO	OHOMS
		⊢			9C0/\\S	•		09/26/91 Metal	SW032	• •	- F	04/15/92 WQP	680MS
			S Redionucides			•	T	90W 16/70/80	SW033		· · ·	04/19/85 AQC	60MS .
		Г	(ateM 60		960WS		F	OOV 16/70/80	844033				SM038
		Г	33 Radionuciide	3/17/200	9C0AVS		. ⊩	60/07/91 Redionucide	280448	•	· · · L	THE CANTEND	62045
		F	IntoM C	3/17/200	9COMS	`	ļ-	Metal 1970/80	20003		. · [90W 19/81/11	
		} −	S WQP		9COVAS	•	L.		20003		,	11/19/81 AOC	600AS
		⊢	200 50		9COMS		. L	. 90W 18/01/TO				ebilounolbe FI 19/81/11	6EOMS
		├	SISVOC		9COMS	•	. [OV/16/91 VOC	SEOWS	•	l l	INDEM 16/81/11	6EOMS
		Ŀ			9000		. г	ebilounolba A 19/01/10	SCOW8		· •	10/02/91 WQP	6EOMS
		<u>L</u>	ebilounoibe R &	661/1/9		•		htteM 19/01/10	200MS		· • • • • • • • • • • • • • • • • • • •	10/02/91 1/00	6COMS
		L.	5 Pesticide		900008	•		90W 19/61/80	SW033 ·	•	• •	20V2 18/20/01	600MS
		ŗ	lateM &		9C0\\\3	·	- F	JON 16/81/90 .	SCOMS		ı		6EOMS
		Г	9DW 6	3/23/188	900MS	*		epipnuoipe y 16/61/90	20003			10/03/91 Radionuclide	
	-	• -	PIADC	3/23/188	800MS				SMOSS			10/02/91 Pesticide	6E0MS
		-		3/53/188	20MS		L	htteM 19/51/80		1		10/02/91 Metal	680MS
	٠,	,			9COMS		. [90W 18/80/20	SW032			GOW 16/20/60	2AA038
	,	L	5 Radionuciide		9EOMS			02/03/81 AOC	SW032			20V 19/20/e0	6EOMS
		L.	5 Pesticide				t	05/09/91 Redionuciide	SM033	•		09/02/61 Kadiorucide	2AA038
			lateM 3	3/23/188	960448		l l	hateM 18/80/20	20003		•		8X0038
		r	4 WQP	661/81/1	960MS			4DW 16/10/10	20003		1	Intel® 19/20/90	2M028
		F		661/81/7	\$60W8	•		20V 18/10/10	\$60008			9DW 19\20\80	
	•	h		661/91/9	900008		Į.		20003			08/02/91 VOC	6EOMS
	*		Redionucide		9C0W8		L L	04/04/61 SVOC	80033		<i>1</i> *	lateM 19/20/80	6E0MS
		<u> </u>	Pesticide		9coms		٠ . ا	04/04/91 Redionucible				90W 19/80/TO	6E0MS
		L			9COAS			ebiolize9 Pesticide	SW035			OV 18/80/10	660MS
		L		661/91/1		·	. 1	MateM 16/40/40	SW032			epipnuopsy / 6/80/40	2AA039
				2881/97/9	9COW2	,		99/13/91 WQP	20003			Material FGA80\TO	680MS
			00V	2661/92/9	90000		. 1	03/13/81/AOC	200003				2AA028
	•	ľ	Metal	8/52/1885	9604/38			03/13/81 Redonuciide	20003	•	•	90W 164-0\20	60005
		t t		7/8/1885	900MS	l			SW033			06/04/91 VOC	
		· · · · · · · · · · · · · · · · · · ·		7/8/1885	9E0MS	03/24/93 Regionndide	SAV50283	hateM 19/51/50	20003			06/04/91 Redionuciide	SAN038
		}		7/8/1992	9COMS		SM20583	12/04/90 WQP		:		MateM 16/10/90 .	SM038
		1			8W036		SW50183	15/04/90 VOC	20003	•	. ,	95W 16/50/20	E 600MS
		l.		1661/2/11	900008	200 200	SW20193	15/04/90 Redionucide	SEOWS		× 5	05/03/91 VOC	6EQAAS
		Į.		1661/2/11			2M10582	12/04/90 Metal	SWOOS			09/03/81 Redionucide	650WS
			Redionucide		960W8		CCOMS	. 90W 08/70/11	SMOOS		e e	Mate M 16/00/20	6E0MS
		ſ		1661/4/11	9COAAS		SEOMS	11/07/90 VOC	SW032	•	3	40M 16/10/10	600MS
	•		90W	1661/21/8	960448		EE0MS		20003				60005
				1661/01/9	BEOWNS				20003			04/01/81 AOC	60045
•			Radionuctide		960MS	1 1/O4/92 Metal	EEOMS		20002	•		20/01/81 SAOC	
				1661/21/0	900MS	04/06/92 Metal	SEOWS	10/04/90 (WQP				ebitounoibeR F6/10/M0	6COMS
				1661/91/9	960//8		SW033		20003			04/01/91 Pesticide	600AS
					9000		SW033	10/04/90 SAOC	80008		•	HISTORY LG/LO/NO	8EOMS
			Redionucide		90000		£60W3	10/04/90 Redionucide	20003	3/24/93 Redionucide	1 INOMS		600MS
				1661/91/9			SW033	10/04/90 Metal	SW032				6COMS
		j		1661/8/1	90000		SW033		SW033	3/24/83 Metail			2M028
			VOC	1661/8/9	9COAAS		20003		SWOOS	2/17/92 Metal			660WS
				1661/9/1	90000				20003	0/05/81 Metal	1 1000		620VS
		009/48			960W3		E0W3		20003	18/20/81 Metal		12/04/90 WQP	6COMS
Regionno			Pesticide		90000		CCOMS		SOMS	8/05/91 Redionuclide		15/04/80 AOC 2	
	10/2/1883	2005005			960W		££0W3			8/05/91 Metal			. 60MS
	10/23/1881	SM159		1681/9/7	90000		EEOMS		20003				600MS
Intellal I	1661/81/6	2MIS8		3/12/1881			SE0W2		SW032	7/08/91 Redionuciide			2AA038
Redionuc		SW129		1661/51/6	90000		EEGAS		SMOOS	hateM 19\80\7			6£0MS
	1661/E1/9	SM159	Redionuciide	2/12/1881	90000		ECOMS		SW033	8/04/91 Redionuciide			2M038
Dunolbash Interior		SALIS		1661/91/6	90000	B 1819M 16/61/90			SWO32	1steM 16\40\8		2 abilbunoibe A 06/80/11	
					9COAA	B ebitounoibe F (*e.4-0/4-0	20003	March Clonesis					•
		AZIAAQ	a down	10001/06/11									
	1/22/1881	6ZIMS	aom	11/20/1890	· · · · · · · · · · · · · · · · · · ·						•• •		

Table 3
Sampling and Analytical Summary for OLF Surface Water

SW041	05/26/89 Radionuclide
	05/26/89 WQP
SWD41	05/20/89 44/27
SW041	06/16/89 Metal
SW041	06/15/89 Radionuclide
377071	06/16/89 WQP
\$W041	
SW041	11/20/89 Metal
SW041	11/20/89 Radionuclide
SW041	11/20/89 WQP
	12/05/89 Metal
SW041	12/05/89 Radionuclide
SW041	12/05/89 Radionacide
SW041	12/05/89 WQP
SW041	01/04/90 Metal
SW041	01/04/90 Redionactide
	. 01/04/90 WQP
SW041	01/04/90 VVQr
SW041	02/06/90 Metal
SW041	02/06/90 Radionuclide
SW041.	02/06/90 WQP
	03/21/90 Metal
SW041	
SW041.	03/21/90 Radionuclide
SW041	03/21/90 WQP
CANCEL	04/05/90
SW041	04/05/90 Metal
SW041	U4/US/SU MEURI
SW041	04/05/90 Pesticide
SW041	04/05/90 SVOC
	04/05/90 VOC
SW041	
SW041	04/05/90 WQP
SW041	05/02/90 Metal
SW041	05/02/90 Redionuclide
SW041	. 05/02/90 VOC
	05/02/90 WQP
SW041	05/02/90/444
SW041	05/04/90 Metal
SW041	06/04/90 Radionuclide
SW041	06/04/90 VOC
	06/04/90 WQP
SW041	00/04/80 44/21
SW041	07/05/90 Metal
SW041	07/05/90 Radionuclide
	07/05/90 VOC
SW041	07/05/00/14/08
SW041	07/05/90 WQP
SW041 ·	08/06/90 Metal
CHARAS	
. SW041	· 08/06/90 Radionuclide
SW041	. 08/06/90 Radionuclide 08/06/90 VOC
SW041 SW041	. 08/06/90 Radionuclide 08/06/90 VOC 08/06/90 WQP
SW041	08/06/90 Radionuclide 08/06/90 VOC 08/06/90 VVQP 09/05/90 Metal
SW041 SW041 SW041	08/06/90 Radionuclide 08/06/90 VOC 08/06/90 WQP 09/05/90 Metal 09/05/90 Radionuclide
SW041 SW041 SW041 SW041 SW041	08/06/90 Radionuclide 08/06/90 VOC 08/06/90 WQP 09/05/90 Metal 09/05/90 Radionuclide
SW041 SW041 SW041 SW041 SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 WOP 09/05/90 Wetall 09/05/90 Woc 09/05/90 VOC
SW041 SW041 SW041 SW041 SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 WOP 09/05/90 Metal 09/05/90 Radionuclide 09/05/90 VOC 09/05/90 VOC
SW041 SW041 SW041 SW041 SW041 SW041	08/06/90 Radionuclide 08/06/90 VOC 08/06/90 WCP 09/05/90 Metal 09/05/90 Radionuclide 09/05/90 VOC 09/05/90 WCP 10/02/90 Metal
SW041 SW041 SW041 SW041 SW041 SW041	08/08/90 Redionuclide 08/08/90 VOC 08/08/90 VOP 09/05/90 Metal 09/05/90 Redionuclide 09/05/90 VOC 09/05/90 VVOP 10/02/90 Metal 10/02/90 Pesticide
SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041	08/06/90 Radionuclide 08/06/90 VOC 08/06/90 WCP 09/05/90 Metal 09/05/90 Radionuclide 09/05/90 VOC 09/05/90 WCP 10/02/90 Metal
SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 WOP 09/05/90 Metal 09/05/90 Radionuclide 09/05/90 VOC 09/05/90 WOP 10/02/90 Metal 10/02/90 Pesticide 10/02/90 SVOC
SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOCP 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VOC 10/02/90 Metal 10/02/90 Pesticide 10/02/90 SVOC 10/02/90 SVOC
SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041	08/08/90 Redionuclide 08/08/90 VOC 08/08/90 VOP 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VVOP 10/02/90 Metal 10/02/90 SVOC 10/02/90 VVOC 10/02/90 VVOC 10/02/90 VVOP
SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 WOP 09/05/90 Metal 09/05/90 Radionuclide 09/05/90 WCC 09/05/90 WCC 09/05/90 WCP 10/02/90 Metal 10/02/90 Pesticide 10/02/90 VOC 10/02/90 VOC 10/02/90 WQP 12/04/90 Wetal
SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VOC 10/02/90 Wetal 10/02/90 SVOC 10/02/90 SVOC 10/02/90 WQP 12/04/90 Wetal 12/04/90 Wetal 12/04/90 Wetal 12/04/90 Wetal 12/04/90 Metal 12/04/90 Metal
SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VOC 10/02/90 Wetal 10/02/90 SVOC 10/02/90 SVOC 10/02/90 WQP 12/04/90 Wetal 12/04/90 Wetal 12/04/90 Wetal 12/04/90 Wetal 12/04/90 Metal 12/04/90 Metal
SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOCP 09/05/90 Metal 09/05/90 Metal 09/05/90 WQP 10/02/90 Metal 10/02/90 Metal 10/02/90 SVCC 10/02/90 VOC 10/02/90 WdP 12/04/90 WdP 12/04/90 Metal 12/04/90 Metal 12/04/90 Metal 12/04/90 Metal 12/04/90 Metal 12/04/90 Metal
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VOC 09/05/90 VOC 10/02/90 Pesticide 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 Metal 12/04/90 Radionuclide 12/04/90 Radionuclide 12/04/90 VOC
SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 WQP 10/02/90 Metal 10/02/90 Pesticide 10/02/90 SVOC 10/02/90 VOC 10/02/90 WQP 12/04/90 Metal 12/04/90 Metal 12/04/90 Metal 12/04/90 WQP 12/04/90 WQP
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 WQP 10/02/90 Metal 10/02/90 Pesticide 10/02/90 SVOC 10/02/90 VOC 10/02/90 WQP 12/04/90 Metal 12/04/90 Metal 12/04/90 Metal 12/04/90 WQP 12/04/90 WQP
SW041 SW041	08/08/90 Redionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 WOP 10/02/90 Metal 10/02/90 Metal 10/02/90 SVOC 10/02/90 VOC 10/02/90 WoP 12/04/90 Metal 12/04/90 Metal 12/04/90 WOP 12/04/90 WOP 12/04/90 WOP 05/03/91 Metal 05/03/91 Metal
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 WOP 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 WOP 10/02/90 Metal 10/02/90 Pesticide 10/02/90 SVOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 WOP 12/04/90 Pedionuclide 12/04/90 VOC 12/04/90 WOP 05/03/91 Metal 05/03/91 Redionuclide 05/03/91 Redionuclide
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VOC 09/05/90 VOC 10/02/90 Metal 10/02/90 SVOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 Metal 12/04/90 VOC 12/04/90 VOC 12/04/90 VOC 12/04/90 VOC 05/03/91 Metal 05/03/91 VOC 05/03/91 VOC
SW041 SW041	08/08/90 Redionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 WOP 10/02/90 Metal 10/02/90 Metal 10/02/90 SVCC 10/02/90 SVCC 10/02/90 VOC 10/02/90 WOP 12/04/90 Metal 12/04/90 WOP 12/04/90 WOP 12/04/90 WOP 12/04/90 WOP 05/03/91 Metal 05/03/91 Redionuclide 05/03/91 WOP 05/03/91 WOP
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOCP 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VOC 09/05/90 VOC 10/02/90 Metal 10/02/90 SVOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 WoP 12/04/90 Metal 12/04/90 VOC 12/04/90 VOC 05/03/91 VOC 05/03/91 WOP 05/03/91 WOP 05/03/91 WOP
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOCP 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VOC 09/05/90 VOC 10/02/90 Metal 10/02/90 SVOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 WoP 12/04/90 Metal 12/04/90 VOC 12/04/90 VOC 05/03/91 VOC 05/03/91 WOP 05/03/91 WOP 05/03/91 WOP
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VOC 09/05/90 VOC 10/02/90 Metal 10/02/90 SVOC 10/02/90 VOC 10/02/90 VOC 12/04/90 WQP 12/04/90 WQP 12/04/90 VOC 12/04/90 VOC 12/04/90 VOC 05/03/91 VOC 05/03/91 VOC 05/03/91 VOC 05/03/91 VOC 08/04/91 Radionuclide 08/04/91 Radionuclide
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 WOP 09/05/90 Metal 09/05/90 WOP 09/05/90 VOC 09/05/90 VOC 09/05/90 VOC 10/02/90 Pesticide 10/02/90 Pesticide 10/02/90 SVOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 Radionuclide 12/04/90 WOP 05/03/91 Metal 05/03/91 WOP 08/04/91 Radionuclide 05/03/91 VOC 05/03/91 WOP 08/04/91 Radionuclide 08/04/91 Radionuclide
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 WOP 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VOC 09/05/90 VOC 10/02/90 Metal 10/02/90 SVOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 Wetal 12/04/90 VOC 12/04/90 WOP 05/03/91 Metal 05/03/91 VOC 05/03/91 WOP 06/04/91 Metal 06/04/91 Metal 06/04/91 Metal 06/04/91 Metal 06/04/91 Metal 06/04/91 Metal 06/04/91 Radionuclide 06/04/91 Metal 06/04/91 Radionuclide
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VOC 09/05/90 VOC 10/02/90 Metal 10/02/90 SVOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 Metal 12/04/90 WQP 12/04/90 WQP 12/04/90 WQP 05/03/91 VOC 05/03/91 VOC 05/03/91 VOC 06/04/91 VOC 06/04/91 VOC 08/04/91 VOC
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VOC 09/05/90 VOC 10/02/90 Metal 10/02/90 SVOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 Metal 12/04/90 WQP 12/04/90 WQP 12/04/90 WQP 05/03/91 VOC 05/03/91 VOC 05/03/91 VOC 06/04/91 VOC 06/04/91 VOC 08/04/91 VOC
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/08/90 Metal 08/08/90 VOC 09/08/90 Metal 08/08/90 VOC 09/08/90 VOC 09/08/90 VOC 10/02/90 Metal 10/02/90 Pesticide 10/02/90 SVOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 WoP 12/04/90 WoP 05/03/91 Metal 05/03/91 WoP 08/03/91 WoP 08/03/91 WoP 08/03/91 VOC 08/03/91 VOC 08/03/91 VOC 08/03/91 VOC 08/03/91 VOC 08/03/91 VOC
SW041 SW041	08/08/90 Redionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 VOC 09/05/90 VOC 09/05/90 VOC 10/02/90 Pesticide 10/02/90 SVOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 Wetal 12/04/90 VOC 12/04/90 VOC 12/04/90 VOC 05/03/91 Metal 05/03/91 Metal 06/04/91 Metal 06/04/91 Metal 06/04/91 Metal 06/04/91 VOC 08/04/91 VOC 08/04/91 VOC 08/04/91 Redionuclide 06/04/91 VOC 08/04/91 VOC 08/04/91 Redionuclide 06/04/91 Redionuclide 06/04/91 VOC 08/04/91 VOC 08/04/91 Redionuclide
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 WQP 10/02/90 VOC 09/05/90 VOC 09/05/90 VOC 10/02/90 Pesticide 10/02/90 SVCC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 Wdp 12/04/90 Wdp 12/04/90 Wdp 05/03/91 Metal 05/03/91 Radionuclide 05/03/91 VOC 05/03/91 VOC 05/03/91 VOC 05/03/91 VOC 05/03/91 VOC 06/04/91 VOC 08/04/91 VOC 08/04/91 WQP 07/08/91 Metal 07/08/91 Metal 07/08/91 Metal 07/08/91 Metal 07/08/91 Metal 07/08/91 VOC 07/08/91 VOC 07/08/91 VOC
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/08/90 Metal 08/08/90 Metal 08/08/90 Metal 08/08/90 WOP 10/02/90 Redionuclide 10/02/90 Pesticide 10/02/90 Pesticide 10/02/90 SVCC 10/02/90 SVCC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 Wop 12/04/90 Wop 08/03/91 Metal 08/03/91 Metal 08/03/91 WOP 08/03/91 Wop 08/04/91 Redionuclide 08/04/91 Redionuclide 08/04/91 Redionuclide 08/04/91 Redionuclide 08/04/91 Redionuclide 08/04/91 Wop 07/08/91 Wop 07/08/91 Wop 07/08/91 Wop 07/08/91 Wop 08/08/91 Redionuclide
SW041 SW041	08/08/90 Radionuclide 08/08/90 VOC 08/08/90 VOC 09/05/90 Metal 09/05/90 Metal 09/05/90 WQP 10/02/90 VOC 09/05/90 VOC 09/05/90 VOC 10/02/90 Pesticide 10/02/90 SVCC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 10/02/90 VOC 12/04/90 Wdp 12/04/90 Wdp 12/04/90 Wdp 05/03/91 Metal 05/03/91 Radionuclide 05/03/91 VOC 05/03/91 VOC 05/03/91 VOC 05/03/91 VOC 05/03/91 VOC 06/04/91 VOC 08/04/91 VOC 08/04/91 WQP 07/08/91 Metal 07/08/91 Metal 07/08/91 Metal 07/08/91 Metal 07/08/91 Metal 07/08/91 VOC 07/08/91 VOC 07/08/91 VOC

٠,	•	
SW033	_	07/01/88 Metal
SW033	三	07/01/88 Radionucide
SW033		07/01/88]VOC
SW033		07/01/88 WQP
SW033		04/04/89 Metal
SW033		04/04/89 Pesticide
SW033	_	04/04/89 Radionuclide
SW033	_	04/04/89 SVOC 04/04/89 VOC
SW033	-	04/04/89 WQP
SW033		05/24/89 Pesticide
SW033	-	05/24/89 Pasticide 05/24/89 Radionuclide
SW033	-	05/24/89 WQP
SW033		06/21/89 Metal
SW033		06/21/89 Radionuclide
SW033	ļ	06/21/89 VOC
SW033	⊢	06/21/89 WQP. 09/19/89 Meta)
SW033	╄	09/19/89 Radionuclide
SW033	╌	09/19/89 VOC
SW033	٠.	09/19/89 VOC 09/19/89 WQP
SW033	┪.	10/13/89) Metal
SW033	1	10/13/89 Pesticide
SW033		10/13/89 Radionuctide
SW033	L	10/13/89 SVOC
SW033	Į.	10/13/89 VOC
SW033	4-	12/15/89 Metal 12/15/89 Redionuclide
SW033	+-	12/15/89 VOC
SW033	+-	12/15/89 WQP
SW033	+-	01/16/90 Metal
SW033	\top	01/16/90 Radionuclide
SW033	Τ.	01/16/90 VOC
SW033	1	01/16/90 WQP
SW033	4-	02/20/90 Radionuclide
SW033	-{-	02/20/90 VOC 03/23/90 Metal
5W033		03/23/90 Radionuclide
SW033	+	03/23/90 VOC
SW033	┰	04/11/90
SW033	_	04/11/90 Metal .
SW033		04/11/90 Pesticide
SW033	4	04/11/90 Redionuclide
SW033	-	04/11/90 SVOC 04/11/90 VOC
SW033	+	04/11/90 WQP
SW033 SW033	+	05/10/90 Metal
8W033	-	05/10/90 Radionuclide
SW033	\neg	05/10/90 VOC
SW033		05/10/90 WQP
SW033	4	06/07/90 Metat 06/07/90 Redionuclide
SW033	+	06/07/90 Radionucide
SW033 SW033	+	08/07/90 WQP
54033	+	07/16/90 Radionuclida
5W033	7	07/16/90 VOC
SW033		07/16/90 WQP
SW033		08/14/90 Radionuclide .
SW033	\Box	. 09/13/90 Metal
SW033	-4	09/13/90 Radionuclide
SW033		09/13/90 WQP 10/04/90 Metal
SW033		10/04/90 Radionuclide
SW031		10/04/90 SVOC
SW033		10/04/90 VOC
5003		10/04/90 WQP
SW033		11/07/90 Metal
SW03:		11/07/90 Radionuciide
SW033		11/07/90 VOC 11/07/90 WQP
SW03	,	11/0//80 WUP

Siamon	5/20/2003 Metal
5W036 5W036	5/20/2003 Radionuclide
SW036	7/18/2003 Metal
SW036	7/18/2003 Radionuclide
SW036	4/26/2004 Metal
SW036	4/26/2004 Radionuctide
SW036	5/12/2004 Metal
SW038	5/12/2004 Radionuclide
SW036	6/17/2004 Metal
SW036	6/17/2004 Radionuclide
SW038	10/15/1990 Metal
SW038	10/15/1990 Pesticide
SW038	10/15/1990 Radionuclide 10/15/1990 SVOC
SW038	10/15/1990 VOC
SW038	10/15/1990 WQP
SW038	11/5/1990 Metal
8W038	11/5/1990 Redionuclide
SW038	11/5/1990 VOC
SW038	11/5/1990 WQP
SW038	12/11/1990 Metal
SW038	12/11/1990 Radionuclide
SW038	12/11/1990 VOC
SW038	12/11/1990 WQP
SW038	3/28/1991 Metal
SW038	3/28/1991 Radionuclide
SW038	3/28/1991 VOC
\$14038	3/28/1991 WQP 4/9/1991 Metal
8W038	4/9/1991 Metal
SW038	4/9/1991 Pesticide
80038	4/9/1991 Radionuclide
SW038	4/9/1991 SVOC
SW038	4/9/1991 VOC 4/9/1991 WQP
SW038	5/16/1991 Metal
SW038	5/16/1991 Radionuclide
SW038	5/16/1991 VOC
SW038	5/16/1991 WQP
SW038	6/20/1991 Metal
SW038	6/20/1991 Radionucide
SW038	6/20/1991 VOC
SW038	6/20/1991 WQP
SYV038	7/25/1991 Metal
SW038	7/25/1991 Radionuclide
SW038	7/25/1991 VOC
SW038	7/25/1991 WQP
SW038	8/28/1991 Metal
SW038	8/28/1991 Radionuclide
SW038	8/28/1991 VOC 8/28/1991 WQP
SW038	9/18/1991 Metal
SW038	9/18/1991 Redionuclide
SW038	9/18/1991 VOC
SW038	9/18/1991 WQP
SW038	10/23/1991 Metal
SW038	10/23/1991 Pesticide
SW038	10/23/1991 Radionuclide 10/23/1991 SVOC
SW038	10/23/1991 SVOC
SW038	10/23/1991 VOC
SW038	10/23/1991 WQP
SW038	11/7/1991 Metal
SW038	11/7/1991 Radionuclide
SW038	11/7/1991 VOC
SW038	11/7/1991 WQP
SW038	1/20/1992 Metal
8W038	1/20/1992 Radionuclide
SW038	1/20/1992 VOC
8W038	1/20/1992 WQP 4/7/1992 Metal
8W038	4/7/1992 VOC
844790	4////002/199

Table 3
Sampling and Analytical Summary for OLF Surface Water

SW041	08/05/91 WQP
SW041	. 09/05/91 Metal
SW041	09/05/91 Radionuclide
SW041	09/05/91 VOC
SW041	09/05/91 WQP
SW041	10/02/91 Metal
SW041	10/02/91 Pesticide
SW041	10/02/91 Radionuclide
SW041	10/02/91 SVOC
SW041	10/02/91 VOC
SW041	10/02/91 WQP
SW041	12/17/92 Metal
SW041 ·	12/17/92 Radionuclide
SW041	12/17/92 VOC
SW041	12/17/92 WQP
SW041	03/24/93 Metal
SW041	03/24/93 Pesticide
SW041	03/24/93 Radionuclide
SW041	03/24/93 SVOC
SW041	03/24/93 VOC
SW041	03/24/93 WQP

SW033	12/04/90 Metal
SW033	12/04/90 Radionuclide
SW033	12/04/90 VOC .
SW033	12/04/90 WQP
SW033	03/08/91 Metal
SW033	03/08/91 Radionuclide
SW033	03/08/91 VOC
SW033	03/08/91 WQP
	Od Date Made
EW033	04/04/91 Metall
SW033	04/04/91 Metal 04/04/91 Pesticide 04/04/91 Radionuolide 04/04/91 SVOC
SW033	04/04/91 Radionuolide
SW033	04/04/91 SVOC
SW033	04/04/91 VOC
	04/04/91 WQP
SW033	
SW033	05/13/91 Metal
SW033	. 05/13/91 Radionuclide
SW033	05/13/91 VOC
SW033	05/13/91 WQP
SW033	
SW033	06/13/91 Radionuclide
SW033	06/13/91 VOC
SW033	06/13/91 WQP
SW033	07/10/91 Metal
	07/10/91 Redionuclide
SW033	0//10/91 Radionucida
SW033	07/10/91 VOC
SW033	07/10/91 WQP
SW033	08/07/91 Metal 08/07/91 Redionuclide
SW033	08/07/91 Radionuclide
	0007041400
SW033	08/07/91 VOC
SW033	08/07/91 WQP
SW033	09/26/91 Metal
SW033	09/26/91 Radionuclide
SW033	09/26/91 VOC
	09/26/91 WQP
SW033	
SW033	10/10/91 Metal
SW033	10/10/91 Pesticide 10/10/91 Redionuclide
SW033	10/10/91 Redionuclide
SW033	10/10/91 SVOC
SW033	10/10/91 VOC
SW033	10/10/91 WQP
SW033	11/13/91 Metal
SW033	11/13/91 Radionuclide
41111	
I CYANTA	
SW033	11/13/91 VOC
SW033	11/13/91 VOC 11/13/91 WQP
SW033 SW033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal
SW033 SW033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal
SW033 SW033 SW033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal
5W033 5W033 SW033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Radionuclide 01/15/92 VOC
SW033 SW033 SW033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Radionucide 01/15/92 VOC 01/15/92 WQP
SW033 SW033 SW033 SW033 SW033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 WQP 04/06/92 Metal
5W033 5W033 5W033 5W033 5W033 5W033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 VQP 04/06/92 Metal 04/06/92 VCC
5W033 5W033 5W033 5W033 5W033 5W033 5W033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 VOC 04/06/92 Metal 04/06/92 VOC 04/06/92 WQP
5W033 5W033 5W033 5W033 5W033 5W033 5W033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 VOC 04/06/92 Metal 04/06/92 VOC 04/06/92 WQP
SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033	11/13/91 VOC 11/13/91 WQP 11/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 WQP 04/06/92 Metal 04/06/92 WQP 11/04/92 WQP
SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 VQP 04/06/92 WQP 04/06/92 WQP 11/04/92 Metal 11/04/92 Pesticide
SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033	11/13/91 VOC 11/13/91 WQP 91/15/92 Metal 01/15/92 Radionuclide 01/15/92 VOC 01/15/92 VOC 04/06/92 Metal 04/06/92 WQP 11/04/92 WQP 11/04/92 Pesticide 11/04/92 Radionuclide
SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 WQP 04/06/92 Metal 04/06/92 WQP 11/04/92 Metal 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 SVOC
SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 VQP 04/06/92 WQP 04/06/92 WQP 11/04/92 WQP 11/04/92 WQP 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 VVOC
SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 VQP 04/06/92 WQP 04/06/92 WQP 11/04/92 WQP 11/04/92 WQP 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 VVOC
SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033	11/13/91 VOC 11/13/91 WQP 01/15/92 IMetal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 VOC 01/15/92 VOC 04/05/92 WQP 04/05/92 WQP 11/04/92 WQP 11/04/92 Pesticide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 VOC 11/04/92 VOC
SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033	11/13/91 VOC 11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 WQP 01/15/92 VWQP 04/08/92 WQP 04/08/92 WQP 04/08/92 VVC 04/08/92 VVC 11/04/92 Metal 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 VVC 11/04/92 VVC 11/04/92 VVC 11/04/92 VVC 11/04/92 VVC 03/24/93 Metal
SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033	11/13/91 VOC 11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Metal 01/15/92 VOC 01/15/92 VOC 01/15/92 VOC 04/06/92 VOC 04/06/92 VOC 04/06/92 VOC 04/06/92 VOC 11/04/92 Pesticide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 VOC 11/04/92 VOC 11/04/92 VOC 11/04/92 VOC 03/24/93 Pesticide 03/24/93 Pesticide 03/24/93 Pesticide 03/24/93 Pesticide 03/24/93 Pesticide 03/24/93 Pesticide 03/24/93 Pesticide 03/24/93 Pesticide 03/24/93 Pesticide 03/24/93 Pesticide 04/15/15/93 VOC 05/24/93 Pesticide 04/15/93 Pesticid
SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 VOC 01/15/92 VOC 04/06/92 WQP 11/04/92 Metal 11/04/92 Metal 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 VOC 11/04/92 VOC 11/04/92 WQP 03/24/93 Metal 03/24/93 Metal 03/24/93 Metal
SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033 SW033	11/13/91 VOC 11/13/91 VOC 11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Metal 01/15/92 VOC 01/15/92 VOC 04/06/92 VOC 04/06/92 VOC 04/06/92 VOC 04/06/92 VOC 11/04/92 Pesticide 11/04/92 Redionuclide 11/04/92 SVOC 11/04/92 VOC 11/04/92 VOC 11/04/92 VOC 11/04/92 VOC 03/24/93 Metal 03/24/93 Pesticide 03/24
\$\(\colon\)33 \$\(\colon\)33	11/13/91 VOC 11/13/91 VOC 11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Metal 01/15/92 VOC 01/15/92 VOC 04/06/92 VOC 04/06/92 VOC 04/06/92 VOC 04/06/92 VOC 11/04/92 Pesticide 11/04/92 Redionuclide 11/04/92 SVOC 11/04/92 VOC 11/04/92 VOC 11/04/92 VOC 11/04/92 VOC 03/24/93 Metal 03/24/93 Pesticide 03/24
\$W033 \$W	11/13/91 VOC 11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 VVC 01/15/92 VVC 01/15/92 VVC 04/06/92 VVC 04/06/92 VVC 04/06/92 VVC 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 WQP 03/24/93 Metal 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 SVCC
\$\\033 \$\	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 Wetal 01/15/92 VOC 01/15/92 WQP 04/06/92 WQP 11/04/92 Pesticide 11/04/92 Pesticide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 VOC 11/04/92 VOC 03/24/93 Metal 03/24/93 Pesticide 03/24/93 SVOC 03/24/93 SVOC 03/24/93 VOC 03/24/93 VOC 03/24/93 VOC
\$\\033 \$\	11/13/91 VOC 11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 WQP 04/08/92 WQP 04/08/92 WQP 11/04/92 Metal 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Pesticide 11/04/92 VOC 11/04/92 VOC 01/104/92 VOC 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 VOC 03/24/93 VOC 03/24/93 VOC 03/24/93 VOC 03/24/93 VOC
\$\\033 \$\	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 WQP 04/06/92 VVC 04/06/92 WQP 04/06/92 VVC 04/06/92 VVC 04/06/92 VVC 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 VVC 11/04/92 VVC 11/04/92 VVC 03/24/93 Pesticide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 VVC 03/24/93 VVC 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP
SW033 SW03 SW0	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 VQP 04/06/92 WQP 04/06/92 WQP 11/04/92 WQP 11/04/92 WQP 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 VOC 03/24/93 VOC 03/24/93 VOC 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP
SW033 SW03 SW0	11/13/91 VOC 11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Metal 01/15/92 WQP 04/08/92 WdP 04/08/92 WdP 04/08/92 VOC 04/08/92 WQP 11/04/92 Wdp 11/04/92 Redionuclide 11/04/92 Sesticide 11/04/92 VOC 11/04/92 VOC 11/04/92 VOC 11/04/92 VOC 03/24/93 Metal 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 VOC 03/24/93 VOC 03/24/93 VOC 03/24/93 VOC 03/24/93 WQP 05/24/93 Metal 05/24/93 Metal 05/24/93 WQP 05/24/93 WQP
SW033 SW03 SW0	11/13/91 VOC 11/13/91 VOC 11/13/91 MQP 01/15/92 Metal 01/15/92 Metal 01/15/92 Metal 01/15/92 VOC 01/15/92 VQP 04/06/92 VQP 04/06/92 VQC 04/06/92 VQC 11/04/92 Wqtal 11/04/92 Pesticide 11/04/92 SVOC 11/04/92 VVC 11/04/92 VVC 11/04/92 VVC 03/24/93 Metal 03/24/93 Metal 03/24/93 Pesticide 03/24/93 VVC
SW033 SW03 SW0	11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 WQP 04/08/92 WQP 04/08/92 WQP 04/08/92 WQP 11/04/92 WQP 11/04/92 WQP 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 WQP 03/24/93 Metal 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Redionuclide 03/24/93 Metal 03/24/93 WQC 03/24/93 WQC 03/24/93 WQC 03/24/93 WQC 03/24/93 WQC 03/24/93 Metal 05/03/94/93 Redionuclide 05/03/94/93 Redionuclide
SW033 SW03 SW0	11/13/91 VOC 11/13/91 VOC 11/13/91 WQP 01/15/92 Metal 01/15/92 Metal 01/15/92 Redionuclide 01/15/92 VOC 01/15/92 WQP 04/08/92 WQP 04/08/92 WQP 11/04/92 Metal 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Redionuclide 11/04/92 Pesticide 11/04/92 VOC 11/04/92 VOC 03/24/93 Redionuclide 03/24/93 Pesticide 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 WQP 03/24/93 Metal 03/24/93 Metal 03/24/93 Metal 03/24/93 Metal

W038	4/7/1992 WQP
W038	8/10/1992 Metal
W038	8/10/1992 Radionuclide
W038	8/10/1992 VOC
W038	8/10/1992 WQP
W038	4/18/1994 Metal
W038	4/18/1994 Pesticide
W038	4/18/1004 Perlionuclide
W038	4/18/1994 SVOC
W038	4/18/1994 VOC
30038	4/18/1994 WQP
W038	9/30/1994 Metal
W038	9/30/1994 Pesticide
W038	9/30/1994 Radionuclide
W038	9/30/1994 SVOC
W038	9/30/1994 VOC
	9/30/1994 WQP
W038	12/13/1994 Metal
SW038	
SW038	12/13/1994 Pesticide
5W038	12/13/1994 Radionuclide 12/13/1994 SVOC
SW038	
50038	12/13/1994 VOC
SW038	12/13/1994 WQP
BW038	3/23/1995 Metal
SW038	3/23/1995 Pesticide
6W038	3/23/1995 Radionuclide
SW038	3/23/1995 SVOC
SW038	3/23/1995 VOC
8W038	3/23/1995 WQP
SW038	6/1/1995 Metal
SW038	6/1/1995 Pesticide
SW038	6/1/1995 Radionuclide
8W038	6/1/1995 SVOC
SW038	6/1/1995 VOC
SW038	6/1/1995 WQP
SW038	9/26/1995 Metal
SW038	9/26/1995 Pesticide
SW038	9/26/1995 Radionuclide
SW038	9/26/1995 SVOC
SW038	9/26/1995 VOC
SW038	9/26/1995 WQP
SW038_	6/8/2004 Metal
SW038	6/8/2004 Radionuclide
SW038	6/8/2004 SVOC
SW038	6/8/2004 VOC
SW129	10/15/1990 Metal
SW129	10/15/1990 Pesticide
SW129	10/15/1990 Radionuclide
SW129	10/15/1990 SVOC
SW129	10/15/1990 VOC
SW129	10/15/1990 WQP
SW129	11/5/1990 Metal
SW129	11/5/1990 Radionuclide
	11/5/1990 VOC
SW129	11/5/1990 WQP
SW129	
SW129	12/6/1990 Metal
5W129	12/6/1990 Radionuclide 12/6/1990 VOC
5W129	
SW129	12/8/1990 WQP
SW129	3/28/1991 Metal
SW129	3/28/1991 Radionuclide
SW129	3/28/1991 VOC
SW129	3/28/1991 WQP
SW129	4/9/1991 Metal
SW129	4/9/1991 Pesticide
SW129	4/9/1991 Radionuclide
SW129	4/9/1991 SVOC
SW129	4/9/1991 VOC
SW129	4/9/1991 WQP
SW129	5/16/1991 Metal



н	=	5/16/1991 VOC	5/16/1991 WQP	6/26/1991 Metal	6/26/1991 Radionuclide	6/26/1991 VOC	6/26/1981 WQP	7/22/1991 Metal	7/22/1991 Radiomuclide	7/22/1991 VOC	7/22/1991 WQP	8/13/1991 Metal	8/13/1991 Radionuclide	8/13/1991 VOC	8/13/1991 WQP	9/18/1991 Metal	9/18/1991 Radiomucide	9/18/1991 VOC	9/18/1991 WQP	10/23/1991 Metal	10/23/1991 Pesticide	10/23/1991 Radionuctide	10/23/1991 SVOC	10/23/1991 VOC	10/23/1991 WQP	10/5/1992 Metal	10/5/1992 Pesticide	10/5/1992 Radionuclide	-	10/5/1992[VOC	-
	SW1Z9	SW129	SW129	SW120	SW129	SW129	SW129	SW129	SW129	SW129	SW129	SW129	SW129	SW129	SW129	SW129	SW129	SW129	SW129	SW129	SW129	SW129	SW128	SW129	SW120	SW500	SW500	SW500	SW500	SW800	SWEGO

Table 4
Sampling and Analytical Summary for OLF Sediment

	Sediment **	1 10 19 19 19 19 19 19 19 19 19 19 19 19 19
	Collection Date:	
INT. DITCH	4/3/1992	
SED41400		Radionuclide
SED51693	7/8/1993	Metal
SED51693	7/8/1993	
SED51693		Pesticide
SED51693		Radionuclide
SED51693	7/8/1993	
SED51693	7/8/1993	
SW036	11/29/1993	Metal
SW036	11/29/1993	
SW036	11/29/1993	
SW036		Radionuclide
SW036	11/29/1993	SVOC
SW036	11/29/1993	VOC
SW506	11/5/1992	
SW506	11/5/1992	Radionuclide
SW507	11/5/1992	
SW507	11/5/1992	Radionuclide

Appendix C

Summary – Removal of Radiologically Contaminated Surface Soil

Summary

Removal of Radiologically Contaminated Surface Soil Original Landfill

Rocky Flats Environmental Technology Site Rev. 1 - October 29, 2004

OVERVIEW

This work involved the removal of surface soil with uranium contamination above the Wildlife Worker Action Levels at four locations within the Original Landfill (see attached figure for locations). Discussion of source and location of the contamination can be found in the Original Landfill IM/IRA section 2.2. Characterization sampling efforts used to define the hot spots are discussed in sections 4.2 and 4.3 of the Original Landfill IM/IRA. The soil excavation was performed in late July 2004.

SCOPE

Preparation

- Straw bales were placed along the up-gradient and down-gradient sides of the planned excavation.
- Empty waste containers were brought into proximity of the planned excavation and placed on plastic sheets.

Remediation


- A sampling program had previously identified four locations of contaminated surface soil. Each location was staked using GPS surveying techniques. A square was drawn on the surface of the soil, with each side of the square extending out 5 feet north, south, east and west from the stake, creating a 10 feet by 10 feet square.
- Soil was then removed to a depth of at least 6-inches with a track-mounted excavator. Equipment was kept out of the excavation to prevent the spread of contamination. A visual inspection was performed to ensure that the entire square had been removed to the required depth. A radiological survey of the excavator was performed following excavation to assure that no contact had been made with contaminated soil.
- Air monitoring was performed throughout the excavation activities by Radiological Operations for worker safety and to ensure no airborne spread of contamination. No readings approaching the suspension limit of 0.3 DAC in RWP 04-RISS-0031 were noted
- All the removed soil was placed directly into IP-1 waste containers. Each location required two containers for a total of 8 containers generated by the project. Plastic sheets and accumulated soil were emptied and placed into the waste containers. All 8 waste containers are awaiting shipment for disposal at Envirocare in Utah as lowlevel waste.

Post-Remediation Sampling

- Two composite samples were collected from within 2 inches of the surface following the excavation of each square.
- One composite sample consisted of soil collected from the middle of each of the four sidewalls of the excavation.
- The other composite sample collected following excavation consisted of soil collected from the surface in the northeast, northwest, southeast and southwest quadrants of the floor, and from the center of the floor.
- Both samples were screened with gamma spectrometry and then sent to an off-site lab for alpha spectrometry confirmation analysis.
- Analytical results from all samples were below action levels for all radionuclides.
- All sample locations were flagged and GPS surveyed. The extent of the excavation was also GPS surveyed.

Erosion Control

- Following receipt of the analyses from the field screen of the samples, permanent erosion controls were performed.
- The edges of each of the four excavations were graded to blend into the surrounding grade.
- Additional straw bales were added to completely surround each of the four excavations.
- Erosion (coconut) mat was placed over the exposed soil of the excavations and over soil disturbed by the movement of the equipment.



Analytical Results

The following are the analytical results from before and after remediation at each of the four hot spots:

Original Landfill Hotspots Sites								
	Alpha Spe	ec	All in pCi	<u>//g</u>	1		-	
	Analytica	l Results <u>F</u> e	ollowing F	Remediation	Analytical Results Prior to Remedia			
[U-234	U-235	U-238		U-234	U-235	U-238	
<u>Site 1</u>				_		<u>. </u>	·	
04F1864-001.002	0.854	0.0892	0.962	Wall Composite		46	2000	
04F1864-002.002	0.939	0.0632	1.16	Floor Composite				
		,_ ,						
<u>Site 2</u>								
04F1749-001.002	4.04	0.669	18.9	Wall Composite	1	19	780	
04F1749-002.002	3.82	0.178	20.5	Floor Composite	1			
		L ₂₄₄			1	1	,	
<u>Site 3</u>								
04F1749-003.002	2.27	0.248	5.55	Wall Composite	1	23	1000	
04F1749-004.002	4.34	0.399	10.8	Floor Composite				
04F1749-005.002	3.52	0.298	9.68	Duplicate				
•								
<u>Site 4</u>								•
04F1869-001.002	0.675	0.16	1.44	Wall Composite	2800	670	38000	
04F1869-002.002	0.756	0	0.809	Floor Composite	1			•
					1			
Wrw_al	300	8	351		300	8	351	

(Wildlife Refuge Worker Action Level)

Surveying within Site 1 of the Original Landfill following excavation.



Original Landfill Site 4 following excavation



Appendix D

Accelerated Action Alternatives Cost Estimates

Original Landfill Accelerated Action Construction Cost Estimate Alternative 1 - No Action

Rocky Flats Environmental Technology Site

Construction Item	Quantity	Units	Unit Price	Cost	Assumptions/Comments
Mobilization/Demobilization	1	LS	\$1,000	\$1,000	
Sign Fabrication	22	signs	\$500	\$11,000	includes signs and posts
Sign Installation	22	signs	\$1,000	\$22,000	
Vegetation/Erosion Control	5	ac	\$2,500	\$12,500	Existing Roadway Vegetation
Subtotal				\$46,500	
Contingency	15	percent		\$6,975	
Construction Project Total (1)				\$53,475	with 30% contingency total = \$60,450

⁽¹⁾ Construction Project Total does not include construction oversight, QA/QC oversight and testing, preparation of work control documents, design, closure certification document or K-H direct costs.

Operations and Maintenance Costs - Annual Costs

Item	Quantity Units	Unit Rate	Cost Assumptions/Comments
Weed control	0.00 acres	\$150	\$0 \$150 per acre/year for weed control
Veg. maintenance/ reseeding	0.00 acres	\$30	\$0 \$30 per acre/year for reseeding
Vegetation monitoring - Fieldwork	0 days	\$600	\$0 1 ecologists x 1 day x 8 hours/day @\$75/hour
Vegetation monitoring - Office	0 days	\$600	\$0 1 ecologists x 1 day x 8 hours/day @\$75/hour
Slope Stability Monitoring - Fieldwork	2 days	\$800	\$1,600 1 engineer x 1 day x 8 hours/day @\$100/hour
Slope Stability Momitoring - Office	4 days	\$800	\$3,200 1 engineer x 1 day x 8 hours/day @\$100/hour
Moitoring Well Sampling - Fieldwork	2 days	\$1,200	\$2,400 1 team x 1 day x 8 hours/day @\$150/hour
Monitoring Well Sampling - Office	4 days	\$800	\$3,200 1 engineer x 1 day x 8 hours/day @\$100/hour
Monitoring Well Sampling - Lab	8 samples	\$600	\$4,800
Monitoring Well Maintenance	1 LS	\$500	, \$ 500
Surface Water Sampling - Fieldwork	2	\$1,200	\$2,400 1 team x 1 day x 8 hours/day @\$150/hour
Surface Water Sampling - Office	4	\$800	\$3,200 1 engineer x 1 day x 8 hours/day @\$100/hour
Surface Water Sampling - Lab	6 samples	\$600	\$3,600
Surface Water Station Maintenance	1 LS	\$500	\$500



Original Landfill Accelerated Action Construction Cost Estimate Alternative 2 - Grading with Soil Cover Rocky Flats Environmental Technology Site

Construction Item	Quantity	Units	Unit Price	Cost	Assumptions/Comments
Mobilization/Demobilization	1 1	LS	\$200,000	\$200,000	
Site Preparation (Clear & Grub)	25	acres	\$4,000	\$100,000	Removal of vegetation & debris
Pregrade Cut	55,000	су	\$6	\$330,000	Cut to reach subgrade elevations/slopes .
Pregrade Fill	105,000	су	\$14	\$1,470,000	Fill to reach subgrade elevations/slopes
Final Grade Preparation	25	acres	\$3,000	\$75,000	Fine Grading
Soil Cover	65000	су	\$14	\$910,000	Rocky Flats Alluvium
Vegetation	30	acres	\$6,000	\$180,000	Native seeding with crimped straw
Surface Drainage Ditches/Diversion	11	LS	\$200,000	\$200,000	
Vegetation/Erosion Control	30	ac	\$2,500	\$75,000	,
Subtotal				\$3,540,000	
Contingency	15	percent		\$531,000	
Construction Project Total (1)				\$4,071,000	Total cost with 30% contingency = \$4,602,000

⁽¹⁾ Construction Project Total does not include construction oversight, QA/QC oversight and testing, preparation of work control documents, design, closure certification document or K-H direct costs.

Operations and Maintenance Costs - Annual Costs

item	Quantity	Units	Unit Rate	Cost	Assumptions/Comments
Weed control	25.00	acres	\$150	\$3,750	\$150 per acre/year for weed control
Veg. maintenance/ reseeding	5.00	acres	\$30	\$150	\$30 per acre/year for reseeding
Vegetation monitoring - Fieldwork	1	days	\$600	\$600	1 ecologists x 1 day x 8 hours/day @\$75/hour
Vegetation monitoring - Office	2	days	\$600	\$1,200	1 ecologists x 1 day x 8 hours/day @\$75/hour
Slope Stability Monitoring - Fieldwork	2	days	\$800	\$1,600	1 engineer x 1 day x 8 hours/day @\$100/hour
Slope Stability Momitoring - Office	4	days	\$800	\$3,200	1 engineer x 1 day x 8 hours/day @\$100/hour
Moitoring Well Sampling - Fieldwork	2	days	\$1,200	\$2,400	1 team x 1 day x 8 hours/day @\$150/hour
Monitoring Well Sampling - Office	4	days	\$800	\$3,200	1 engineer x 1 day x 8 hours/day @\$100/hour
Monitoring Well Sampling - Lab	8	samples	\$600	\$4,800	
Monitoring Well Maintenance	1	LS	\$500 [°]	\$500	•
Surface Water Sampling - Fieldwork	2		\$1,200	\$2,400	1 team x 1 day x 8 hours/day @\$150/hour-
Surface Water Sampling - Office	4		\$800	\$3,200	1 engineer x 1 day x 8 hours/day @\$100/hour
Surface Water Sampling - Lab	. 6	samples	\$600	\$3,600	
Surface Water Station Maintenance	1	LS	\$500	\$500	

Original Landfill Accelerated Action Construction Cost Estimate Alternative 3 - Grading with Soil Cover & Buttress Fill Rocky Flats Environmental Technology Site

Construction Item	Quantity	Units	Unit Price	Cost	Assumptions/Comments
Mobilization/Demobilization	1	LS	\$200,000	\$200,000	
Site Preparation (Clear & Grub)	30	acres	\$4,000	\$120,000	Removal of vegetation & debris
Pregrade Cut	55,000	су	\$6	\$330,000	Cut to reach subgrade elevations/slopes
Pregrade Fill	105,000		\$14	\$1,470,000	Fill to reach subgrade elevations/slopes
Final Grade Preparation	30	acres	\$3,000	\$90,000	Fine Grading
Buttress Fill	60000	су	\$28	\$1,680,000	Structural Fill
Soil Cover	65000	су	\$14	\$910,000	Rocky Flats Alluvium
Vegetation	30	acres	\$6,000	\$180,000	Native seeding with crimped straw
Surface Drainage Ditches/Diversion	1	LS	\$200,000	\$200,000	
Vegetation/Erosion Control	30	ac	\$2,500	\$75,000	
Subtotal				\$5,255,000	
Contingency	15	percent		\$788,250	
Construction Project Total (1)	 		-	\$6,043,250	Total cost with 30% contingency = \$6,831,500

⁽¹⁾ Construction Project Total does not include construction oversight, QA/QC oversight and testing, preparation of work control documents, design, closure certification document or K-H direct costs.

Operations and Maintenance Costs - Annual Costs

Item	Quantity	Units	Unit Rate	Cost	Assumptions/Comments
Weed control	25.00	acres	\$150	\$3,750	\$150 per acre/year for weed control
Veg. maintenance/ reseeding	5.00	acres	\$30	\$150	\$30 per acre/year for reseeding
Vegetation monitoring - fieldwork	1	days	\$600	\$600	1 ecologists x 1 day x 8 hours/day @\$75/hour
Vegetation monitoring - office	2	days	\$600	\$1,200	1 ecologists x 1 day x 8 hours/day @\$75/hour
Slope Stability Monitoring - Fieldwork	2	days	\$800	\$1,600	1 engineer x 1 day x 8 hours/day @\$100/hour
Slope Stability Momitoring - Office	4	days	\$800	\$3,200	1 engineer x 1 day x 8 hours/day @\$100/hour
Moltoring Well Sampling - fieldwork	2	days	\$1,200	\$2,400	1 team x 1 day x 8 hours/day @\$150/hour
Monitoring Well Sampling - Office	4	days	\$800	\$3,200	1 engineer x 1 day x 8 hours/day @\$100/hour
Monitoring Well Sampling - Lab	8	samples	\$600	\$4,800	
Monitoring Well Maintenance	1	LS	\$500	\$500	ı
Surface Water Sampling - Fieldwork	2		\$1,200	\$2,400	1 team x 1 day x 8 hours/day @\$150/hour
Surface Water Sampling - Office	4		\$800	\$3,200	1 engineer x 1 day x 8 hours/day @\$100/hour
Surface Water Sampling - Lab	6	samples	\$600	\$3,600	
Surface Water Station Maintenance	、 1	LS	\$500	\$500	•

Original Landfill Accelerated Action Construction Cost Estimate Alternative 4 - Removal with Offiste Disposal (10% mixed waste & 90% solid waste)

Rocky Flats Environmental Technology Site

Construction Item	Quantity	Units	Unit Price	Cost	Assumptions/Comments
Mobilization/Demobilization	1	LS	\$300,000	\$300,000	
Site Preparation (Clear & Grub)	30	acres	\$4,000	\$120,000	Removal of vegetation & debris
Excavation	160,000	су	\$8	\$1,280,000	Cut & fill to reach subgrade elevations/slopes
Sampling for Disposal Characterization	1,600	samples	\$1,000	\$1,600,000	1 sample every 100 cy
Disposal (Offsite, Mixed Waste)	19,200	су	\$4,000	\$76,800,000	10
Disposal (Offsite, Soild Waste)	172,800	су	\$40	\$6,912,000	90
Pregrade Fill	100,000		\$8	\$800,000	
Final Grade Preparation	30	acres	\$3,000	\$90,000	Fine Grading
Vegetation	30	acres	\$6,000	\$180,000	Native seeding with crimped straw
Surface Drainage Ditches/Diversion	. 1	LS	\$200,000	\$200,000	
Vegetation/Erosion Control	. 30	ac	\$2,500	\$75,000	
Subtotal				\$88,357,000	
Contingency	15	percent		\$13,253,550	
Construction Project Total (1)				\$101,610,550	Total cost with 30% contingency = \$114,864,100

⁽¹⁾ Construction Project Total does not include construction oversight, QA/QC oversight and testing, preparation of work control documents, design, closure certification document or K-H direct costs.

Original Landfill Accelerated Action Construction Cost Estimate Alternative 4 - Removal with Offiste Disposal (25% mixed waste & 75% solid waste)

Rocky Flats Environmental Technology Site

Construction Item	Quantity	Units	Unit Price	Cost	Assumptions/Comments
Mobilization/Demobilization	1	LS	\$300,000	\$300,000	
Site Preparation (Clear & Grub)	30	acres	\$4,000	\$120,000	Removal of vegetation & debris
Excavation	160,000	су	\$8	\$1,280,000	Cut & fill to reach subgrade elevations/slopes
Sampling for Disposal Characterization	1,600	samples	\$1,000	\$1,600,000	1 sample every 100 cy
Disposal (Offsite, Mixed Waste)	48,000	су	\$4,000	\$192,000,000	25
Disposal (Offsite, Soild Waste)	144,000	су	\$40	\$5,760,000	75
Pregrade Fill	100,000		\$8	\$800,000	
Final Grade Preparation	30	acres	\$3,000	\$90,000	Fine Grading
Vegetation	30	acres	\$6,000	\$180,000	Native seeding with crimped straw
Surface Drainage Ditches/Diversion	1	LS	\$200,000	\$200,000	
Vegetation/Erosion Control	30	ac	\$2,500	\$75,000	
Subtotal		·		\$202,405,000	
Contingency	15	percent		\$30,360,750	
Construction Project Total (1)			<u> </u>	\$232,765,750	Total cost with 30% contingency = \$263,126,500

⁽¹⁾ Construction Project Total does not include construction oversight, QA/QC oversight and testing, preparation of work control documents, design, closure certification document or K-H direct costs.

Appendix E

Wetland Mitigation Plan

Original Landfill Project Wetland Mitigation Plan For The Rocky Flats Environmental Technology Site

MARCH 2004

CLASSIFICATION EXEMPTION CEX-105-0

INTRODUCTION	. 1
PROJECT INFORMATION	
Location of Project/Ownership	1
Responsible Parties	<i>I</i>
Historical Background of OLF	
ENVIRONMENTAL DESCRIPTION OF OLF AREA	2
Physiography	2
Climate	
Geology	
Groundwater	4
Surface Water	
Ecological Setting	6
Existing Functions and Values	8
Buffers	
Drouger Approach	٥و
PROJECT APPROACH	0
IMPACTED WETLAND AREA DESCRIPTIONS	10
MITIGATION APPROACH	10
Mitigation Goals and Objectives	10
MITIGATION APPROACH	11
Mitigation Bank Approach	11
Mitigation Bank Approach Project Funding	11
References	12

Original Landfill Project Wetland Mitigation Plan

Introduction

The Rocky Flats Environmental Technology Site (the Site) is a U.S. Department of Energy (DOE) facility located in rural northern Jefferson County, Colorado, which is approximately 16 miles northwest of Denver. It is approximately 6,200 acres in size. The developed portion of the site, referred to as the Industrial Area (IA), is centrally located within RFETS and occupies approximately 400 acres. The Rocky Flats Buffer Zone surrounds the IA and occupies the remaining 5,800 acres. The Original Landfill (OLF) is located in the RFETS Buffer Zone (BZ), south of the Industrial Area (IA; Figure 1). The proposed alternative (for which this wetland mitigation plan was prepared) consists of the removal of surface soil "hot spots" (completed in August 2004), clearing and grubbing of the landfill area, area grading, and implementing the presumptive remedy by placement of a soil cover, cover re-vegetation, monitoring, and institutional controls. Remediation activities will require unavoidable impacts to wetlands within the OLF project area. The wetland mitigation plan outlines the approach and basic plan that will be taken to mitigate for wetland impacts.

Project Information

Location of Project/Ownership

The OLF area located south of the IA at T2S,R70W, Sec. 10 and 15 (Figure 1). The OLF occupies approximately 20 acres.

Responsible Parties

Joseph A. Legare, Director Project Management Division Rocky Flats Environmental Technology Site U.S. Department of Energy 10808 Hwy. 93 Golden, CO 80403-8200 Ph. 303-966-5918

Bob Davis, Project Manager Kaiser-Hill Company, L.L.C. 10808 Hwy. 93 Golden, CO 80403-8200 Ph. 303-966-7872

Historical Background of OLF

For historical information on the OLF see the "Draft Interim Measure/Interim Remedial Action for the Original Landfill (including IHSS Group SW-2; IHSS 115 and IHSS 196, Filter Backwash Pond" document (K-H 2004a) of which this wetland mitigation plan is an Appendix.

Environmental Description of OLF Area

Physiography

The Site is located on the western margin of the Colorado Piedmont section of the Great Plains Physiographic Province at an elevation of approximately 6,000 feet (K-H 1996a). The Colorado Piedmont is characterized as an area of dissected and denuded topography, representing an old erosion surface along the eastern margin of the Rocky Mountains. Several pediments (broad sloping planes formed by coalescing alluvial fans along a mountain front) developed across bedrock in the RFETS area during the Quaternary Period (Scott 1963). The Rocky Flats pediment is the most extensive of these pediments.

The IA is located on a relatively flat surface of the Rocky Flats pediment. The pediment surface has been eroded by Walnut Creek on the north and Woman Creek on the south. As a result, the pediment surface is located at an elevation of 50 feet to 150 feet above the creeks. The grade of the gently eastward-sloping surface of the Rocky Flats pediment ranges from one percent in the IA to approximately two percent just east of the IA. Further east, the pediment's nearly flat-lying surface gives way to lower gently rolling terrain of the High Plains section of the Great Plains Physiographic Province (K-H, 1996a).

Four ephemeral creeks drain the surface water from the Site. The surface water that flows from the northern portion of RFETS is drained by Rock Creek, which is a northeast-trending tributary of Coal Creek. The central and southern portions of the site are drained by Walnut Creek, South Walnut Creek, and Woman Creek. These drainages are all tributaries of Big Dry Creek that flows eastward. Coal Creek separates all of the streams on the Rocky Flats pediment from the Front Range foothills. Surface water flow in these creeks is generally ephemeral; however, some reaches may support intermittent or perennial flow.

Climate

The climate at the Site is characterized as semi-arid (K-H, 1996a) with a mean annual precipitation of approximately 15.5 inches, based on 20-year means for Boulder and Lakewood, Colorado. The wettest season is spring (March through May), which accounts for approximately 40 percent of the annual precipitation, much of which is snow. Thunderstorms during the summer months provide another 30 percent of the annual precipitation. The precipitation gradually declines through the summer, fall and winter (K-H, 1996a). Average annual pan evaporation in central Colorado is approximately 55 inches (DBS 2001). The predominant wind direction at the Site is northwesterly, and average wind speeds are under 15 miles per hour. Daytime heating causes upslope winds to form, with northeasterly winds common over the broad South Platte River Valley. More localized southeasterly winds

also occasionally occur during the day at the Site because the terrain is oriented southeast toward Standley Lake and the City of Arvada. The winds reverse at night with a shallow westerly drainage wind forming over the site and a broad southerly drainage wind forming over the South Platte River Valley (DOE 1999).

The Site is noted for its strong winds. Gusty winds frequently occur with thunderstorms and the passage of weather fronts. The highest wind speeds occur during the winter as westerly windstorms, known as Chinooks. The windstorm season at the site extends from late November into April, with the height of the season usually occurring in January. The windstorms typically last 8 to 16 hours, with wind speeds exceeding 75 miles per hour in almost every season. Wind gusts exceeding 100 miles per hour are experienced every three to four years (DOE 1999).

Geology

Geologic units beneath the OLF consist of unconsolidated Quaternary deposits that lie unconformably over Cretaceous claystone bedrock. The unconsolidated surface deposits include the Rocky Flats Alluvium that dominates the surface at the Site, colluvial materials that form the slopes of the Woman Creek valley, and valley fill materials on the bottom of Woman Creek valley (EG&Ga, 1995; K-H, 1996a). These materials overlie the Laramie Formation bedrock (Metcalf & Eddy 1995). Geologic units in the OLF area are described below.

Rocky Flats Alluvium

The Rocky Flats Alluvium was deposited by a system of coalescing alluvial fans aggraded by debris flows and braided streams along the base of the Front Range at the mouth of Coal Creek Canyon (EG&G 1995a). The alluvial deposits generally consist of beds and lenses of poorly sorted, clast- and matrix-supported, white to pink, sandy cobbly gravel, gravelly sand, and silty sand (K-H, 1996a). The thickness of this unit ranges from about 3 feet to 30 feet in the areas where the pediment deposits overlie Cretaceous-aged bedrock (K-H, 1996a).

Colluvial Deposits

Colluvial deposits along the valley slopes at the Site are middle Pleistocene to Recent in age (K-H, 1996a). The colluvial material commonly consists of dark-gray to light-reddish-brown, silty sand, sandy silt, clayey silt, and silty clay that contains minor amounts of boulders and cobbles. The unit locally includes clast- and matrix-supported boulders and cobbles, and coarse to fine gravel in a silty-clay matrix. These materials are well graded to poorly graded and unstratified to poorly stratified. Clasts are typically subangular to subrounded, and their sedimentological composition reflects that of the bedrock and surface deposits from which they were derived. The thickness of the colluvial deposits ranges from 3 to 15 feet.

In the OLF area the unconsolidated colluvial deposits consist of sandy, clayey gravel (derived from the adjacent Rocky Flats Alluvium) to sandy clay (Metcalf & Eddy 1995). The colluvium is frequently mixed with fill material in the landfill. Soil borings indicate that the

thickness of the colluvium ranges from 1 to 13 feet. The colluvium is damp to moist, although it can be wet near its contact with the Laramie Formation (Metcalf & Eddy 1995).

Valley-fill Alluvium

Valley-fill alluvium, located along the Woman Creek drainage, includes channel and terrace deposits related to the modern stream. These Recent alluvial deposits are commonly grayish-brown, slightly cobbly, silty sand to sandy, clayey silt in the upper part, and poorly sorted, clast supported, slightly cobbly, gravel in a light yellowish brown, clayey, silty sand matrix in the lower part (K-H, 1996a). Clasts are mostly subangular quartzite, with a minor amount of subrounded sandstone derived from older Quaternary deposits. The thickness of these deposits ranges from approximately 3 to 15 feet, with an average of about 10 feet. During geotechnical investigations at the OLF (Metcalf & Eddy 1995), valley fill alluvium was encountered in three boreholes along the toe of the landfill. The alluvium consisted of medium dense to dense, sandy, silty, clayey gravel with cobbles. The alluvium ranged from 5 to 7 feet thick, and groundwater was encountered as shallow as two feet below ground surface (bgs).

Laramie Formation

Bedrock in the OLF area is Laramie Formation (K-H, 1996a). The Cretaceous-aged Laramie Formation is approximately 600 feet to 800 feet thick. It has been informally divided into upper and lower members (K-H, 1996a). The upper Laramie Formation is generally distinguished from the lower Laramie Formation where the upper Laramie Formation is dominantly composed of fine-grained sedimentary rocks (primarily claystone with no thick sandstone beds). The upper part of the upper Laramie Formation is approximately 300 feet to 500 feet thick, and consists primarily of olive-gray to yellowish orange claystone with large ironstone nodules. A few thin, discontinuous coal seams occur in the upper Laramie Formation. Lenticular beds of platey laminated or friable, calcareous, fine-grained, light olive-gray sandstone occur in the upper Laramie Formation, particularly in the upper portions of the formation.

In the OLF area, the Laramie Formation is a weak claystone formation that underlies the soil-bearing slopes in the area of the OLF (Metcalf & Eddy 1995). It is severely weathered (soft, plastic and moist) in its near-surface aspect and underlies surficial materials in over 50 percent of borings. Moderately weathered Laramie Formation underlies the severely weathered Laramie Formation and is locally plastic, soft, damp, and fractured. It was encountered underlying surficial material in approximately 35 percent of the borings, indicating that the severely eroded Laramie Formation was sometimes displaced through sliding or erosion. Unweathered Laramie is the deepest component of the upper member and is similar to the moderately weathered Laramie Formation, although somewhat drier (Metcalf & Eddy 1995).

Groundwater

The uppermost groundwater is shallow, unconfined groundwater that occurs within the Rocky Flats Alluvium, colluvial deposits, valley fill alluvium, and the weathered Laramie Formation.

This water bearing zone is also referred to as the Uppermost Hydrostratigraphic Unit (UHSU) (EG&G, 1995b). The UHSU is not an "aquifer" because it is not capable of yielding significant and useable quantities of groundwater to wells or springs (EG&G, 1995b). Soil borings in the Rocky Flats alluvium indicate that groundwater appears hydraulically disconnected from the LHSU groundwater. A review of water level change in time reveals that average saturated heights above the weathered bedrock are quite variable. For example, saturated heights range from 0 to 5 feet along Woman Creek; below the bedrock in the east-central waste area; 5 to 10 feet in the central waste area; 0 to 5 feet in the western waste area; and from 10 to more than 40 feet above the bedrock north of the OLF.

UHSU groundwater typically flows towards the nearest stream, or seep area. Flows are strongly affected by unconsolidated material hydraulic properties, and the morphology and orientation of the underlying claystone bedrock and topographic surfaces. Within the OLF waste extent, areas of greater vegetation density typically indicate zones of shallow groundwater or seeps. Groundwater elevations vary seasonally, typically on the order of 5 to 10 feet primarily due to direct precipitation recharge and evapotranspiration. The highest groundwater levels occur in the late winter and spring, and the lowest groundwater levels occur during the late summer and fall. This variability typically causes any seep discharges in the area to be ephemeral.

Surface Water

The OLF is located within the Woman Creek drainage basin, which extends eastward from the base of the foothills near the mouth of Coal Creek Canyon to Standley Lake. The long-term average annual yield generated by this basin is 32.1 acre-feet, with average storms producing surface flows of 4 to 7 cubic feet per second (cfs). During extreme precipitation events (greater than the 15-year return occurrence based on precipitation), surface flows up to 40 cfs have been generated. Although seasonal flows can be low, Woman Creek receives continuous flow from Antelope Springs Creek. The reach of Woman Creek adjacent to the OLF is a gaining reach of stream (groundwater discharges to surface water); however, this inflow is likely due to inflow from the south side of the valley and seepage from the old orchard area (K-H, 1996a).

The Woman Creek drainage basin has an artificial water control structure, the South Interceptor Ditch (SID), which intercepts runoff and routes it to Pond C-2. This runoff would normally flow into Woman Creek or percolate into the underlying subsurface materials of the basin. The Woman Creek diversion dam routes all Woman Creek flows less than the 100-year flood peak around Pond C-2 (K-H, 1996a). With the completion of the Woman Creek Reservoir, located just east of Indiana Street and operated by the city of Westminster, Woman Creek flows are detained in cells of the reservoir until the water quality has been assured by monitoring of Site discharges via Woman Creek Reservoir into the Walnut Creek Drainage below Great Western Reservoir.

In the past, most natural flows in Woman Creek were diverted to Mower Reservoir and did not exit the Site via Woman Creek. This is no longer the case. The Mower Ditch headgates were upgraded, and water in Woman Creek leaves RFETS via Woman Creek (at GS01) and enters the Woman Creek Reservoir. In the past, Pond C-2 (located off-channel in the Woman Creek drainage) was sampled and then pumped to the offsite Broomfield Diversion Ditch. Currently, the Site discharges Pond C-2 directly into Woman Creek via pump (at GS31); the water then flows to the Woman Creek Reservoir.

Ecological Setting

Vegetation

The overall OLF work area crosses several plant community and soil types. The pediment top on the north portion of the OLF project area is composed largely of the Rocky Flats Alluvium. The upper part of the OLF work area is located on this surface. The soil types on this surface are classified as Flatirons very cobbly sandy loam and Nederland very cobbly sandy loam (SCS 1980). The vegetation on this surface is predominantly xeric tallgrass prairie on the western portions of the Site and gradually changes to a needle and threadgrass community as the alluvium thins to the east (K-H 1997). Common species on the xeric tallgrass prairie include big bluestem (Andropogon gerardii), little bluestem (Andropogon scoparius), mountain muhly (Muhlenbergia montana), needle and thread grass (Stipa comata), blue grama (Bouteloua gracilis), side-oats grama (Bouteloua curtipendula), sunsedge (Carex heliophila), Canada bluegrass (Poa compressa), and a variety of other graminoid and forb species (K-H 1997). The dominance of these species varies from location to location.

The hillside area in the OLF area is dominated by mesic mixed and reclaimed grassland communities. Although native soils on the hillslopes at the Site are classified as Denver-Kutch-Midway clay loams (SCS 1980), much of the OLF area has been reworked and disturbed. Common species on mesic mixed grassland portions of the OLF includes blue grama, side-oats grama, western wheatgrass (Agropyron smithii), green needle grass (Stipa viridula), Kentucky bluegrass (Poa pratensis), Canada bluegrass, Japanese brome (Bromus japonicus), and other forbs and graminoids (K-H 1997). However, along much of the SID and other disturbed areas of the OLF hillside the vegetation consists of exotic, reclamation grasses such as smooth brome (Bromus inermis), intermediate wheatgrass (Agropyron intermedium), and other non-native species. The noxious weeds, diffuse knapweed (Centaurea diffusa) and Scotch thistle (Onopordum acanthium) are also prevalent, along with several others that are less abundant in the area.

Jurisdiction wetlands in the OLF area are shown in Figure 1. Within the OLF area, the South Interceptor Ditch (SID) has also been designated as a jurisdictional wetland. South of the landfill area, wetland areas are associated with springs and riparian fringe in the Woman Creek drainage. The SID wetland is a narrow, linear ditch, with some cattails (*Typha latifolia*) and coyote willow (*Salix exigua*), and as such has lower functional integrity than natural wetlands associated with Woman Creek (COE 1994). On the hillside above the SID, additional wet areas have developed over the years where outflow pipelines from the IA have exited. At some of these locations, enough moisture has been present at or near the ground surface to support the growth of vegetation characteristic of wetter areas. Coyote willow, plains cottonwood trees (*Populus deltoides*), and arctic rush (*Juncus balticus*) are common in some of these areas. Along Woman Creek, the wetlands are dominated by plains cottonwood,

coyote willow, false indigo (Amorpha fruticosa), snowberry (Symphoricarpos occidentalis), arctic rush, and various other plants.

Fauna

Wildlife use in the OLF area is comparable to that documented elsewhere on the grasslands and riparian areas at the Site (K-H 2001). Common wildlife species that could be encountered include small mammals such as deer mice (Peromyscus maniculatus), prairie voles (Microtus ochrogaster), meadow voles (Microtus pennsylvanicus), and house mice (Mus musculus), which provide forage for predators like raptors and covotes (Canis latrans). Common raptors at the Site include red-tailed hawks (Buteo jamaicensis), Swainson's hawks (Buteo swainsoni), great horned owls (Bubo virginianus), and kestrels (Falco sparverius). Herptiles would be represented by boreal chorus frogs (Pseudacris triseriatus maculata), leopard frogs (Rana pipiens), and prairie rattlesnakes (Crotalus viridis). A variety of songbirds could be found utilizing the grassland and riparian habitats at different times of the year. Western meadowlarks (Sturnella neglecta) and vesper sparrows (Pooecetes gramineus) are common inhabitants of the grasslands, while Bullock's orioles (Icterus bullockii). American goldfinches (Carduelis tristis), yellow warblers (Dendroica petechia), brownheaded cowbirds (Molothrus ater), and other songbirds are common along the streams. Mule deer (Odocoileus hemionus) and an occasional white-tailed deer (Odocoileus virginianus) also utilize the habitat in and around the OLF work area.

Even though the OLF is a highly disturbed site, the area includes portions of the Preble's Meadow Jumping Mouse (Preble's mouse; Zapus hudsonius preblei) protection areas at the Site and wetland areas associated with surface water in the area. The Preble's mouse is listed as threatened by the U.S. Fish and Wildlife Service (USFWS). This listing provides special protection for the species under the Endangered Species Act, and potential remedial actions at the OLF must be evaluated for potential impacts to the Preble' mouse. Preble's mice have been identified in all the major drainages of the Site: Rock Creek, Walnut Creek, and Woman Creek, and the Smart Ditch drainages. The plant communities present in these areas provide a suitable habitat for this small mammal. Preble's mice at the Site are restricted to riparian areas and pond margins, apparently requiring multi-strata vegetation with abundant herbaceous cover. Preble's populations at the Site are found in association with the riparian zone and seep wetlands across the Site. The vegetation communities that provide Preble's habitat include the Great Plains riparian woodland complex, tall upland shrubland, wetlands adjacent to these communities, and some of the upland grasslands surrounding these areas. Recent studies have produced a better understanding of population centers of the species at the Site (K-H 1999, 2000, 2001).

Preble's mice have been captured along Woman Creek in the area of the OLF where a significant amount of suitable habitat occurs. The Preble's mice were captured in riparian areas with well-developed shrub canopies and an understory of grasses and forbs. This is typical of habitats occupied by the subspecies throughout its range (K-H 1996b). The current Preble's protection areas at the Site includes a portion of the OLF area below the SID. The Preble's habitat continues east-west along Woman Creek. Section 7 consultations with the

U.S. Fish and Wildlife Service are ongoing to address Preble's mouse impacts resulting from the OLF project (K-H 2004b).

Existing Functions and Values

The function and value of the wetlands within the OLF work area provide several functions including water quality enhancement, filtering or trapping of sediment, nutrients, and toxic compounds, ground water recharge and discharge, minor flood conveyance and attenuation, and providing habitat for many plant and animal species at the Site.

Buffers

The areas surrounding the OLF work area and the wetlands within the work area include undeveloped portions of the Buffer Zone and the developed IA. The IA is located to the north of the OLF project area while the Buffer Zone surrounds the project area on the other three sides.

Project Approach

The OLF is being addressed as an accelerated action under the Rocky Flats Cleanup Agreement (RFCA), a combined CERCLA federal facility agreement and RCRA/CHWA Corrective Action Order. Based upon an evaluation of the OLF operation and the waste types and the risks posed by exposure pathways from the OLF, an accelerated action consistent with municipal and military landfill presumptive remedies of source containment after hot spot removal has been determined to be appropriate for the OLF (K-H 2004a). The proposed action is to implement the presumptive remedy of source containment. There are two pathways of exposure to be addressed by source containment:

- direct exposure to disposed waste and commingled soil; and
- surface erosion and runoff of contaminants into surface water.

The components of the source containment remedy that are necessary to address these pathways are:

- a landfill cover to prevent direct contact with landfill soil or debris;
- the landfill cover must also adequately control erosion caused by water run on and run off;
 and
- institutional controls to supplement the engineering controls to appropriately monitor and maintain the remedy.

In addition to these components, ground water and surface water monitoring will be done to evaluate whether contamination is potentially migrating from the source area and creating a path of exposure through surface water.

The proposed alternative consists of the removal of surface soil "hot spots" (completed in August 2004), clearing and grubbing of the landfill area, area grading, and implementing the presumptive remedy by placement of a soil cover, cover re-vegetation, monitoring, and institutional controls. The surface soil hot spots would be removed prior to all other activities at the site to enhance worker safety.

Control measures would be implemented during this activity to control the spread and release of contamination. The control measures would include the establishment of work zones, decontamination procedures, dust suppression methods, traction mats, visual inspections, and radiological surveys. Work would be suspended when environmental conditions such as during high winds that greatly increase the possibility of the spread of contaminated materials. Monitoring would be performed, as necessary, to verify that there has been no release of contaminated materials.

Excavated areas would be carefully monitored with appropriate field screening devices and laboratory analyses to determine the outer limits of the contaminated surface soil areas. Field screening using standard Site instrumentation would be used to verification the depth and extent of excavation to below the action levels (e.g., NE Electra, micro-R, Ludlum 12, HPGE). Confirmation soil samples would be taken for final isotopic analysis. Following the confirmation samples, non-impacted soils from locations adjacent to the excavated areas would be moved to reduce surface slopes and to blend excavated areas into the surrounding surfaces prior to the action for the entire OLF.

The waste fill areas would be graded to a constant 18 percent (5.5:1) slope angle using a cut and fill approach that is as balanced as possible. Standard earth-moving equipment, such as dozers, hoes or scrapers, would be used to cut the areas where the slope exceeds the desired 18 percent and to fill the areas where the slope is less than the desired 18 percent slope. It is estimated that approximately 70,000 cubic yards of waste fill material would be moved during the process. Control measures would be implemented during the grading process to control the spread and release of waste materials in the OLF. The control measures would include the establishment of work zones, decontamination procedures, dust suppression methods, traction mats, visual inspections, and radiological surveys. Work would be suspended when environmental conditions could greatly increase the possibility of the spread of contaminated materials. Monitoring would be performed, as necessary, to verify that there has been no release of contaminated materials. Erosion controls will be used to control runoff/sedimentation from the project area.

After the grading of the landfill surface is complete, a soil cover will be placed over the landfill to a minimum thickness of 2 feet. About 65,000 cubic yards of local or onsite soil will be used to construct the cover. The soil cover will be compacted sufficiently to provide a stable cover system to promote surface water runoff, reduce surface water ponding, and increase overall slope stability. Revegetation of the soil cover with native species will slow runoff and allow "greater" infiltration. The seeding will be conducted along with erosion control matting or mulch to prevent erosion of the cover while allowing the vegetation to establish a strong stand.

As a result of the remediation actions on the OLF approximately 1.24 acres of jurisdictional wetlands (COE 1994) will be impacted.

Impacted Wetland Area Descriptions

Based on the 1994 U.S. Corps of Engineers wetland report for the Site (COE 1994), approximately 1.24 acres of jurisdictional wetlands may be disturbed by the remediation and construction activities. Table 1 lists the wetland types and acreages that may be impacted. Figure 1 shows the locations of these areas.

Table 1. Wetland Impacts

Wetland Type	Acreage	
Palustrine emergent, seasonally and semipermanently flooded	0.61	
Palustrine, scrub-shrub, seasonally flooded	0.63	
Total	1.24	

The SID wetland locations consist of a linear, man-made ditch with some cattails and coyote willow. The wetland impacts along Woman Creek will occur in palustrine emergent and scrub-shrub wetland areas dominated by cattails, arctic rush, snowberry, coyote willow, and some plains cottonwood trees.

Mitigation Approach

A plan to mitigate wetland impacts has been developed to offset the wetland losses resulting from the OLF project. The typical approach to wetland issues is to 1) avoid impacts, 2) minimize impacts that are unavoidable, and 3) mitigate for unavoidable impacts. The OLF project is a required cleanup and remediation action under RFCA. Total avoidance of impacts to the wetlands is not feasible due to the remediation requirements. The wetland losses (1.24 acres) will be mitigated through the use or purchase of wetland banking credits. NOTE: The actual number of acres of wetland disturbed will be mitigated should the actual amount of disturbance be different from that described. If based on the final design of the toe of the landfill slope, it is possible to re-establish the wetlands at that location, the possibility of insitu wetland re-creation may be evaluated. This would involve contouring the disturbed areas to re-establish the stream channel and then revegetating the area with native wetland/riparian species by seeding, using potted materials, or planting stakes or poles. However, at the present time, the final design of the cover is not available and so it is not possible to evaluate this possibility in any detail.

Mitigation Goals and Objectives

1. Mitigate OLF wetland impacts through the use or purchase of wetland mitigation bank credits (mitigation ratio = 1:1). The total wetland acreage to be mitigated for is estimated to be approximately 1.24 acres.

Rationale for Choice

Given the lack of detailed plans and uncertainty of what will occur along Woman Creek at the bottom of the OLF project area and the permanent loss of wetlands under the OLF cover, the use of wetland mitigation bank credits is the preferred approach.

Mitigation Bank Approach

The first mitigation bank option may use the DOE's Standley Lake wetland mitigation bank for credits to offset wetland impacts in the OLF area. This bank was constructed several years ago by the DOE for use to offset wetland damages at Rocky Flats. At the time of writing, however, the Standley Lake bank had not been certified officially by the EPA although it is expected that this certification will occur soon. If the Standley Lake wetland bank credits cannot be applied to the OLF, then purchase of wetland bank credits from an off-site wetland mitigation bank will be necessary. A mitigation ratio of 1:1 will be used for use or purchase of wetland bank credits from either bank. Two potential commercial wetland mitigation banks that are present along the Front Range of Colorado are listed below.

Potential Off-Site Commercial Wetland Mitigation Banks

Middle South Platte River Wetland Mitigation Bank, Erie, CO

Banker: Land and Water Resources, Inc., 9575 W. Higgins Rd., Suite 470, Rosemont, IL 60018

John Ryan, Ph. 708-878-3903

Mitigation credits were still available as of June 2002. Cost: 60K to 80K+ per acre, variable depending on number of acres purchased.

Mile High Wetland Bank, Brighton, CO

Banker: Mile High Wetland Group, LLC, 80 South 27th Ave., Brighton, CO 80601

Laurie Rink, Ph. 303-659-7002

Mitigation credits are available as of July 2002. Cost: \$80,000 per acre, with some decrease for volume purchases.

The wetland acres disturbed (debits) will be tracked in the Site's wetland debit/credit spreadsheet. The use of any wetland mitigation banking credits will also be tracked in the spreadsheet. NOTE: The actual number of acres of wetland disturbed will be mitigated should the actual amount of disturbance be different from that described.

Project Funding

Funding for the project is being provided by the DOE as part of the Site cleanup and closure activities that are being directed and overseen by Kaiser-Hill Company, L.L.C.

References

COE. 1994. Rocky Flats Plant Wetlands Mapping and Resource Study. U.S. Army Corps of Engineers, Omaha District. December 1994.

DBS. 2001. Feasibility Study for the Solar Evaporation Ponds at RFETS. Daniel B. Stephens & Associates, Inc. December.

DOE. 1999. Vegetation Management Environmental Assessment. Rocky Flats Environmental Technology Site, Golden, CO. April.

EG&G. 1995a. Geologic Characterization Report for the Rocky Flats Environmental Technology Site, Volume I of the Sitewide Geoscience Characterization Study. Golden, Colorado. March. EG&G Rocky Flats, Inc. Golden, CO.

EG&G. 1995b. Hydrogeologic Characterization Report for the Rocky Flats Environmental Technology Site. Volume 2, Text. EG&G Rocky Flats, Inc. Golden, CO.

Geomatrix. 1995. Evaluation of the Capability of Inferred Faults in the Vicinity of Building 371. Geomatrix Consultants, Inc. Rocky Flats Environmental Technology Site, Colorado. January.

K-H. 1996a. Final Phase 1 RFI/RI Report, Woman Creek Priority Drainage, Operable Unit. April. Rocky Flats Environmental Technology Site, Golden, CO.

K-H. 1996b. 1996 Annual Report: Preble's Meadow Jumping Mouse Study at Rocky Flats Environmental Technology Site. Prepared by Exponent for Kaiser-Hill Company, LLC. Rocky Flats Environmental Technology Site, Golden, CO.

K-H. 1997. Site Vegetation Report: Terrestrial Vegetation Survey (1993-1995) for the Rocky Flats Environmental Technology Site. Prepared by Exponent for Kaiser-Hill Company, LLC. Rocky Flats Environmental Technology Site, Golden, CO.

K-H. 1999. 1998 Annual Wildlife Report for Rocky Flats Environmental Technology Site. Prepared by Exponent for Kaiser-Hill Company, LLC. Rocky Flats Environmental Technology Site, Golden, CO.

K-H. 2000. 1999 Annual Wildlife Report for Rocky Flats Environmental Technology Site. Prepared by Exponent for Kaiser-Hill Company, LLC. Rocky Flats Environmental Technology Site, Golden, CO.

K-H. 2001. 2000 Annual Wildlife Report for Rocky Flats Environmental Technology Site. Prepared by Exponent for Kaiser-Hill Company, LLC. Rocky Flats Environmental Technology Site, Golden, CO.




K-H. 2004a. Draft Interim Measure/Interim Remedial Action for the Original Landfill (including IHSS Group SW-2; IHSS 115 and IHSS 196, Filter Backwash Pond. Kaiser-Hill Company, LLC, Rocky Flats Environmental Technology Site, Golden, CO.

K-H. 2004b. Preble's Meadow Jumping Mouse Protection Plan, Programmatic Biological Assessment, Part I, Appendix A, U.S. Department of Energy, Rocky Flats Field Office. Kaiser-Hill Company, LLC. Rocky Flats Environmental Technology Site, Golden, CO.

Metcalf & Eddy. 1995. Geotechnical Investigation Report for Operable Unit No. 5, ME-EEG-T-0009. Rocky Flats Environmental Technology Site, Golden, CO. September (Draft).

Scott, G.R. 1963. Quaternary Geology and Geomorphic History of the Kassler Quadrangle, Colorado. USGS Professional Paper 421, pp. 1-70.

SCS. 1980. Soil Survey of Golden Area, Colorado. U.S. Department of Agriculture, Soil Conservation Service, Washington, DC.



Appendix F

Comment Responsiveness Summary



Integrated Flow and VOC Fate and Transport Modeling for the Original Landfill

Rocky Flats Environmental Technology Site, Golden, Colorado

TECHNICAL MEMO



December 2004

Integrated Flow and VOC Fate and Transport Modeling for the Original Landfill at the Rocky Flats Environmental Technology Site, Golden, Colorado

Technical Report

December 6, 2004

Ву

Integrated Hydro Systems, LLC

Executive Summary

Development and results of integrated flow and Volatile Organic Compounds (VOC) fate and transport modeling to support the Original Landfill (OLF) Interim Measure/Interim Remedial Action (IM/IRA) document are described in this technical memorandum. The integrated hydrologic flow code MIKE SHE is used to simulate conditions that develop for closure configurations because system flows are complex, and realistic closure configuration model parameter values can be assigned in the physically-based code. Development of the integrated flow model follows an approach similar to that used in former Site-Wide Water Balance (SWWB) integrated flow modeling (KH, 2002), where saturated and unsaturated flows are dynamically coupled with overland and channel flows. Development of the fate and transport modeling follows the approach used in more recent modeling to support the Comprehensive Risk Assessment (KH, 2004) where a reactive transport code is used to simulate attenuation processes such as degradation, sorption, dispersion and diffusion.

The primary objective of the flow modeling involves simulating integrated flow conditions within the OLF for four closure configurations. In addition, the fate and transport of elevated levels of VOCs within the OLF are modeled to estimate a range of long-term groundwater concentrations at possible surface water discharge locations. The four OLF closure configurations considered include the following:

- Scenario 1 IA reconfiguration, no OLF modifications;
- Scenario 2 IA reconfiguration, OLF regrade (basecase);
- Scenario 3 IA reconfiguration, OLF regrade, buttress fill, and drain;
- Scenario 4 IA reconfiguration, OLF regrade, buttress fill, drain, and slurry wall.

These objectives are addressed in several steps. First, available geologic, hydrologic and chemical data, including recent water levels and geotechnical information, are compiled into a Graphical Information System (GIS) to conceptualize flow within the OLF. A localized, fully-integrated flow model is then developed for the OLF area based on these data for current conditions to demonstrate that parameter values are appropriate for simulating closure configurations. The integrated model is modified to simulate the hydrologic changes to the system for each of the four closure configurations. Finally, fate and transport of elevated levels of PCE and its daughter products are conservatively evaluated from inferred constant concentration source areas within the OLF using a reactive transport code.

Current Configuration Data Evaluation

Several observations can be made from evaluation of available hydrologic data that are relevant to the geotechnical stability analysis:

- Evaluation of historical groundwater level data in the OLF area indicates groundwater levels above the weathered bedrock range from 0 to 10 feet over about two thirds of the waste extent, while the levels are actually below the bedrock over the remaining one third.
- 2) For current conditions, average annual observed groundwater depths throughout the OLF area vary from over 20 feet depth at the top of the hillslope to less than 3 feet near Woman Creek and in shallow bedrock areas within the OLF.
- 3) Seasonal levels vary from 5 to 10 feet within the OLF.

Integrated Flow Model Development and Performance

The integrated flow model developed uses a much finer grid resolution of 25 feet than the former SWWB model to more accurately simulate the spatial variability of factors that affect flows in the OLF such as permeability distributions, surface topography and the weathered bedrock surface. The model only considers the Upper Hydrostratigraphic Unit (UHSU) material, but this unit is subdivided into four distinct layers that differentiate the OLF waste, fill material, native soils and the underlying weathered bedrock. Flow through the unsaturated zone is simulated using USGS mapped soils distributions and the current waste extent. Overland flow simulated in paved areas, or in unpaved areas when precipitation rates exceed the infiltration rate of the soils, is then routed into surface channels where it dynamically interacts with subsurface flows, or exits the model. The model also includes spatially distributed and time-varying inflow to channels from subsurface drains in the IA.

Results of model simulations for the current configuration using climate data from the year 2000 show that input parameter values reproduce average flow conditions well over the OLF. The model simulates average annual water levels within the OLF to within a foot of observed levels, and over the entire model area to within just over a foot with a standard deviation of less than four feet.

Closure Configuration Model Development and Simulation Results

Several model parameters are adjusted in the integrated flow model to simulate hydrologic effects of the closure configurations. In Scenario 1, adjustments are made to model input only in the IA. In the remaining scenarios adjustments are made to both the IA and OLF area. Closure modifications in the IA are similar to those assumed in the SWWB modeling (KH, 2002), where pavement and buildings are removed, subsurface drains are deactivated, and the surface of the

IA is regraded and revegetated. For scenarios 2 through 4, the surface topography in the OLF is regraded using a surface that is only preliminary and will be modified based on this modeling and geotechnical analyses. In scenario 3, a structural buttress fill extending to the weathered bedrock surface and an upgradient drain are assumed along the southern extent of the OLF. In scenario 4, a slurry wall extending to the weathered bedrock surface is placed upgradient of the OLF to simulate hydrologic effects of reducing lateral inflow from the IA into the OLF.

A typical climate sequence, based on year 2000 data developed in the SWWB modeling (KH, 2002), is reasonable for simulating flow conditions within the model because this sequence reproduces time-averaged (10 years) water levels well in the current configuration model. To support geotechnical stability analyses, a wet-year climate sequence (based on 100 years) is simulated for Scenario 2 to approximate conservatively high groundwater levels that develop within the OLF area.

Modeling results can be summarized as follows:

- Model results show that reconfiguring the IA (Scenario 1) causes groundwater levels to increase less than one foot over the OLF. However locally, levels decrease less than 3 feet and increase up to 4 feet. Simulated depths are similar to current conditions and range from less than 5 feet to over 20 feet within the OLF.
- 2) Simulated effects of regrading the OLF and reconfiguring the IA (Scenario 2) for a typical climate sequence (WY2000) cause levels to increase an average of about two feet. Locally they decrease up to 3.5 feet and increase up to nearly 7 feet. This is due in part to the adjustments in evapotranspiration caused by changes in the depth to groundwater below the new regrade. Simulated groundwater depths vary throughout the OLF, mostly in response to 'fill' and 'cut' adjustments. At the western and eastern waste extents depths increase to near 40 feet due to increased fill thickness. Saturated heights above the bedrock increase from 3 to 7 feet over most of the OLF compared to Scenario 1.
- 3) Simulating a wet-year climate (100-year basis) sequence for Scenario 2 causes average annual groundwater levels within the OLF to increase about two feet (ranging from 0 to 4 feet over the OLF) compared to those for a typical climate sequence. Results also indicate that groundwater reaches ground surface in shallow bedrock areas, though this could be controlled by increasing the regrade surface height above bedrock. These simulated groundwater/levels represent conservatively high levels that might be sustained for up to a month during a wet year climate sequence.
- 4) Simulated effects of adding a buttress fill and upgradient buttress drain (Scenario 3) cause average annual groundwater levels to decrease less than

one foot over the OLF. However locally, the drain causes levels to decrease up to 3 feet over the southern half of the OLF. Levels near the drain decrease about 11 feet. Simulated annual discharge rates from the drain are less than 1 gpm.

- 5) Simulated effects of adding a slurry wall to Scenario 3 (Scenario 4) cause average annual groundwater levels over the OLF to change less than one foot. However levels downgradient (south) of the slurry wall decrease less than 3 feet, while those upgradient of the slurry wall (north) increase up to 3 feet within about 300 feet.
- 6) Results of the current and closure simulations conducted in this study indicate that surface regrading results in the largest impact on OLF groundwater levels. Modeling also shows that seeps may occur under wetter climate though this could be controlled by adjusting the surface regrade topography.
- 7) A sensitivity analysis to determine the most sensitive parameters controlling water levels in the OLF was not conducted in this study, though results suggest that the regraded surface, bedrock depth and waste area hydraulic properties are the most sensitive. An uncertainty analysis to assess the range of hydrologic response to input parameter value uncertainty was also not conducted in this study. As such, simulated responses could change depending on the specific parameter values used, though reasonable values were assumed.

Fate and Transport Model Development and Simulation Results

Only tetrachloroethene (PCE) and its daughter products are evaluated in this study because they are detected in the OLF. Average annual groundwater velocity field estimated using the integrated flow model for Scenario 1 and 3 are used as the basis for reactive transport modeling using the RT3D code.

Reactive fate and transport modeling of PCE (and daughter products) detected in groundwater in the OLF waste indicate that concentrations at Woman Creek remain well below surface water standards for both Scenario 1 and 3. More conservative fate and transport scenarios (most conservative parameter values) show that groundwater concentrations may reach the buttress drain at detectable concentrations, though they remain below the surface water standards. Results of the fate and transport simulations assume that the PCE source concentrations remain constant during any regrade of the area.

1.0 Introduction

Results of integrated flow modeling and VOC fate and transport associated with the Original Landfill (OLF) flow system are described in this technical memo in support of the OLF Interim Measure/Interim Remedial Action (IM/IRA). Key factors affecting the stability of the proposed OLF closure configuration are groundwater levels and their fluctuations with time. Although current groundwater level data in the OLF area are useful in assessing spatial characteristics such as groundwater depths, flow directions, and fluctuations in time, they should not be used to assess these characteristics for closure configurations. As groundwater flow at RFETS is complex, 3-dimensional and depends on many factors, an integrated flow model, using a similar approach to that described in the Site-Wide Water Balance Modeling report (KH, 2002), is developed to assess flow conditions under both current (WY2000) and closure configurations. The fate and transport of VOCs detected in the OLF are assessed using an approach similar to that described in a recent VOC fate and transport modeling report (KH, 2004).

The objectives of the modeling are described in Section 1.1. The steps taken to meet these objectives are outlined in Section 1.2. A brief discussion of available data and an analysis of these data are presented next in Section 2, followed by a description of the development of the integrated flow model and simulated results for current conditions in Section 3. In Section 4, specific closure scenarios are outlined, assumptions are outlined, and results are summarized. VOC fate and transport modeling is described in Section 5. Finally, key steps in this study are summarized and conclusions outlined in Section 6.

1.1 Objectives

The objectives of the modeling include the following:

- 1) Simulate integrated flow conditions within and surrounding the OLF waste for the following closure configurations:
 - No modifications to current OLF system;
 - Regrade OLF area and IA closure;
 - Regrade OLF area and IA closure, structural buttress fill downhill of waste, and upgradient drain; and
 - Same as above, but includes a slurry wall upgradient of waste.
- 2) Assess the following:
 - Change in groundwater levels for each closure configuration from current conditions; and

- Change in groundwater depths.
- 3) Assess the fate and transport of VOCs:

1.2 Approach

Several steps required to meet the objectives above are outlined graphically on Figure 1-1. The approach used here in developing the integrated model for the OLF system is similar to that described in (KH, 2002). Current system flows are first simulated to demonstrate that assumed model parameter values reproduce observed flow conditions adequately. Then several model input parameters are adjusted to simulate the integrated hydrologic system response of the closure configurations. The MIKE SHE code, developed by DHI (1999), is used to simulate the integrated flows at the OLF because it is physically-based (uses non-empirical flow equations) and fully-integrated, coupling subsurface flows (unsaturated and saturated zone) with surface flows (overland and channel flow). Effects of evapotranspiration and snowmelt are also considered in the OLF integrated flow model, and scenarios are continuously simulated using spatially-variable sub-hourly climate input over a full year.


A sensitivity analysis was not performed in this study. However, previous integrated modeling (KH, 2002, and KH, 2004) showed that the weathered bedrock surface, surface topography and hydraulic conductivity distribution are among the most important parameters. An uncertainty analysis to assess effects of input parameter uncertainty was also not conducted in this study, though reasonable values were assumed. As such, simulated responses presented could change depending on the specific parameter values assumed.


An important step in the development of the integrated flow model for the current configuration was updating the existing GIS database, developing new surfaces with recent data, and incorporating this information into the integrated flow model through a series of database algorithms.

2.0 Available Data and Analysis

The OLF study area, waste extent, and existing surface topography are shown on Figure 2-1. Vertical profile locations are also shown that correspond with the locations cited in Metcalf and Eddy (1995). The Building 444/440/460 area north of the OLF was included in the study to consider hydrologic impacts of the closure on the OLF area.

Available geologic, hydrologic, and chemical data in the OLF and surrounding area were reviewed and compiled into a spatial Geographical Information System (GIS) database to support model development. Most of this information was obtained from former SWWB modeling (KH, 2002), though several new datasets were prepared specific to the OLF. For example, a more accurate ground






surface topography in the OLF area was obtained. In addition, all available field geologic borehole logs were reviewed to define approximate waste and bedrock surface contacts. Recent logs in the area, along with the higher resolution surface topography, were used to construct weathered and unweathered bedrock surfaces throughout the OLF area that are more accurate than previously approximated surfaces (KH, 2002). The refinement of the weathered bedrock surface is important as this was found to strongly control groundwater flow gradients and levels in hillslope areas.


Vertical profiles at lines shown on Figure 2-1 are illustrated on Figure 2-2. The existing topography, regrade surface, weathered bedrock, and unweathered bedrock are shown including approximate time-averaged groundwater levels determined through spatial interpolation. Thicknesses of unconsolidated material from the Building 440 area, south through the waste to Woman Creek, range from over 20 feet to less than 5 feet (Figure 2-3). Thickness of the waste material is also variable, ranging from less than 5 feet in the east-central area to more than 12 feet to the west. Unweathered bedrock thickness remains relatively uniform at about 20 feet through the OLF area.


More than 10 years of groundwater level data (Figure 2-4) in the OLF area, including recent 2004 data, were also reviewed and indicate several things. Groundwater levels in most wells within the OLF vary less than 5 feet annually, while surrounding, external, water levels typically vary between 5 to 10 feet over the year (some range from 10 to 15 feet per year, but are likely related to increased recharge from snow removal and mounding), reflecting seasonal recharge, evapotranspiration and drainage effects. The difference in magnitude of groundwater fluctuations between the two areas suggests that unsaturated and saturated zone hydraulic properties of the waste area may differ somewhat from non-waste areas.


Groundwater depths (Figure 2-5) in the Upper Hydrostratigraphic Unit (UHSU) decrease from about 20 to 30 feet below ground near the Building 440 area on the mesa to about 15 feet below ground within the waste, to less than about 5 feet below ground along Woman Creek. In Lower Hydrostratigraphic Unit (LHSU) wells in the OLF area groundwater depths are significantly lower than in nearby UHSU wells (57194, 71194 are greater than 100 feet, indicating that the LHSU and UHSU are hydraulically disconnected in the area.

Finally, a potentiometric surface map, constructed using time-averaged water level information, indicates a west-east groundwater divide just north of the Building 444. Therefore, groundwater south of this divide eventually flows towards Woman Creek.









Time-averaged Groundwater Depths (ft) below ground surface at well locations

U 1-5

5 - 10

10 - 20

20 - 30

30 - 99.296

Note:

1) Several locations shown along Woman Creek are control points used in defining initial conditions for the integrated flow model and are not wells.

Figure 2-5

Time-averaged groundwater depths in OLF study area

3.0 Integrated Model Development and Performance for Current Conditions


3.1 Integrated Model Development

Constructing the integrated flow model involved several steps. First, the integrated flow model is based on a 25-foot numerical grid, as shown on Figure 3-1, to better simulate local flow conditions associated with the OLF (the SWWB model used a 200-foot grid resolution). Several GIS techniques were used to convert spatial hydrogeologic GIS information onto the finer grid. Spreadsheet algorithms were then used to convert gridded GIS information into model input. Figure 3-2 shows modeled utility corridors and drain distributions and Figure 3-3 shows modeled vegetation and unconsolidated soil distributions in the OLF area. These are examples of OLF GIS coverages converted into model input.

The saturated portion of the model is specified using four layers, the upper two for unconsolidated materials and drains, and the lower two for weathered bedrock. At each model cell, an unsaturated zone column is discretized into more than 100 cells to describe the non-linear dynamics including infiltration, depth-varying evapotranspiration, redistribution, and eventually groundwater recharge (using a full Richard's based equation). Overland flow and channel flow are simulated like in the SWWB modeling. Unsaturated and saturated zone hydraulic properties determined through integrated model calibration conducted for the original SWWB model and subsequent VOC fate and transport modeling (KH, 2004) were specified in the OLF model. However, new values for drain conductances and hydraulic properties for the waste were determined through initial OLF model simulations.

3.2 Model Performance – Current Conditions

The integrated model of the current system configuration, using climate data from October 1999 through September 2000, reproduced observed flow conditions well. Model simulations require that the WY2000 climate sequence is cycled for three consecutive years to stabilize effects of prescribed initial conditions. Model performance is assessed by comparing time-averaged simulated and observed water levels at wells throughout the model area (Figure 3-4). Results indicate that the model simulated time-averaged heads are within 3 feet in most locations. This is considered good given the complexity of flows in the area and change in topographic relief over the model area. Furthermore, residuals appear to decrease to within 3 feet from the upper waste area to Woman Creek. In some areas, levels are over-estimated between 3 to 7 feet. This discrepancy can be explained by an underestimation of drain discharge in the area, increased localized recharge due to runoff from paved areas into unpaved areas, or the reduced groundwater discharge to channels. These factors become unimportant in closure configurations.








Figure3-2 Simulated Utility Corridors and Subsurface Drains



Vegetation Distributions



Unconsolidated Soil Distributions

NOTE:

- 1) Colors represent major vegetation zones
- 2) Six major vegetation zones defined
 - -mesic
 - -xeric
 - -riparian
 - -wetland
 - -paved areas (only surface evaporation-interception)
 - -dirt areas (only evaporation)


NOTE:

- 1) Twenty-eight soil zones defined to simulate flow through the unsaturated zone.
- 2) Major distribution defined by USGS surficial material definitions (i.e., Qrf, Qls, Qp, Qc, Qt, Qp, and Qls),
- 3) Within major distributions, soil types further subdivided based on depth to bedrock (5-foot depth increments).

General Note:

1) The vegetation and unconsolidated soil distributions are only shown here to indicate the resolution and spatial variability included in the integrated flow model. Refer to the SWWB modeling report for more detailed description based on field mapping (KH, 2002).

Figure 3-3 Model Input -Soil and Vegetation Distributions



Simulated minus observed groundwater depths (feet).

Note:

1) Negative (red)
difference denotes
model under-simulates
groundwater levels.

2) Positive (blue) denotes model oversimulates groundwater levels. Figure 3-4. Difference between simulated and observed timeaveraged groundwater depths

Simulated annual surface flow at gage GS22, though less than observed indicates most surface events are captured in peak flow, timing of events, snowmelt, and baseflow. Additional adjustment of drain conductances would likely improve the comparison between observed and simulated surface flows. However, the drain conductances are unimportant in evaluating impacts of closure configurations on system flows as the drains are removed in these simulations.

Figure 3-5 and 3-6 show the simulated annual average groundwater depths based on the existing topography and the simulated average annual saturated heights above the weathered bedrock surface, respectively. Simulated depths are quite variable over the OLF model area. Depths range from 7 to 10 feet north of Building 440/444/460 area to greater than 20 feet at the top of the slope and then decrease to 3 to 7 feet near Woman Creek. Saturated heights above the weathered bedrock, important to the stability analysis in the waste area, only range from 5 to 10 feet in the west-central area, and are actually unsaturated in the east-central area.

4.0 Closure Configuration Integrated Flow Model Development and Simulation Results

4.1 Closure Configuration Scenarios

Changes to the integrated hydrologic flow regime at and surrounding the OLF were evaluated for several different closure configurations. For each of the closure configurations, it is assumed that the configuration in the Industrial Area (IA) (north of the OLF) undergoes modifications consistent with those described previously in both the SWWB modeling (KH, 2002) and more recent VOC fate and transport modeling (KH, 2004). The only differences in the IA closure configuration from these previous evaluations are the surface topography and drainage. These were updated during August 2004 and are used in this analysis. Major assumptions in the IA closure configuration are briefly summarized below. Specific OLF-related changes are described next for each scenario.

Key IA Closure Configuration Assumptions include the following:

- Buildings are removed, but basements for B444 are assumed to remain;
- Pavement removed:
- Sanitary, storm and footing drains deactivated;
- Leaky water supply lines deactivated;
- Surface topography regrade (over IA); and
- Surface drainage modifications.





Figure 3-5

annual groundwater depths (ft)

Current Conditions - Simulated (Typical Climate) average




Scenario-specific Closure Configurations and Assumptions include the following:


- Scenario 1 IA Regrade-only
 - IA undergoes closure configuration (as per above);
 - No changes made to existing OLF area; and
 - Typical climate year sequence assumed (WY2000).
- Scenario 2 IA & OLF Regrade (basecase)
 - IA undergoes closure configuration (as per above);
 - OLF area is regraded;
 - OLF area is re-vegetated;
 - Fill material is used as part of regrade (assume Qrf); and
 - Typical and Wet Year (100-year basis) climate year sequence assumed.
- Scenario 3 IA & OLF Regrade, Buttress fill, Buttress drain
 - Same as Scenario 2;
 - Includes Buttress fill and Buttress drain on Upgradient side; and
 - Typical climate year sequence assumed (WY2000)
- Scenario 4 IA & OLF Regrade, Buttress fill, Buttress drain, and Slurry Wall
 - Same as Scenario 3, but includes slurry wall immediately north of the waste area footprint.

In the 'basecase' OLF closure configuration scenario (Scenario 2), both the IA and OLF are reconfigured. To the north of the OLF, the IA is closed as described in the VOC Fate and Transport integrated modeling (KH, 2004). Pavement, buildings, drains and water supply lines are removed, the IA is regraded, and then re-vegetated. Over the OLF area, only the ground surface is regraded and re-vegetated.

Three-dimensional perspective views of the current, regrade, and weathered bedrock surfaces are shown on Figure 4-1a. The change in surface topography and unconsolidated material thickness is shown on Figure 4-1b. Two notable changes occur in the OLF area that cause notable changes in local hydrologic flow conditions. First, the regrade results in increases in unconsolidated thickness up to 30 feet, and decreases up to 20 feet. This in turn increases and decreases the depth to the weathered bedrock from the new regrade. These changes cause groundwater level adjustments throughout the waste area described further in Section 4.2.



Regraded area considered in this modeling




:etoN


1) Thicknesses shown in feet.

areas. fill areas and volume than cut topography results in greater 2) Change in surface

decrease in thickness. Negative numbers indicate a increase in thickness. 3) Positive numbers indicate



Change in unconsolidated thickness due to regrade (ft).



Change in surface topography (Regrade surface minus existing surface).

thickness. Change in OLF surface topography and unconsolidated Figure 4-1b

DLL ametay2 onlyH betargetni

4.2 Simulation Results - Closure Configurations

Results of model simulations are summarized in this section. Simulated groundwater depths below surface topography are plotted for each scenario to assess possible seep development. Plots of simulated water levels above the top of the weathered bedrock are used in the geotechnical slope stability analysis. Finally the change in water levels between different scenarios is shown to demonstrate the relative effects of each scenario's modification on the OLF hydrologic conditions.

4.2.1 Scenario 1 - No OLF Regrade


This scenario was simulated to assess hydrologic effects over the OLF area due to only IA reconfiguration. Figure 4-2 shows simulated average annual groundwater depths over the OLF area. A reduced model area was utilized to improve computational efficiencies. The range of simulated depths are similar to those calculated for current conditions and range from less than 3 feet in the west model area to more than 23 feet in the northern waste and south-central area. Average annual simulated saturated heights above weathered bedrock (Figure 4-3a) are similar to current conditions, but increase slightly in the western area (from <1 to 15 feet).

The change in groundwater levels from current conditions (Figure 4-3b), which reflects the relative effect of the IA reconfiguration, indicates levels increase less than a foot on average over the OLF. Locally, levels decrease less than 2.5 feet and increase up to 4 feet. The average increase is caused by a combination of factors, but is mostly due to removal of footing drains and removal of impervious areas.

4.2.2 Scenario 2 – OLF Regrade

A number of figures were generated to illustrate how the OLF area responds to the combination of IA closure (Scenario 1) and only a regrade in the OLF area. Simulated average annual depths for the OLF regrade show changes that mostly reflect the adjustment in unconsolidated material thicknesses (i.e., see Figure 4-1). As shown on Figure 4-4, depths increase in areas where the existing topographic surface is 'filled', while depths tend to decrease relative to the new surface topography, in areas where the existing surface is 'cut'. The range of depths is similar to that which develops in Scenario 1, and also do not indicate seep discharge, though levels are within 3 feet of surface.

An annual water balance evaluation of only the OLF waste extent (as shown on Figure 3-1), summarized on Figure 4-5) indicates that most precipitation



Simulated average annual groundwater depths (feet).

-10 - 0

0-5

5-10

10 - 15

15 - 20


20 - 45

Note:


- 1) Scenario 1 assumes no modifications to the OLF, but IA is closed per site configuration.
- 2) Negative numbers (yellow) indicate groundwater levels are above ground surface. These areas represent seeps.
- 3) Scenario 1 assumes no modifications to the OLF.

Figure 4-2

Scenario 1 - Simulated (Typical Climate) average annual groundwater depths (ft)



Simulated average annual groundwater height above weathered bedrock (feet).




Note:


- 1) Negative numbers indicate areas where groundwater levels are below weathered bedrock.
- 2) Positive numbers indicate saturated groundwater heights above the top of the weathered bedrock surface.
- 3) Scenario 1 assumes no modifications to the OLF.

Figure 4-3a

Scenario 1 - Simulated (Typical Climate) average annual saturated height above Weathered Bedrock surface (ft).



Change in groundwater levels (feet)




Note:

- 1) Change in groundwater levels calculated by subtracting Scenario 1 simulated depths from current condition depths.
- 2) Negative numbers indicate areas where groundwater levels decrease from Calibration.
- 3) Positive numbers indicate saturated groundwater heights above the top of the weathered bedrock surface.
- 4) Change in levels south of Woman Creek invalid due to different model boundaries.
- 5) Scenario 1 assumes no modifications to the OLF.

Figure 4-3b

Scenario 1 change in groundwater levels (feet) from current conditions (Effect of IA reconfiguration only)

groundwater depths (ft)



NOTE:

Infiltration differs from Net recharge because it is calculated as infiltration at ground surface only. Lateral UHSU inflow and outflows is calculated for waste, underlying colluvium, and weathered bedrock. Highest lateral flows are through the coluvium. Net recharge is calculated as net flux across water table and includes evapotranspiration loss through the unsaturated zone (Actual recharge is much higher).




Figure 4-5
Scenario 2 Simulated water balance for waste area (in/yr)

infiltrates due to relatively high surface soil permeabilities. Of this infiltration, most is lost via evapotranspiration through the root zone. A smaller, but important portion of this infiltration recharges the groundwater flow system. Although net annual recharge is less than annual lateral inflow or outflow (through the entire UHSU, including weathered bedrock and underlying Colluvium), it includes annual discharge to evapotranspiration via the unsaturated zone. Local recharge and evapotranspiration account for most of the groundwater level seasonal variability and changes in groundwater storage with time, rather than lateral flow variations.

In Figure 4-6 the average annual saturated height above weathered bedrock increases in the north-western part of the OLF and less notably in the east-central area (previously levels below top of bedrock) compared to Scenario 1.

As a conservative estimate of high water levels within the OLF area, a 100-year basis wet-year climate was simulated for Scenario 2. Results shown on Figure 4-7 indicate groundwater discharges to surface in the south-eastern and central areas of the OLF. This condition represents the wettest part of the wet-year climate sequence. Although not shown, it may also be possible for localized groundwater levels to reach ground surface in Scenario 2 during high recharge periods. For the wet climate, saturated heights above the weathered bedrock (Figure 4-8) increase above the typical climate, ranging from 5 to 15 feet over most of the OLF, but in localized areas it exceeds 20 feet. Average annual wet-year groundwater levels increase an average of about 1.3 feet over the waste area. Compared to average annual levels for a typical climate year, the highest wet-year levels increase from about 2 feet within the waste area to more than 4 feet south of the waste area.


Figure 4-9 illustrates changes in water table elevation from Scenario 1. Results indicate levels increase within most of the OLF 3 to 7 feet. This increase in elevation also appears to cause an increase north of the OLF in the B440/B444 area. Levels appear to decline up to 3 feet immediately south of the waste extent.

4.2.3 Scenario 3 – OLF Regrade, Buttress fill, and Buttress drain

A buttress fill and upgradient buttress drain are simulated in Scenario 3 at the southern end of the waste area (see Figure 3-1). The buttress fill is assumed to extend to the top of the weathered bedrock and is assigned a very low hydraulic conductivity (1e-10 m/s). It is represented in the model as using cells wide as indicated by the boundary shown on Figure 3-1. The buttress drain is also assumed to extent to the top of the weathered bedrock. In the model, a low resistance drain is simulated by assigning a high conductance to the drain cells.

604

Simulated average annual groundwater height above weathered bedrock (feet).



Note:

1) Scenario 2 assumes the OLF is regraded along with the IA.

No other modifications in the OLF assumed.

Negative numbers indicate areas where groundwater levels are below weathered bedrock.

 Positive numbers indicate saturated groundwater heights above the top of the weathered bedrock surface.




Figure 4-6

Scenario 2 - Simulated (Typical Climate) average annual saturated height above Weathered Bedrock surface (ff)






Figure 4-7

Scenario 2 - Simulated (Wet-Year Climate) minimum annual groundwater depths (ft)



Integrated Hydro Systems, LLC

Scenario 2 - Simulated (Wet-Year Climate) maximum annual saturated height above Weathered Bedrock surface (ft)



Simulated groundwater depths and saturated heights above the weathered bedrock (Figures 4-10 and 4-11, respectively) are similar those generated in Scenario 2, but decline due to the buttress drain upgradient of the buttress fill. Compared to Scenario 2, levels decrease up to about 3 feet for the lower half of the OLF extent and decrease up to about 7 feet near the buttress drain upgradient of the buttress, as shown on Figure 4-12.

4.2.4 Scenario 4 – OLF Regrade, Buttress fill, Buttress drain, and Slurry Wall

The effect of adding a slurry wall to the last scenario with a regrade, buttress fill and buttress drain is described here. The slurry wall, placed immediately north of the waste extent in the integrated model, is assigned a very low hydraulic conductivity (1e-10 m/s), similar to the buttress fill. The water balance performed on Scenario 2 indicates that most of the lateral inflow occurs in the unconsolidated material of the UHSU. Therefore, extending the slurry wall from ground surface to the top of the weathered bedrock will block most of the lateral inflow to the OLF from upgradient.

Simulated average annual groundwater depths, shown on Figure 4-13 are similar to Scenario 3. Only a slight adjustment to the average annual saturated height above the weathered bedrock is simulated (Figure 4-14). This is further indicated on Figure 4-15, showing the change in groundwater levels compared to Scenario 3. Results show that levels immediately upgradient of the slurry wall increase less than 3 feet, while those immediately downgradient, within the waste area, decrease less than 3 feet. The change in levels is constrained to about 200 to 300 feet on either side of the slurry wall. Based on this simulation and the lower weathered bedrock permeabilities, additional declines in the water table are unlikely if the slurry wall were extended through the weathered bedrock.


5.0 Fate and Transport of VOCs in the OLF area


5.1 Model Development


The fate and transport of VOCs detected in the OLF area are evaluated for closure Scenarios 2 and 3. These two scenarios are selected for fate and transport simulations because they represent configurations with the greatest potential for producing higher downgradient VOC concentrations. Specifically, impacts to surface water (Woman Creek, or seeps) are assessed. Available groundwater sampling data indicate elevated concentrations of Tetrachloroethylene (PCE) were detected in the central portion of the OLF waste area.


The approach used to model the fate and transport of PCE (and its daughter products) from the waste area is consistent with that described in detail in the IA VOC fate and transport modeling study (KH, 2004). The RT3D code is used to


Figure 4-10 Tigure 4-10 Tigure 4-10 dinaste) average annual groundwater depths (ft)	Scenario 3 – Simulate	JLJ ,zmajsvžč onbyH bejragejr
3) Scenario 3 includes OLF regrade, Buttress fill and drain.		
drain on upgradient side of buttress. 2) Megative numbers (yellow) indicate groundwater levels are above ground surface. These areas represent seeps.		Woman Creek
Mote: 1) Scenario 3 assumes OLF regrade, clay buttress and toe		
01-3 31-01 51-20		
Simulated average annual groundwater depths (feet). -10 - 0 -10 - 5		











model the fate and transport of PCE so that advection and attenuation processes including degradation, sorption, diffusion and dispersion could be considered.

Three-dimensional time-averaged water levels (WY2000), estimated using the integrated flow model for Scenarios 2 and 3, are first used to define approximate steady-state velocity fields for the RT3D simulations. A number of conservative fate and transport simulations are then conducted to estimate a range of long-term groundwater concentrations at surface water discharge locations given uncertainties in source location, depth and timing, among other parameters controlling fate/transport. Source locations simulated in the model are based on inferred locations (shown on Figure 5-1) and long-term concentrations are assumed constant. This assumption is reasonable because concentrations at wells in the OLF show no clear increasing, or decreasing trends in time.


The following long-term simulations were conducted for Scenarios 2 and 3:


- Scenario 1 Basecase;
- Scenario 2 Low degradation (one tenth of basecase);
- Scenario 3 Low porosity (halved for all layers);
- Scenario 4 Low degradation and increase in hydraulic conductivity (one tenth and three times for all layers, respectively);
- Scenario 5 Advection-dispersion only (no sorption, degradation, or ET loss), increase in hydraulic conductivity (2 times all layers); and
- Scenario 6 Advection=dispersion only.
- Fate and Transport Simulation Results


Results from both simulations show that neither PCE, nor its daughter products, reach Woman Creek at concentrations above surface water action concentrations for any of the conservative simulations considered. Results are summarized on Figures 5-2 and 5-3, for scenarios 2 and 3, respectively. For scenario 3, with the buttress fill and buttress drain, more conservative simulations indicate it is possible for concentrations to reach the drain, but they are likely to be lower than the surface water action levels.

6.0 Summary and Conclusions

This summary presents modeling the integrated hydrologic response of current conditions and four different OLF closure configuration scenarios, and the fate and transport from inferred source areas. Several steps were required. First, all available data, including recent water levels and geotechnical information, were compiled into a GIS and analyzed. A localized, fully-integrated flow model was then developed for the OLF area based on these data for current conditions. Model performance runs were simulated to demonstrate that parameter values were appropriate for simulating closure configurations. Next, the integrated model was modified to simulate the four closure configurations to show the







relative effects of each scenario. A 100-year wet-climate sequence was simulated in the basecase, OLF regrade scenario to approximate the highest groundwater levels in the OLF area. Finally, the fate and transport of elevated levels of PCE within the OLF was evaluated using the reactive transport code, RT3D, for two closure configurations.

The four OLF closure configurations considered in the integrated flow model include the following:

- Scenario 1 IA reconfiguration, no OLF modifications;
- Scenario 2 IA reconfiguration, OLF regrade (basecase);
- Scenario 3 IA reconfiguration, OLF regrade, buttress fill, and buttress drain; and
- Scenario 4 IA reconfiguration, OLF regrade, buttress fill, buttress drain, and slurry wall.

Several conclusions can be made from the integrated OLF flow model simulations and VOC fate and transport modeling. These are summarized below:

- A combination of natural and anthropogenic factors affects local groundwater levels within the OLF area in the current (pre-closure) configuration. These include the following:
 - 1) Anthropogenic factors:
 - 1) Drains north of OLF in IA;
 - 2) Utility corridors in IA;
 - 3) Leaky water supply lines (Bldg 124 area); and
 - 4) Pavement and buildings.
 - 2) Natural factors:
 - 1) Hillslope configuration:
 - 1) Weathered bedrock surface;
 - 2) Unconsolidated thickness spatial distribution; and
 - 3) Vegetation distribution/types.
 - 2) Climate sequence characteristics; and
 - 3) Unsaturated and saturated zone hydraulic properties of waste and surrounding media.
- 2) Historical time-average groundwater levels in the OLF area indicate saturated heights above the weathered bedrock range from 0 to 10 feet over about two thirds of the waste extent, while the levels are actually below the bedrock over the remaining one third.
- 3) For current conditions, average annual observed groundwater depths throughout the OLF area vary from over 20 feet depth at the top of the

- hillslope to less than 3 feet near Woman Creek and in shallow bedrock areas within the OLF.
- 4) Model results show that reconfiguring the IA (Scenario 1) causes groundwater levels to increase less than one foot over the OLF. However locally, levels decrease less than 3 feet and increase up to 4 feet. Simulated depths are similar to current conditions and range from less than 5 feet to over 20 feet within the OLF.
- 5) Simulated effects of regrading the OLF and reconfiguring the IA (Scenario 2) for a typical climate sequence (WY2000) cause levels to increase an average of about two feet. Locally they decrease up to 3.5 feet and increase up to nearly 7 feet. Simulated groundwater depths vary throughout the OLF, mostly in response to 'fill' and 'cut' adjustments. At the western and eastern waste extents depths increase to near 40 feet due to increased fill thickness. Saturated heights above the bedrock increase from 3 to 7 feet over most of the OLF compared to Scenario 1.
- 6) Simulating a wet-year climate (100-year basis) sequence for Scenario 2 causes average OLF groundwater levels to increase about two feet (ranging from 0 to 4 feet) compared to a typical climate sequence. Results also indicate that groundwater reaches ground surface in shallow bedrock areas, though this could be controlled by increasing the regrade surface height above bedrock. These simulated groundwater levels represent conservatively high levels that might be sustained for up to a month during a wet year climate sequence.
- 7) Simulated effects of adding a buttress fill and upgradient buttress drain (Scenario 3) cause average annual groundwater levels to decrease less than one foot over the OLF. However locally, the drain causes levels to decrease up to 3 feet over the southern half of the OLF. Levels near the drain decrease about 11 feet. Simulated annual discharge rates from the drain are less than 1 gpm.
- 8) Simulated effects of adding a slurry wall to Scenario 3 (Scenario 4) cause average annual groundwater levels over the OLF to change less than one foot. However levels downgradient (south) of the slurry wall decrease less than 3 feet, while those upgradient of the slurry wall (north) increase up to 3 feet within about 300 feet.
- 9) Results of the current and closure simulations conducted in this study indicate that surface regrading results in the largest impact on OLF groundwater levels. Modeling also shows that seeps may occur under wetter climate though this could be controlled by adjusting the surface regrade topography.
- 10)Reactive fate and transport modeling of PCE (and daughter products) detected in groundwater in the OLF waste indicate that concentrations at

Woman Creek remain well below surface water standards for both Scenario 1 and 3. More conservative fate and transport scenarios (most conservative parameter values) show that groundwater concentrations may reach the buttress drain at detectable concentrations, though they remain below the surface water standards. Results of the fate and transport simulations assume that the PCE source concentrations remain constant during any regrade of the area.

11)A sensitivity analysis to determine the most sensitive parameters controlling water levels in the OLF was not conducted in this study, though results suggest that the regrade surface, bedrock depth and waste area hydraulic properties are the most sensitive. An uncertainty analysis to assess the range of hydrologic response to input parameter value uncertainty was also not conducted in this study. As such, simulated responses could change depending on the specific parameter values used, though reasonable values were assumed.

7.0 References

- Kaiser-Hill (KH). 2002. Site-Wide Water Balance Model Report for the Rocky Flats Environmental Technology Site. May.
- Kaiser-Hill (KH), 2004. Fate and Transport Modeling of Volatile Organic Compounds at Rocky Flats Environmental Technology Site. April.
- Kaiser-Hill (KH), 2004. Geotechnical Investigations for Accelerated Action
 Design at the Original Landfill Phase 1 Data Review Technical
 Memorandum Rocky Flats Environmental Technology Site Original
 Landfill. Prepared by Earth Tech, April.
- Metcalf and Eddy, 1995. for US DOE. Rocky Flats Environmental Technology Site Geotechnical Investigation Report for Operable Unit No. 5. RFETS Draft September.

49